



EUSTON TOWER

Transport Assessment

December 2023



EUSTON TOWER, REGENT'S PLACE

TRANSPORT ASSESSMENT

PROJECT NO. 22/181 DOC NO. D002

DATE: DECEMBER 2023

VERSION: 1.0

CLIENT: BRITISH LAND PROPERTY MANAGEMENT LIMITED

Velocity Transport Planning Ltd

www.velocity-tp.com



VELOCITY
Transport Planning

DOCUMENT CONTROL SHEET

Document Reference

Project Title	Euston Tower, Regent's Place
Document Title	Transport Assessment
Project Number	22/181
Document Number	D002
Revision No.	1.0
Document Date	DECEMBER 2023

Document Review

	Name	Date completed
Prepared By	EN	December 2023
Reviewed By	MP	
Authorised By	TM	

Notes

The document reference number, revision number and date are given on the footer of each page
© Velocity Transport Planning Ltd
Extracts may be reproduced provided that the source is acknowledged



TABLE OF CONTENTS

1	INTRODUCTION	8
2	STRATEGIC POLICY DELIVERY	16
3	TRANSPORT PLANNING FOR PEOPLE	25
4	SITE & SURROUNDINGS	27
5	ACTIVE TRAVEL.....	52
6	LONDON-WIDE NETWORK.....	78
7	TRAVEL DEMAND AND NETWORK IMPACT	87
8	OUTLINE CONSTRUCTION LOGISTICS PLAN	121
9	SUMMARY AND CONCLUSIONS	160

FIGURES

FIGURE 1-1: SITE LOCATION AND LOCAL CONTEXT	9
FIGURE 1-2: REGENTS PLACE	10
FIGURE 1-3: EXISTING GROUND FLOOR LAYOUT	11
FIGURE 1-4: PROPOSED DEVELOPMENT – GROUND FLOOR PLAN	13
FIGURE 3-1: INBOUND/OUTBOUND TRIPS BY START TIME (WEEKDAY) EMPLOYEES	26
FIGURE 4-1: EXISTING NETWORK AND SITE ACCESS.....	27
FIGURE 4-2: LONGFORD STREET SERVICING ACCESS AND RAMP.....	28
FIGURE 4-3: DRUMMOND STREET CAR AND CYCLE ACCESS AND RAMP.....	28
FIGURE 4-4: PROPOSED ACCESS POINTS	29
FIGURE 4-5: EXISTING PUBLIC REALM	29
FIGURE 4-6: EXISTING FOOTWAY WIDTHS	30
FIGURE 4-7: PROPOSED LANDSCAPING AND PUBLIC REALM	31
FIGURE 4-8: PROPOSED FOOTWAY WIDTHS.....	33
FIGURE 4-9: EXISTING REGENTS PLACE BASEMENT AREA	34
FIGURE 4-10: EXISTING SERVICE AREA - SWEEPED PATH ANALYSIS	35
FIGURE 4-11: REVISED BASEMENT SERVICE AREA.....	36
FIGURE 4-12: ACCESS STRATEGY FOR LARGER CARGO BIKES.....	36
FIGURE 4-13: ACCESS STRATEGY FOR STANDARD CARGO BIKES.....	37
FIGURE 4-14: SPECIALIST GAS DELIVERIES.....	38
FIGURE 4-15: EXISTING CYCLE PARKING	39



FIGURE 4-16: REGENTS PLACE PUBLIC REALM CYCLE PARKING	40
FIGURE 4-17: LOCAL AREA CYCLE PARKING	40
FIGURE 4-18: CGI IMAGE OF THE PROPOSED GROUND LEVEL CYCLE ACCESS	41
FIGURE 4-19: GROUND LEVEL CYCLE ACCESS	42
FIGURE 4-20: PROPOSED CYCLE PARKING LAYOUT – BASEMENT	43
FIGURE 4-21: PROPOSED SHORT-STAY CYCLE PARKING	45
FIGURE 4-22: PROPOSED BLUE BADGE AND EXISTING SANTANDER CAR PARKING	46
FIGURE 4-23: EXISTING PEDESTRIAN FLOWS.....	47
FIGURE 4-24: FUTURE PEDESTRIAN FLOWS – AM PEAK.....	49
FIGURE 4-25: FUTURE PEDESTRIAN FLOWS – PM PEAK	49
FIGURE 4-26: PROPOSED OVERSAILING.....	51
FIGURE 5-1: EXISTING SITE ACCESSIBILITY AND FACILITIES	52
FIGURE 5-2: WALKING ISOCHRONE PLAN.....	53
FIGURE 5-3: LOCAL CYCLE NETWORK	54
FIGURE 5-4: CYCLING CATCHMENT	55
FIGURE 5-5: MAP ONE - ACTIVE TRAVEL ZONE MAP	57
FIGURE 5-6: NEIGHBOURHOOD ZONE MAP 2	58
FIGURE 5-7: PERSONAL INJURY ACCIDENT MAP.....	59
FIGURE 5-8: HEALTHY NEIGHBOURHOOD CHARACTERISTICS	63
FIGURE 5-9: KEY ROUTE 1 WORST POINT	65
FIGURE 5-10: KEY JOURNEY 2 WORST POINT	67
FIGURE 5-11: KEY JOURNEY 3 WORST POINT	69
FIGURE 5-12: KEY JOURNEY 4 WORST POINT	71
FIGURE 5-13: KEY JOURNEY 4B WORST POINT	73
FIGURE 5-14: KEY JOURNEY 5 WORST POINT	75
FIGURE 6-1: SITE PTAL MAP	78
FIGURE 6-2: LOCAL BUS ROUTES	79
FIGURE 6-3: UNDERGROUND AND RAIL NETWORKS WITHIN PROXIMITY OF THE SITE	80
FIGURE 6-4: UNDERGROUND SERVICES AND FREQUENCIES	81
FIGURE 6-5: TIM MAPPING	83
FIGURE 6-6: LOCAL ROAD NETWORK.....	84
FIGURE 7-1: DELIVERY AND SERVICING TRIPS – DAILY PROFILE	94
FIGURE 7-2: BUS ROUTES.....	99
FIGURE 7-3: WARREN STREET STATION HOURLY FLOWS	106
FIGURE 7-4: WARREN STREET STATION - ENTRY, EXIT AND INTERCHANGE FLOWS	107
FIGURE 7-5: WARREN STREET – 2019 VS 2022 FLOWS.....	107
FIGURE 7-6: ELIZABETH LINE IMPACT	108



FIGURE 7-7: EXISTING CYCLE HIRE LOCATIONS.....	113
FIGURE 7-8: HAMPSTEAD ROAD DOCKING STATION – DAILY USAGE.....	114
FIGURE 7-9: WARREN STREET DOCKING STATION – DAILY USAGE	115
FIGURE 7-10: DAILY PROFILE AND ACCUMULATION – HAMPSTEAD ROAD	115
FIGURE 7-11: DAILY PROFILE AND ACCUMULATION – WARREN STREET	116
FIGURE 7-12: TFL CYCLE HIRE USAGE	117
FIGURE 7-13: EXTRACT FROM FUTURE OF TEMP – HAMPSTEAD ROAD	118
FIGURE 7-14: TFL HAMPSTEAD ROAD – PROPOSED GREENING SCHEME	119
FIGURE 8-1: SITE LOCATION WITHIN A REGIONAL CONTEXT	122
FIGURE 8-2: SITE LOCATED IN THE CONTEXT OF THE LOCAL TRANSPORT NETWORK.....	123
FIGURE 8-3: PLANNING APPLICATION BOUNDARY PLAN (GROUND FLOOR)	123
FIGURE 8-4: INDICATIVE CONSTRUCTION PROGRAMME	125
FIGURE 8-5: REGIONAL ROUTING PLAN.....	128
FIGURE 8-6: PROPOSED CONSTRUCTION VEHICLE ROUTES	129
FIGURE 8-7: HAMPSTEAD ROAD BUS STOP	130
FIGURE 8-8: EUSTON ROAD OFF-SLIP BUS STOP.....	131
FIGURE 8-9: INDICATIVE ESTATE WIDE LOADING PLAN	131
FIGURE 8-10: EXISTING SITE CONSTRAINTS.....	132
FIGURE 8-11: CONSTRUCTION LOGISTICS STRATEGY – OPTION A – PHASE 0	133
FIGURE 8-12: CONSTRUCTION LOGISTICS STRATEGY – OPTION A – PHASE 1	133
FIGURE 8-13: CONSTRUCTION LOGISTICS STRATEGY – OPTION A – PHASE 2	134
FIGURE 8-14: CONSTRUCTION LOGISTICS STRATEGY – OPTION A – PHASE 3	134
FIGURE 8-15: CONSTRUCTION LOGISTICS STRATEGY – OPTION B – PHASE 1	136
FIGURE 8-16: CONSTRUCTION LOGISTICS STRATEGY – OPTION B – PHASE 2	136
FIGURE 8-17: CONSTRUCTION LOGISTICS STRATEGY – OPTION B – PHASE 3	137
FIGURE 8-18: CONSTRUCTION LOGISTICS STRATEGY – OPTION C – PHASE 1	138
FIGURE 8-19: CONSTRUCTION LOGISTICS STRATEGY – OPTION C – PHASE 2	138
FIGURE 8-20: CONSTRUCTION LOGISTICS STRATEGY – OPTION C – PHASE 3	139
FIGURE 8-21: CONSTRUCTION LOGISTICS STRATEGY – OPTION D – PHASE 1	140
FIGURE 8-22: CONSTRUCTION LOGISTICS STRATEGY – OPTION D – PHASE 2	140
FIGURE 8-23: CONSTRUCTION LOGISTICS STRATEGY – OPTION D – PHASE 3	141
FIGURE 8-24: PROPOSED HAMPSTEAD ROAD BUS STOP RELOCATION	145
FIGURE 8-25: PROPOSED SITE LAYOUT AND VEHICLE ACCESS	146
FIGURE 8-26: CONSTRUCTION VEHICLE ACCESS – PHASE 1	147
FIGURE 8-27: CONSTRUCTION VEHICLE ACCESS – PHASE 2	147
FIGURE 8-28: CONSTRUCTION VEHICLE ACCESS – PHASE 3	148
FIGURE 8-29: ESTIMATED CONSTRUCTION VEHICLES	152



FIGURE 8-30: TFL CLP TOOL GRAPHS	153
FIGURE 8-31: INDICATIVE CONSTRUCTION LOGISTICS STRATEGY	154
FIGURE 8-32: CONSTRUCTION VEHICLE DISTRIBUTION – PHASE 1	155
FIGURE 8-33: CONSTRUCTION VEHICLE DISTRIBUTION – PHASE 2	156
FIGURE 8-34: CONSTRUCTION VEHICLE DISTRIBUTION – PHASE 3	157

TABLES

TABLE 1-1: PROPOSED DEVELOPMENT ACCOMMODATION SCHEDULE.....	12
TABLE 2-1: LONDON PLAN – DEVELOPMENT COMPLIANCE	19
TABLE 4-1: HEALTHY STREETS INDICATORS COMPLIANCE	32
TABLE 4-2: PROPOSED LONG STAY CYCLE PARKING PROVISION	42
TABLE 4-3: PROPOSED SHORT-STAY CYCLE PARKING PROVISION	44
TABLE 4-4: PEDESTRIAN COMFORT ANALYSIS – EXISTING PEDESTRIAN CONDITIONS.....	48
TABLE 4-5: PEDESTRIAN COMFORT ANALYSIS – PROPOSED PEDESTRIAN CONDITIONS.....	50
TABLE 5-1: ATZ KEY DESTINATIONS PRIORITISATION	57
TABLE 5-2: PERSONAL INJURY DATA.....	60
TABLE 5-3: KEY JOURNEY ONE HEALTHY STREETS ASSESSMENT.....	66
TABLE 5-4: KEY JOURNEY TWO HEALTHY STREETS ASSESSMENT	68
TABLE 5-5: KEY JOURNEY THREE HEALTHY STREETS ASSESSMENT.....	70
TABLE 5-6: KEY JOURNEY FOUR HEALTHY STREETS ASSESSMENT.....	72
TABLE 5-7: KEY JOURNEY FOUR B HEALTHY STREETS ASSESSMENT.....	74
TABLE 5-8: KEY JOURNEY FIVE HEALTHY STREETS ASSESSMENT	76
TABLE 6-1: LOCAL BUS STOP SUMMARY AND FREQUENCY.....	79
TABLE 7-1: EXISTING PERMITTED USE - TOTAL PERSON TRIP RATES AND TRIPS.....	87
TABLE 7-2: MODE SHARE – EXISTING PERMITTED DEVELOPMENT	88
TABLE 7-3: EXISTING PERMITTED USE TRIPS BY MODE	88
TABLE 7-4: REVISED MODE SHARE – PROPOSED DEVELOPMENT	89
TABLE 7-5: PROPOSED DEVELOPMENT – OFFICE - TOTAL PERSON TRIP RATES AND TRIPS (56,250 SQM)	89
TABLE 7-6: PROPOSED DEVELOPMENT – LIFE SCIENCE - TOTAL PERSON TRIP RATES AND TRIPS (24,380 SQM)	90
TABLE 7-7: PROPOSED DEVELOPMENT – OFFICE AND LIFE SCIENCE TRIPS BY MODE	91
TABLE 7-8: RETAIL EMPLOYEE PEAK HOUR – TOTAL TRIPS.....	92
TABLE 7-9: FORECAST RETAIL EMPLOYEE PEAK HOUR TRIPS BY MODE	92
TABLE 7-10: PUBLIC USE EMPLOYEE PEAK HOUR – TOTAL TRIPS.....	92



TABLE 7-11: PUBLIC USE - LEARNING CENTRE VISITOR PEAK HOUR - TOTAL TRIPS	93
TABLE 7-12: FORECAST PUBLIC USE – LEARNING CENTRE PEAK HOUR TRIPS.....	93
TABLE 7-13: FORECAST PUBLIC USE – LEARNING CENTRE (EMPLOYEES & VISITORS) PEAK HOUR TRIPS BY MODE	93
TABLE 7-14: DAILY SERVICING VEHICLES	94
TABLE 7-15: TOTAL DEVELOPMENT TRIPS BY MODE.....	95
TABLE 7-16: COMPARISON OF PERMITTED USE WITH THE PROPOSED DEVELOPMENT AM PEAK HOUR	95
TABLE 7-17: COMPARISON OF PERMITTED USE WITH THE PROPOSED DEVELOPMENT PM PEAK HOUR	95
TABLE 7-18: SENSITIVITY TEST – MAX OFFICE - TOTAL PERSON TRIP RATES AND TRIPS (80,630 SQM)	96
TABLE 7-19: SENSITIVITY TEST – MAXIMUM OFFICE TRIPS BY MODE	96
TABLE 7-20: SENSITIVITY TEST - MAX OFFICE - TOTAL DEVELOPMENT TRIPS BY MODE	97
TABLE 7-21: DAILY SERVICING VEHICLES	97
TABLE 7-22: TRIP DISTRIBUTION BY MODE AND LOCATION FOR TRAVEL TO CAMDEN.....	98
TABLE 7-23: ADDITIONAL BUS PASSENGERS PER SERVICE – PROPOSED DEVELOPMENT	100
TABLE 7-24: PROPOSED DEVELOPMENT - RAIL TRIPS – BY STATION.....	102
TABLE 7-25: PROPOSED DEVELOPMENT - RAIL TRIPS – ONWARD JOURNEY BY MODE	103
TABLE 7-26: PROPOSED DEVELOPMENT - UNDERGROUND TRIPS BY LINE AND STATION	104
TABLE 7-27; PROPOSED DEVELOPMENT - RAIL AND UNDERGROUND TRIPS BY LU STATION	104
TABLE 7-28: SENSITIVITY TEST – MAX OFFICE - UNDERGROUND TRIPS BY LINE AND STATION	105
TABLE 7-29; SENSITIVITY TEST – MAX OFFICE - RAIL AND UNDERGROUND TRIPS BY LU STATION	105
TABLE 7-30: GATE LINE ASSESSMENT – 2022 EXISTING STATION FLOWS	109
TABLE 7-31: GATE LINE ASSESSMENT – 2022 EXISTING STATION FLOWS PLUS PROPOSED DEVELOPMENT.....	110
TABLE 7-32: GATE LINE ASSESSMENT – 2022 EXISTING STATION FLOWS PLUS MAX OFFICE FLOWS.....	111
TABLE 7-33: WARREN STREET STATION – ESCALATOR ASSESSMENT.....	112
TABLE 8-1: INDICATIVE SEQUENCE OF WORKS AND ESTIMATED DURATION	124
TABLE 8-2: IMPACT STUDY – OPTION A.....	142
TABLE 8-3: IMPACT STUDY – OPTION B	142
TABLE 8-4: IMPACT STUDY – OPTION C	143
TABLE 8-5: IMPACT STUDY – OPTION D.....	143
TABLE 8-6: PEDESTRIAN COMFORT ANALYSIS - PEDESTRIAN CONDITIONS DURING THE CONSTRUCTION PERIOD	149
TABLE 8-7: CONSTRUCTION PLANNED MEASURES.....	150



TABLE 8-8: ESTIMATED CONSTRUCTION VEHICLES – MONTHLY AND DAILY	152
TABLE 9-1: HEALTHY STREETS TRANSPORT ASSESSMENT CONCLUSIONS	162

APPENDICES

APPENDIX A	PROPOSED DEVELOPMENT PLANS
APPENDIX B	SWEPT PATH ANALYSIS
APPENDIX C	DRAFT DELIVERY AND SERVICING PLAN
APPENDIX D	OUTLINE TRAVEL PLAN
APPENDIX E	CAR PARKING DESIGN AND MANAGEMENT PLAN
APPENDIX F	ACTIVE TRAVEL ZONE MAPS AND PHOTO LOCATIONS
APPENDIX G	CONSTRUCTION PROGRAMME
APPENDIX H	CONSTRUCTION LOGISTIC STRATEGY OPTIONS
APPENDIX I	CONSTRUCTION LOGISTIC STRATEGY OPTIONS – IMPACT ASSESSMENT
APPENDIX J	HAMPSTEAD ROAD – TEMPORARY BUS STOP RELOCATION



1 INTRODUCTION

1.1 APPOINTMENT

1.1.1 Velocity Transport Planning has been commissioned by British Land Property Management Limited (Thereafter British Land, or the 'Applicant') to prepare a Healthy Streets Transport Assessment (TA) in relation to the proposed development at Euston Tower, which forms part of Regent's Place, situated within the London Borough of Camden (LBC).

1.1.2 This TA is supported by the following documents:

- Outline Travel Plan (TP);
- Draft Delivery and Servicing Plan (DSP);
- Car Parking Design and Management Plan (CPDMP);
- Outline Construction Logistics Plan (CLP)) included as part of this document; and
- Draft Construction Management Plan Camden Proforma (CMP).

1.2 SITE LOCATION

1.2.1 Euston Tower is situated within the London Borough of Camden ('LBC') and the ward of Regent's Park. The Site is bounded by Euston Road (south), Hampstead Road (east), Brock Street (north) and Regent's Place (west). The Site covers an area of 8,079 sqm, comprised of a single ground plus an existing 36-storey tower. The tower has been largely vacant for several years, predominantly comprising office uses on the upper floors; however, there are still retail uses currently in operation at the ground floor level. The Site does not fall within a conservation area; however, Fitzroy Square CA, and Bloomsbury CA are both located in close proximity (south). There are no elements of the Site that are statutory or locally listed. A Certificate of Immunity from listing has been submitted and, at the time of submission, is still pending in respect of the existing tower. There are several buildings located within a close radius of the Site that are Grade I, Grade II and Grade II* listed.

1.2.2 The Site has a PTAL rating of 6b, indicating 'excellent' transport connectivity. The Site is easily accessed by Warren Street Underground Station (south), Euston Square Underground Station (east) and Great Portland Street Underground Station (west). There are also several bus routes which route along Euston Road (south) and Hampstead Road (east).

1.2.3 The land surrounding the Site consists of a range of uses. The Site is designated within the Knowledge Quarter Innovation District ('KQID'), home to world-class clusters of scientific and knowledge-based institutions and companies specialising in life sciences, data and technology and creative industries. The neighbouring Regent's Place comprises commercial, office and cultural land uses, as well as pedestrianised streets and public realm incorporated into the space. The closest residential properties are located along Drummond Street (north) and Hampstead Road (east).

1.2.4 On a London-wide scale, Regent's Place sits within Central London in the London Borough of Camden, approximately 1.5km to the west of Kings Cross and 0.5km to the east of Regent's Park.



1.2.5 **Figure 1-1** shows the location of the site and the surrounding transport network within circa 800m.


Figure 1-1: Site location and local context



1.2.6 Euston Tower is situated at the southwestern corner of the Regent's Place Estate and is bounded by Brock Street to the north and Regent's Place Plaza to the west, which are both pedestrianised. To the east is Hampstead Road, and to the south is the A501 Euston Road.

1.2.7 **Figure 1-2** shows Euston Tower in the context of Regent's Place.

Figure 1-2: Regents Place




1.3 EXISTING SITE

1.3.1 Euston Tower is a 36-storey tall building on the northern edge of Central London, situated in the south-west of the London Borough of Camden. It provides office floor space with ancillary retail at ground level. The existing ground floor plan is shown in **Figure 1-3**.



Figure 1-3: Existing Ground floor layout



- 1.3.2 The Tower is located immediately northwest of a busy junction forming the intersection of Euston Road and Hampstead Road. The UCL Hospital Campus also affronts the junction. Warren Street Station is located at the southwest of the junction.
- 1.3.3 Euston Tower has a prominent presence, given its status as the tallest building in the borough aside from the nearby BT Tower, and as such acts as a physical landmark for London Euston, Euston Square and Warren Street stations as well as wayfinding for the wider neighbourhood.
- 1.3.4 Completed in 1970, Euston Tower was designed in the 'International Style'. Above a two-storey extruded glazed podium, the tower has a pinwheel plan clad in aluminium curtain walling with green reflective tinted glazing. It was designed as an office building to provide cellular office accommodation typical of the period and formed part of a wider masterplan known as The Euston Centre. It now stands on the eastern edge of the pedestrianised Regent's Place Estate.
- 1.3.5 Since its completion, it has undergone a small refurbishment, but beyond this, its external form and façade remain as originally constructed. These elements of the building are in a generally poor condition due to a combination of wear in use and the quality of the original detailing. Gradually, it has been vacated, and since 2021, with the exception of the retail at grade level, the building has been entirely disused.

1.4 PLANNING HISTORY

- 1.4.1 There is no planning history relevant to this assessment within the latest 10-year period.



1.5 PROPOSED DEVELOPMENT

1.5.1 This Transport Assessment has been prepared in support of an application at Euston Tower, 286 Euston Road, London, NW1 3DP.

1.5.2 Full Planning Permission is sought for the following:

Redevelopment of Euston Tower, including the partial retention (retention of existing core, foundations and basement), disassembly, reuse and extension of the existing building, to provide a 32-storey building for use as offices and research and development floorspace (Class E(g)) and office, retail, café and restaurant space (Class E) and learning and community space (Class F) at ground, first and second floors, and associated external terraces. Provision of public realm enhancements, including new landscaping, and provision of new publicly accessible steps and ramp. Provision of short and long-stay cycle storage, servicing, refuse storage, plant and other ancillary and associated works.

1.5.3 This is referred to throughout as the “Proposed Development”.

1.5.4 The Proposed Development’s new land uses and areas are summarised in **Table 1-1**.

Table 1-1: Proposed Development Accommodation Schedule


LAND USE	FLOOR LEVEL	NIA (SQM)	GIA (SQM)	GEA (SQM)
Office (Class E(g))	Level 12 – Level 31	31,575	52,160	56,250
Life Science (Class E(g))	Level 03 – Level 11	16,487	22,631	24,380
Commercial, Business & Service Use (Class E (flexible retail))	Ground – Level 01	717	748	775
Learning (Class F1)	Ground – Level 02	1,960	2,003	2,137
Total		50,739	77,542	83,541

1.5.0 The ground floor plan is illustrated in **Figure 1-4**. The Proposed Development maximises active frontage with public access on Hampstead Road and office and lab space access from Euston Road. Significant improvements to the public realm are proposed to provide a high-quality environment for the Proposed Development.

1.5.1 The Proposed Development Plan are included in **APPENDIX A**.



Figure 1-4: Proposed Development – Ground Floor Plan



1.6 WHY IS THE DEVELOPMENT PROPOSED?

1.6.1

Euston Tower is the oldest building in Regent's Place and (save for the retail floorspace at ground level) has been vacant since 2021. British Land's vision is to create a world-leading science, technology and innovation building and public realm for Camden and the Knowledge Quarter that inspires, connects and creates opportunities for local people and businesses. This will be achieved by:

- Transforming the disused Euston Tower, ensuring it is fit for the future by adopting cutting-edge sustainability targets and reusing, recycling, and offsetting where necessary to reach net zero at completion and in operation.
- Putting social impact at the heart of the project from the start and ensuring that communities play a key role in shaping new spaces which meet local needs.
- Creating pioneering workspaces in the Knowledge Quarter for businesses of all sizes to prosper, including flexible incubator and accelerator spaces, to support start-ups and knowledge sharing.
- Ensuring that the future use of Euston Tower is built upon identified needs and contributes to a thriving local, regional and national economy for our ever-changing world.
- Reimagining the public spaces of Regent's Place, creating safe, inclusive, connected and sustainable spaces for Camden's communities.



1.7 WHEN IS THE DEVELOPMENT PROPOSED?

- 1.7.1 The duration of the construction of the Euston Tower is expected to be five years, with works aimed to be completed by 2030.
- 1.7.2 A construction programme has been developed, and an Outline Construction Logistics Plan (CLP) is contained in **Section 8** of this report.

1.8 TRANSPORT DESIGN AND PLANNING PROCESS

- 1.8.1 This Transport Assessment (TA) has been prepared in accordance with the requirements outlined in National Planning Practice Guidance and TfL's Transport Assessment guidance and is also supported by an Outline Travel Plan (TP), Draft Delivery & Servicing Plan (DSP), Car Parking Design and Management Plan (CPDMP), Draft Construction Management Plan Camden Proforma (CMP) and an Outline Construction Logistics Plan (CLP).
- 1.8.2 The TA has been prepared based on the Healthy Streets and Vision Zero approaches. An Active Travel Zone (ATZ) Assessment has been undertaken, which identifies and assesses key walking and cycling routes in relation to Healthy Streets criteria.

HEALTHY STREETS

- 1.8.3 The development will provide a high-quality environment with enhanced space for walking and cycling.
- 1.8.4 This TA has been prepared in accordance with TfL's Healthy Streets TA Guidance, including an Active Travel Zone (ATZ) assessment of routes to key active travel destinations in the local area within **Section 5** of this TA.

VISION ZERO

- 1.8.5 The Proposed Development will contribute towards a mode shift away from private vehicles due to its car-free nature and provision of cycle facilities within the site that meet London Plan requirements. Furthermore, public realm improvements are proposed, which will help to reduce motor vehicle dominance and encourage walking and cycling, in turn improving road safety for vulnerable road users.
- 1.8.6 The ATZ assessment includes analysis of Killed or Serious Injury (KSI) collisions along routes to key active travel destinations and suggests changes to make these areas safer using the Healthy Streets Approach.
- 1.8.7 The project team has collaborated to create a scheme that prioritises safe, active and sustainable travel. Various factors and challenges have influenced the proposed transport strategy, including:
- Ensuring that the development is closely integrated with the wider Regents Place Plaza and its pedestrianised streets.
 - Making sure pedestrians experience comfortable conditions in the vicinity of the site by planning and designing for increased future pedestrian flows by improving footways and pedestrian connections.
 - A focus on delivering significant and attractive cyclist facilities, including a dedicated cyclist access ramp. Approximately half the basement demise has been dedicated to cycle parking and associated facilities.



- Publicly available ground level short-stay cycle parking will be increased within the development site.
- Ensuring sufficient space for servicing activity is provided in the basement that is clear of the building's various structural elements.
- Accommodating emergency and life science delivery vehicles (which cannot use the basement delivery and servicing routes) in a designated area of the public realm, with the public realm and landscaping designed to facilitate this.
- Re-using the existing basement and not undertaking significant excavation meaning that the existing basement demise has been extended as far as possible to accommodate back of house and cyclist facilities.
- Using existing vehicle access provisions rather than adding new accesses.

1.8.8 The Proposed Development meets the criteria of a large-scale development referable to the Mayor of London, Greater London Authority (GLA) and therefore Transport for London (TfL).

1.8.9 Significant pre-application consultation has been undertaken with transport/highway officers at the LBC and TfL. The transport strategy and scope of this Transport Assessment were discussed and agreed at pre-application meetings in:

- ⊙ 16th May – Pre-Application meeting with LBC;
- ⊙ 3rd July - Pre-Application Meeting 1 with TfL;
- ⊙ 7th September – Construction Logistic Strategy meeting with TfL; and
- ⊙ 25h September - Pre-Application Meeting 2 with TfL.

1.9 DOCUMENT STRUCTURE

1.9.1 The remainder of this TA is structured as follows:

- **Section 2** - assess the Proposed Development's compliance with relevant national and local transport planning policy;
- **Section 3** - considers the users of the development and their common method of travel;
- **Section 4** – outlines the existing and proposed connectivity of the site;
- **Section 5** – summarises the outcome of the Active Travel Zone assessment;
- **Section 6** – outlines the baseline London-wide network and trip generation;
- **Section 7** – outlines the Travel demand and impact of the Proposed Development;
- **Section 8** – provides details of the Outline Construction Logistics Plan; and
- **Section 9** – provides the conclusion of this Transport Assessment.



2 STRATEGIC POLICY DELIVERY

2.1 INTRODUCTION

- 2.1.1 This section sets out details of relevant transport-related policies. National and local planning policies place a focus on encouraging development that maximises the use of sustainable travel modes in areas with good public transport connectivity and reduces the need to travel by car.

2.2 NATIONAL POLICY

- National Planning Policy Framework (2023) (NPPF)
- National Planning Practice Guidance – ‘Travel Plans, Transport Assessments and Statements’ (2014) (NPPG)

2.3 LOCAL POLICY

- The London Plan (2021);
- The Mayor’s Transport Strategy (2018);
- Camden Local Plan (2017);
- Camden Planning Guidance, Transport (2021);
- Euston Area Action Plan (2015).

2.4 NATIONAL POLICY CONTEXT

NATIONAL PLANNING POLICY FRAMEWORK (2023)

- 2.4.1 The National Planning Policy Framework was revised on 5 September 2023 and sets out the government's planning policies for England and how these are expected to be applied.
- 2.4.2 This revised Framework replaces the previous National Planning Policy Framework published in March 2012, revised in July 2018 and updated in February 2019 and July 2021.
- 2.4.3 The NPPF promotes sustainable transport. It notes that transport issues should be considered at the earliest stages of development proposals.
- 2.4.4 Chapter 9 of the NPPF sets out the requirements for promoting sustainable transport, advising that significant development should be focused on locations which are or can be made sustainable by limiting the need to travel and offering a genuine choice of transport modes. The NPPF advises that planning policies should support an appropriate mix of uses across an area and within larger-scale sites to minimise the number and length of journeys needed for employment, shopping, leisure, education and other activities.
- 2.4.5 The NPPF does not set parking standards but notes in Paragraph 107 that parking policies should take into account:
- a) the accessibility of the development;*
 - b) the type, mix and use of development;*
 - c) the availability of and opportunities for public transport;*
 - d) local car ownership levels; and*



- e) *the need to ensure an adequate provision of spaces for charging plug-in and other ultra-low emission vehicles.*

2.4.6 In Paragraph 110, the NPPF sets out that when assessing applications for development, it should be ensured that:

- a) *appropriate opportunities to promote sustainable transport modes can be or have been taken up, given the type of development and its location;*
 b) *safe and suitable access to the site can be achieved for all users;*
 c) *the design of streets, parking areas, other transport elements and the content of associated standards reflects current national guidance, including the National Design Guide and the National Model Design Code; and*
 d) *any significant impacts from the development on the transport network (in terms of capacity and congestion) or on highway safety, can be cost-effectively mitigated to an acceptable degree.*

2.4.7 Paragraph 111 of the NPPF states that "Development should only be prevented or refused on highways grounds if there would be an unacceptable impact on highway safety, or the residual cumulative impacts on the road network would be severe", and in this context, Paragraph 112 states that planning applications should:

- a) *give priority first to pedestrian and cycle movements, both within the scheme and with neighbouring areas; and second so far as possible to facilitating access to high quality public transport, with layouts that maximise the catchment area for bus or other public transport services, and appropriate facilities that encourage public transport use;*
 b) *address the needs of people with disabilities and reduced mobility in relation to all modes of transport;*
 c) *create places that are safe, secure and attractive which minimise the scope for conflicts between pedestrians, cyclists and vehicles, avoid unnecessary street clutter, and respond to local character and design standards;*
 d) *allow for the efficient delivery of goods, and access by service and emergency vehicles; and*
 e) *be designed to enable charging of plug-in and other ultra-low emission vehicles in safe, accessible and convenient locations.*

2.4.8 Paragraph 113 of the NPPF requires all developments that will generate significant amounts of movement to provide a travel plan and be supported by a transport assessment so that the likely impacts of the proposal can be assessed.

2.4.9 The NPPF states in Paragraph 55 that local planning authorities should consider whether otherwise unacceptable development could be made acceptable through the use of conditions or planning obligations. Planning obligations should only be used where it is not possible to address unacceptable impacts through a planning condition

2.4.10 Paragraph 57 further states that planning obligations must only be sought where they meet all of the following tests:

- a) *Necessary to make the development acceptable in planning terms;*
 b) *Directly related to the development; and*
 c) *Fairly and reasonably related in scale and kind to the development*

2.4.11 The Proposed Development supports the NPPF through:

- Promoting sustainable transport by providing attractive pedestrian spaces, the provision of significant cycle parking provisions, and improvements to the active travel network.



- Reducing existing car parking and its associated traffic generation; and
- Not having significant adverse impacts on the transport network or highway safety.

PLANNING PRACTICE GUIDANCE (2014)

2.4.12 In March 2014, the Department for Communities and Local Government (as it was then) launched the Planning Practice Guidance (PPG) to provide web-based guidance in support of the NPPF. The PPG details the overarching principles of Transport Assessments and Travel Plans.

2.4.13 Paragraph 15 (Ref. ID: 42-015-20140306) of the PPG notes that the scope and level of detail of a TA will vary from site to site. It lists matters to be considered when setting the scope of a TA, including:

- Information about the Proposed Development, site layout and access arrangements for all modes of transport.
- Information about the neighbouring uses, amenities and character, and existing functional classification of the nearby road network.
- Data about existing public transport provision, including the provision and frequency of services and proposed public transport changes.
- A qualitative and quantitative description of the travel characteristics of the Proposed Development, including movements across all modes of transport that would result from the development and in the vicinity of the site.
- An analysis of the collision records on the public highway in the vicinity of the site access for the most recent three-year period (or a five-year period if the proposed site has been identified as within a high accident area).
- Measures to improve accessibility where these are necessary to make the development acceptable in planning terms.
- A description of parking facilities in the area and the parking strategy of the development.
- Ways of encouraging environmental sustainability by reducing the need to travel; and
- Measures to mitigate the residual impacts of development such as improvements to the public transport network, introducing walking and cycling facilities, and physical improvements to existing roads.



2.5 REGIONAL POLICY

LONDON PLAN (2021)

- 2.5.1 The London Plan 2021 is the Spatial Development Strategy for Greater London. It sets out a framework for how London will develop over the next 20-25 years and the Mayor's vision for Good Growth.
- 2.5.2 **Table 2-1** demonstrates how the Proposed Development is compliant with the relevant transport-related policies contained within the London Plan.

Table 2-1: London Plan – Development Compliance

POLICY	REQUIREMENTS	DEVELOPMENT CONTEXT
T1	<p>Development proposals should target 80% of all trips in London to be made by foot, cycle, or public transport by 2041.</p> <p>Development should make the most effective use of land, reflecting its connectivity and accessibility by existing and future public transport, walking, and cycling routes, and ensure that any impacts on London's transport networks and supporting infrastructure are mitigated.</p>	<p>The Proposed Development is designed to prioritise pedestrians and cyclists and is located in an area with a high PTAL (6b).</p> <p>The proposed development is car-free and will achieve more than 80% of travel by foot, cycle or public transport.</p>
T2	<p>Policy T2 relates to 'Healthy Streets' and seeks development that delivers patterns of land use that facilitate residents making shorter, regular trips by walking or cycling. The Healthy Streets Approach recognises the importance of promoting and facilitating active modes of travel by making developments permeable and highly connected by foot and cycle, with reduced vehicle dominance.</p>	<p>The proposed development is located in an area with significant retail and leisure destinations which can be reached by foot.</p> <p>The site is well located with respect to the local and strategic cycle network and is being designed to achieve high levels of cycling.</p>
T3	<p>Policy T3 states that development proposals should provide adequate protection for transport schemes, not remove vital transport functions, or limit their necessary expansion without suitable alternative provisions. Proposals should also support capacity, connectivity, and other improvements to the bus network, ensuring it can operate efficiently.</p>	<p>The proposed development does not impact safeguarded transport schemes and is not expected to impact the bus network, given the significant local bus service provision. Land adjacent to the development site is safeguarded as part of HS2, but the proposals do not impact on the scheme.</p>
T4 (A)	<p>Policy T4 identifies that development proposals should reflect and be integrated with current and planned transport access, capacity, and connectivity.</p>	<p>The development is being located in an area with excellent existing connectivity. The connectivity and capacity of the network have been further increased with the opening of the Elizabeth Line.</p>
T4 (B)	<p>Transport Assessments are required to assess impacts on the capacity of the transport network at the local, network-wide, and strategic level. Transport Assessments should focus on embedding the Healthy Streets Approach.</p>	<p>The transport strategy focuses on the Healthy Streets Approach.</p> <p>Impacts on the transport network at different scales have been assessed in this Transport Assessment.</p>
T4 (C)	<p>Where adverse transport impacts are identified appropriate, mitigation will be required, either through direct provision of public transport, walking and cycling facilities and highway improvements or through financial contributions.</p>	<p>At the local scale, significant improvements are being made to the public realm surrounding the building.</p> <p>No adverse impacts are identified on the transport network.</p> <p>A CIL payment is being made to the LBC, which can be used for transport improvements.</p>



POLICY	REQUIREMENTS	DEVELOPMENT CONTEXT
		Although there are no adverse transport impacts identified. Discussions are taking place with TfL over the mechanism of delivery of improvement works to the footways adjacent to the site which form part of the Transport for London Road Network. This may be via s278 or s106.
T4 (D)	In instances where there is limited ability to absorb increased travel demand through active travel modes and existing public transport capacity is insufficient with no plans for increased capacity, planning permission will be contingent on the provision of transport infrastructure.	There is significant potential for active travel at and around the site, and the proposed development will help to facilitate this. The Elizabeth Line has provided a significant increase in public transport capacity at a strategic level. Public transport and pedestrian assessments are provided in this report.
T4 (E)	The cumulative impacts of development on public transport and the road network capacity, including walking and cycling, as well as associated effects on public health, should be considered and mitigated.	Cumulative impacts and future network capacity have been taken into account and are assessed within this report.
T4 (F)	Development proposals should not increase road danger.	The existing vehicle access points to the basement are retained, which are located to the north of the Proposed Development and away from the main pedestrian desire lines.
T5	Policy T5 sets out that development should encourage cycling and provide minimum cycle parking standards. Cycle parking and cycle parking areas should allow easy access and provide facilities for disabled cyclists. In places of employment, supporting facilities are recommended.	Significant cycle parking is proposed with dedicated spaces and facilities for disabled cyclists. Supporting facilities for employees will be provided.
T6	Car-free development should be the starting point for all development proposals in places that are (or are planned to be) well-connected by public transport.	The proposed development will be car-free except for on-site accessible car parking.
T7	Development proposals should facilitate sustainable deliveries and servicing, including the provision of adequate space for servicing, storage, and deliveries off-street. Construction Logistics Plans and Delivery and Servicing Plans will be required and should be developed in accordance with Transport for London guidance and in a way which reflects the scale and complexities of developments. Developments should be designed and managed so that deliveries can be received outside of peak hours and in the evening or nighttime. Appropriate facilities are required to minimise additional freight trips arising from missed deliveries and thus facilitate efficient online retailing.	The existing servicing yard will largely be retained. All loading and unloading facilities are off-street within the basement. Eight servicing bays are provided within a shared servicing yard. The planning application is supported by a Delivery & Servicing Plan and an Operational Waste Management Strategy. This TA details the Outline Construction Logistic Plan.



THE MAYOR'S TRANSPORT STRATEGY (2018)

- 2.5.3 The Mayor's Transport Strategy (MTS) was published in March 2018 and sets out the Mayor's policies and proposals to reshape transport in London over the next 25 years. The central aim of the MTS is for 80% of all trips in London to be made on foot, by cycle or using public transport by 2041.
- 2.5.4 Three key themes are at the heart of the strategy:
- Healthy Streets and Healthy People;
 - A good public transport experience; and
 - New homes and jobs.
- 2.5.5 The MTS sets out Good Growth principles for the delivery of new homes and jobs that use transport to:
- Create high-density, mixed-use places; and
 - Unlock growth potential in underdeveloped parts of the city.
- 2.5.6 A supplementary proposed was added in November 2022, which reviewed the triple challenges of toxic air pollution, the climate emergency and traffic congestion.

2.6 LOCAL POLICY

CAMDEN LOCAL PLAN (2017)

- 2.6.1 The Camden Local Plan is the key strategic document in Camden's development plan and sets out the vision for shaping the future of the Borough, containing policies for guiding planning decisions.
- 2.6.2 The Local Plan was adopted in July 2017 and replaced the Core Strategy and Camden Development Policies documents. It is now the basis for planning decisions and future development in Camden. The Local Plan will ensure that:
- “Camden continues to have robust, effective and up-to-date planning policies that respond to changing circumstances and the borough's unique characteristics and contribute to delivering the Camden Plan and other local priorities. The Local Plan will cover the period from 2016-2031.”*
- 2.6.3 Section 10 of the Local Plan is focused on Transport and identifies four key policies that the Council will seek to promote:
- ⊙ Policy T1 states that the Council will promote sustainable transport by prioritising walking, cycling and public transport in the borough.
 - ⊙ Policy T2 confirms the Council's commitment to limit the availability of parking and will require all new developments in the borough to be car-free.
 - ⊙ The Council will seek improvements to the borough under Policy T3 of the Local Plan.
 - ⊙ Policy T4 of the Local Plan promotes the sustainable movement of goods and materials and seeks to minimise the movement of goods and materials by road.



CAMDEN PLANNING GUIDANCE, TRANSPORT (2021)

- 2.6.4 The Camden Planning Guidance (CPG) on Transport has been prepared to support the policies in the Camden Local Plan 2017. It forms a Supplementary Planning Document (SPD) requiring consideration in planning decisions.
- 2.6.5 The CPG on Transport was adopted in January 2021, replacing the Transport CPG of March 2019 and supports the following Local Plan policies:
- ⊙ Policy A1 Managing the impact of development;
 - ⊙ Policy T1 Prioritising walking, cycling and public transport;
 - ⊙ Policy T2 Parking and car-free development;
 - ⊙ Policy T3 Transport infrastructure;
 - ⊙ Policy T4 Sustainable movement of goods and materials;
 - ⊙ Policy CC4 Air quality; and
 - ⊙ Policy D1 Design.
- 2.6.6 The CPG sets out the requirements for Transport Assessments and identifies the following supporting information to be included:
- ⊙ Travel Plan Framework;
 - ⊙ Draft Car Parking Management and Reduction Plan;
 - ⊙ Draft Delivery and Servicing Plan; and
 - ⊙ Draft Construction Management Plan.
- 2.6.7 The document provides guidance on transport issues within the borough and sets out a list of 'key messages' within each section, providing further guidance on how these items should be addressed within a Transport Assessment as part of a planning application:
- ⊙ Assessing transport impact - a Transport Assessment, Statement or Note is required for all applications that involve a change in the way that a site is accessed from the highway. These documents must clearly demonstrate what measures will be required in order to mitigate the transport impact of the development.
 - ⊙ Travel Plans - Travel Plans enable a development to proceed without adverse impact on the transport network through promoting a greater use of sustainable travel and thereby helping to tackle congestion and air pollution. The requirements of a travel plan will be tailored to the specific characteristics of the site and nature of the development.
 - ⊙ Delivery and Servicing Plans - The need for a Delivery and Servicing Plan (DSP) should be identified in the Transport Assessment. A framework/draft DSP will form part of the Transport Assessment; the DSP itself will form part of the Travel Plan or be a standalone document, secured as a Section 106 planning obligation. The use of the term 'Delivery and Service Plan' is interchangeable with the term 'Delivery and Servicing Management Plan'.



- ⊙ Parking and car-free development - The Camden Local Plan 2017 extends car-free development to the whole of the Borough. Legal agreements will be used to maintain car-free and car-capped development over the lifetime of a scheme.
- ⊙ Car Parking Management and Reduction - Developments with associated car parking will be required to submit a Car Parking Management and Reduction Plan. Applicants must demonstrate how parking will be managed, monitored and enforced, and provide details as to how the car parking can be repurposed in the future.
- ⊙ Cycling Facilities - The Council will seek high-quality cycle parking facilities for development, including redevelopments and in applications that change travel patterns and the travel profile or increase the numbers of people travelling to a site. Applicants must provide, as a minimum, the quantity of cycle parking spaces as set out in the London Plan; and Applicants will provide cycling facilities that are fully inclusive and accessible by step-free access.
- ⊙ Pedestrian and Cycle Movement - All developments must have due regard to the safety, ease of movement and the quality of pedestrian and cycle facilities for people moving to and within a site.

EUSTON AREA PLAN (2015)

2.6.8 The Euston Area Plan (EAP) and the Growth Strategy for Euston are intended to help to shape change and guide development up to 2031. Work on an update to the EAP is currently paused due to the uncertainty following the Government decision to pause most works associated with HS2 at Euston.

2.6.9 Strategic Principle EAP 3: Transport sets out:

- ⊙ The Euston Station redevelopment will provide a world class station and transport interchange. Transport for London and the London Borough of Camden will work with partners to mitigate the impacts of increased passenger numbers (including those resulting from HS2) and general activity in and around Euston, and support growth and development generally in the Euston area by:
 - providing for the effective onward distribution of passengers;
 - promoting sustainable travel;
 - improving accessibility and the local environment; and
 - providing new east-west links across the station and tracks site.
- ⊙ Key transport measures to mitigate HS2 and support growth and development generally in the area include:
 - Measures to promote walking and cycling, including new routes and facilities, enhanced signage and significant public realm improvements, in order to reduce pressure on the public transport network
 - Enhancements to public transport infrastructure, including:
 - ◆ The delivery of Crossrail 2
 - ◆ Significant enhancements to ticket hall and platform access for London Underground services
 - ◆ Improvements to bus facilities



- Car free development
 - Appropriate taxi and private hire provisions to meet the needs of station users
 - Sustainable freight modes and minimising the impacts of freight
 - Measures to support the introduction of an Ultra Low Emissions Zone (ULEZ) at Euston (see Strategic Principle EAP 4)
- ⊙ Where appropriate, developments will be required to contribute towards the measures set out above, in addition to that provided by HS2



3 TRANSPORT PLANNING FOR PEOPLE

3.1 INTRODUCTION

3.1.1 This section summarises who the development will be for, when and why they will travel. TfL's London Travel Demand Survey data has been used and is presented in this section.

3.2 WHO THE DEVELOPMENT IS FOR?

3.2.1 The Proposed Development will be for:

- Employees working in the new building, primarily office and life science workers.
- Visitors to the offices, laboratories, learning facility, community and public spaces including ancillary retail.
- People travelling past and through the development or accessing the new public realm.

3.3 WHEN AND WHY WILL THEY TRAVEL?

3.3.1 Data from the 'London Travel Demand Survey' (LTDS) has been analysed to indicate when prospective employees may travel.


3.3.2 Each year, TfL undertake the LTDS of 8,000 randomly selected London households through three questionnaires to identify their travel habits including trip purposes, modes used, trip start and end times and trip origins and destinations.

EMPLOYEES

3.3.3 A daily profile of journeys being made to and from their 'usual workplace' or 'other work-related' locations is shown in **Figure 3-1**. The highest number of employee trips are undertaken between 8 am and 9 am (trips to work) and between 5 pm and 6 pm (trips from work). There are also higher numbers of trips at the lunchtime period between 12 noon and 2 pm.



Figure 3-1: Inbound/Outbound trips by start time (weekday) employees



VISITORS

3.3.4 There will be various visitors to the development that travel at different times of the day:

- Office and laboratory visitors will travel to and from the development throughout the working day, primarily associated with attending meetings.
- The ancillary retail customers are expected to primarily be local office employees and passers-by working or socialising nearby. The highest numbers of visitors are expected to be at lunchtime and after the working day.
- Visitors to the learning facility and community spaces will be attending seminars, workshops, classes, etc., during the working day and into the evening.



4 SITE & SURROUNDINGS

4.1 INTRODUCTION

4.1.1 This section provides information on the site's existing connectivity to the transport networks before and after development.

4.1.2 Planning guidance highlights the importance of integrating land use, transport, and planning decisions. In order to achieve good integration and maximise growth, high-density development should be encouraged in areas with excellent levels of accessibility to public transport.


4.2 ACCESS

EXISTING

4.2.1 The local transport network and existing accesses are shown in **Figure 4-1**.

4.2.2 A number of pedestrian accesses are provided at the existing Euton Tower building, which is accessed from the south on Euston Road. There are a number of retail units at ground level, which are accessed from Hampstead Road and Regents Place Plaza.

Figure 4-1: Existing network and site access




4.2.3 There are two vehicle access points on Longford Street and Drummond Street to the north of the site. The Longford Street access is for delivery and servicing vehicles to the basement, as shown in **Figure 4-2**.

Figure 4-2: Longford Street Servicing Access and Ramp



- 4.2.4 The Drummond Street entrance provides ramped access to the basement car and cycle parking, as shown in **Figure 4-3**.

Figure 4-3: Drummond Street Car and Cycle Access and Ramp



PROPOSED

- 4.2.5 The proposed access strategy is set out in **Figure 4-4**.
- 4.2.6 Pedestrian entrances will be provided at ground level. The office and laboratory entrance are located on Euston Road to the southern side of the building. The community entrance to the public learning facility is accessed at ground level from the north and east of the site via Brock Street and Hampstead Road. The retail/restaurant uses will be located at Level 1 accessed via Regents Place Plaza or Hampstead Road.
- 4.2.7 A dedicated cycle access is proposed, which provides access to the basement via a dedicated cycle ramp or lift. The cyclist lift is sized to accommodate larger bicycle types. During office hours, access controls for cyclists will be located in the basement so that cyclists do not need to dismount. Outside of these hours access control will be provided at ground level to provide additional security.

Figure 4-4: Proposed Access Points




- 4.2.8 Vehicle access to the basement servicing areas and accessible car parking are being retained via the two existing off site vehicle ramps via Longford Street and Drummond Street.

4.3 PUBLIC REALM

EXISTING

- 4.3.1 The west and north of the Euston Tower are pedestrianised, while the streets to the east and south (i.e., Hampstead Road and Euston Road) accommodate vehicles. Regent's Place Plaza, located to the west of Euston Tower, is a large pedestrianised square.
- 4.3.2 The existing public realm around the site is shown in **Figure 4-5**.


Figure 4-5: Existing public realm



- 4.3.3 Regents Place Plaza, located to the west of the Proposed Development, is regularly used for exhibitions and events.

4.3.4 **Figure 4-6** shows the key existing footway widths and public realm surrounding the site.

Figure 4-6: Existing footway widths




- 4.3.5 The existing landscaping within Regent's Plaza is a temporary scheme by Townshend Landscape Architects. The Plaza features large, planted seating platforms and low planting. Seven trees sit at grade in suspended tree pits. A series of basement ventilation grates are concealed below the planters or adjacent.
- 4.3.6 Along Euston Road, an undulating lawn separates the square from the pedestrian footway. Further east, a fenced basement access pit is planted with a stand trees.
- 4.3.7 At the intersection of Euston and Hampstead Roads, a number of trees of various species and sizes are planted at grade with two formalized seating planters further north along Hampstead Road. Each planter contains eight trees, is densely planted and fixed with wood bench toppers to match those in the square.
- 4.3.8 Brock Street features a linear arrangement of plane trees planted in pits at grade, between which are a series of basement vents, wooden benches, and cycle stands.
- 4.3.9 There are 47 existing trees within the red line boundary.

PROPOSED

- 4.3.10 Active frontage, pedestrian-prioritised and landscaped footways and public realm will be provided as part of the proposal as shown in **Figure 4-7**.

Figure 4-7: Proposed Landscaping and Public Realm



- 4.3.11 The proposed landscape concept pulls inspiration from the natural landscape of Hampstead Heath and reimagines its mosaic of habitats within Regent's Place. A series of mounded landforms compose the majority of the Site and house a rich mix of species from four target habitats: wetland, woodland, grassland, and heathland. A central clearing meets the architectural stairs and ramp, and acts as the main event space, which can be transformed into a shallow reflecting pool during warmer months. Two sunken beds to the west could feature a wetland and riparian grassland and work to collect, attenuate, and filter rainwater from the towers blue roof. This system could double as an educational element to highlight the story of rainwater in the city.
- 4.3.12 The mounds around the site have been placed in order to maximize wind, noise, and pollution buffering, while maintaining clear routes for existing and anticipated pedestrian volumes. The mounds could double as seating elements as well as Hostile Vehicle Mitigation (HVM) where possible.
- 4.3.13 The planted areas extend past the ground plane and integrate lush vegetation and trees up the central stairs and ramp to the podium and wrap around to the level 02 terrace. Through the integrated planting and accessible routes, the concept aims to connect the public realm vertically and invite the public to interact with the internal spaces.
- 4.3.14 The introduction of a significant number of trees with varying maturities, the scheme looks to greatly increase the canopy cover of the site and ensure a succession of planting for decades to come. The use of climate resilient planting, coupled with native habitats, is used to enhance biodiversity on site and creating a meaningful, lasting greenspace in the centre of Camden.

- 4.3.15 There are 107 proposed trees within the red line boundary made up of a mix of multi-stem, deciduous and coniferous.
- 4.3.16 No stopping up of the public highway is required to implement the Proposed Development.
- 4.3.17 The landscaping proposals have been designed to accommodate vehicle access to the development for the delivery of specialist gases associated with the proposed life science uses.

HEALTHY STREETS CRITERIA

- 4.3.18 **Table 4-1** demonstrates how the Healthy Streets Approach has informed the public realm design. The site has two types of character areas:

- Brock Street and Regents Place Plaza are pedestrianised; and
- Euston Road and Hampstead Road which accommodate vehicular traffic.

Table 4-1: Healthy Streets Indicators Compliance

Healthy Streets Indicators	Before - Existing Site	After – Proposed Development
Pedestrians from all walks of life	Brock Street and Regent's Place Plaza are pedestrianised and provide an attractive walking environment for all. Euston Road and Hampstead Road have pedestrian footways on each side of the road.	The pedestrianised area of Regent's Place Plaza will be improved and deliver public realm that is safe and accessible to everyone. The public realm improvements will align with the Healthy Streets Approach and include footways resurfacing with paving, new planting, seating and secure cycle stands.
People choose to walk, cycle and use public transport	The site is located within LB Camden and has excellent accessibility to public transport services, as well as good pedestrian and cyclist routes. The pedestrianised nature of the Regent's Place actively encourages people to walk through the area.	The proposed cycle parking and end of trip facilities will encourage travel/daytime activity by active sustainable modes. The Travel Plan submitted alongside this TA seeks to further encourage prospective employees to travel via cycle and use the facilities within the development.
Clean air	According to the London Air Quality Network, the area that the site is situated within exceeds the annual mean and 1-hour mean objectives for NO ₂ . Some parts of the site pass the 24-hour mean for PM ₁₀ air pollution. There are currently 102 car parking spaces within the basement demise.	The Proposed Development will deliver extensive additional planting, relocate existing trees, and provide new trees and landscaping/amenity space. The development will encourage the use of electric freight vehicles which will help to improve air quality. The Proposed Development removes 100 car parking spaces which will help to improve air quality.
People feel safe	The existing tower has some active frontages, but the northern and southern building frontages are largely inactive. The surrounding buildings and active frontages provide passive surveillance.	The Proposed Development will increase the amount of active frontage providing additional passive surveillance. Street lighting, the presence of building management personnel and CCTV will contribute to improved safety perceptions around the site.
Not too noisy	Euston Road and Hampstead Road are relatively heavily trafficked. Regent's Place Plaza and Brock Street are pedestrianised and are not affected by noise from traffic.	It is expected that noise levels will remain unaffected by the presence of the Proposed Development. Facilities are being provided at the development to encourage quieter vehicle types – electric and cargo bikes.




Healthy Streets Indicators	Before - Existing Site	After – Proposed Development
Easy to cross	Signalised crossings are provided at Euston Road and Hampsted Road. The pedestrian green times are relatively long.	No changes to the crossings are proposed.
Places to stop and rest	Regent’s Place Plaza has a number of benches and installations that provide opportunities to stop and rest.	Regent’s Place Plaza will be improved as part of the Proposed Development and will have benches and installations that provide opportunities to stop and rest.
Shade and shelter	Shade and shelter are primarily offered in the form of street trees.	The level 2 podium provides a covered walking route around the building. New trees are proposed, which will offer shade.
People feel relaxed	The high footfall and vehicular traffic on Euston Road and Hampstead Road during the peak hours may mean new visitors to the area do not feel relaxed. Regent’s Place Plaza provides a large open space.	The improved pedestrian connections across the Plaza and around the building will provide a more comfortable and relaxing environment.
Things to see and do	Regent’s Place Plaza has various cafes, restaurants and bars, restaurants, and temporary displays and artwork.	The Proposed Development will provide a new community learning facility and further increase the retail entertainment offering at Regent’s Place Plaza. The new public realm will provide diverse natural habitats and spaces for children to explore as well as a variety of social spaces.

PROPOSED FOOTWAY WIDTHS

4.3.20 **Figure 4-8** shows the proposed footway widths and new public realm surrounding the site. Consistent and generous footway widths are proposed.

Figure 4-8: Proposed Footway Widths




4.4 SERVICING

EXISTING

- 4.4.1 The existing access for servicing vehicles is via Longford Street. The basement ramp provides access to a number of servicing areas which serve buildings across Regents Place. The access and basement are fully managed by Regent's Place Management.
- 4.4.2 The service yard area for Euston Tower is located towards the eastern side of the basement and is shared with 10 – 30 Brock Street. The existing basement layout is shown in **Figure 4-9**.

Figure 4-9: Existing Regents Place Basement Area



- 4.4.3 The servicing area provides nine loading bays in total, shared between Euston Tower and Brock Street. There are two 10m loading bays, three 8m bays and four 6m bays. The loading bays are located at a lower level than the Euston Tower and Brock Street back-of-house accesses and platform lifts are used to move goods and bins between the two levels.
- 4.4.4 The swept paths are shown in **Figure 4-10**, and drawings are also included at **APPENDIX B**.

Figure 4-10: Existing Service Area - Swept Path Analysis



WASTE MANAGEMENT

- 4.4.5 Waste for Euston Tower is managed by Regent’s Place Management, and waste storage is provided in line with the Regent’s Place waste strategy.
- 4.4.6 A copy of the Operational Site Waste Management Plan is included with the planning submission.


PROPOSED

OFFICE, LIFE SCIENCE AND ANCILLARY RETAIL DELIVERIES

- 4.4.7 The existing access and vehicle route to the servicing area will be retained for Euston Tower and Brock Street, and Regent’s Place Management will continue to manage the entire basement area. There will be a reduction in one 8m loading bay to accommodate refuse storage at the service yard level with cycle storage above.
- 4.4.8 The swept paths are shown in, and drawings are also included in **APPENDIX B**. All vehicles will enter and exit the servicing area in a forward gear.



Figure 4-11: Revised Basement Service Area




CARGO BIKE DELIVERIES

4.4.9


Deliveries made by larger cargo bikes or quadricycles similar to that in **Figure 4-12** will service the Proposed Development via the existing basement ramp and loading area. Within the basement loading area, two cargo bike parking bays will be provided. Deliveries will be received by a member of on-site staff.

Figure 4-12: Access Strategy for Larger Cargo Bikes



- 4.4.10 For standard cargo bike deliveries, two parking spaces will be provided at ground level, adjacent to the cycle access and main pedestrian building access. Deliveries will be received by a member of on-site staff.

Figure 4-13: Access Strategy for Standard Cargo Bikes




SPECIALIST LIFE SCIENCE DELIVERIES

- 4.4.11 The requirements for specialist deliveries are highly dependent upon the tenants. At this stage, it is therefore necessary to design flexibly to allow for different volumes, types and delivery methods of liquids/ gases.
- 4.4.12 Life sciences require several additional specialist bottled/liquid gas deliveries, along with the regular deliveries expected to a lab-type building.
- 4.4.13 The liquid and bottled gas deliveries cannot take place within the basement and need to be at ground level with 'blue sky' above them. All specialist delivery activity is proposed to be at ground level at the northwest corner of the building.

VEHICLE MOVEMENT

- 4.4.14 The proposed specialist delivery location will enable deliveries to be made safely and directly into the ground-level gas store. The vehicle will access the delivery bay from Drummond Street via Triton Square and stop in an area close to the gas store. An area will be cordoned off to pedestrians between the proposed planter to the north and the building. An alternative pedestrian route is provided to the north of the planter. **Figure 4-14** shows the vehicle access route and delivery bay location.

Figure 4-14: Specialist Gas Deliveries



4.4.15 All vehicle movements across the Regent's Place Plaza and the delivery process will be fully managed by trained staff with a 'banksman' provided to guide the vehicles across and manoeuvre within the plaza.

4.4.16 It is proposed that gas deliveries will be scheduled to be undertaken outside of peak pedestrian times where less people will be within the plaza.

TRANSFER FROM VEHICLE TO BUILDING

4.4.17 Once the servicing vehicle has arrived, the delivery can be transferred into the building.

4.4.18 For liquid nitrogen (LN2) deliveries, LN2 may be pumped directly to an on-site tank via a hose. If a Dewar exchange solution is adopted, full and empty Dewars will be transferred between the building and the LN2 store.

4.4.19 Gas bottles will be brought directly into the store from the delivery vehicle using trolleys and directly to the gas store at ground level.

WASTE MANAGEMENT

4.4.20 The proposed development will continue to form part of the wider Regent's Place Waste Strategy.

4.4.21 Waste will be segregated within a dedicated waste store at Basement Level 1 prior to transfer to a central location within the basement level for collection. Specialist and hazardous wastes will be stored in separate areas designed in accordance with their specific properties, either on tenant floors or centrally at the basement level.

4.4.22 Further detail regarding the waste storage and collection arrangement is set out in the Operational Waste Management Strategy submitted as part of the planning application.



SUMMARY

- 4.4.23 A Draft Delivery and Servicing Plan (DSP) has been produced as part of the planning application outlining the servicing strategy and is provided in **APPENDIX C**.
- 4.4.24 Through the DSP, deliveries can be minimised, timed and managed appropriately. The DSP also encourages deliveries outside of the peak pedestrian/cyclist hours.
- 4.4.25 Further detail regarding the waste storage and collection arrangement is set out in the Operational Waste Management Strategy submitted as part of the planning application.


4.5 CYCLE PARKING

EXISTING

LONG STAY

- 4.5.1 The site's existing cycle parking is provided within the basement level and accessed from the Drummond Street car park ramp. There are approximately 200 cycle parking spaces within the Euston Tower basement provided by Sheffield stands. There are a number of areas where car parking has been removed and cycle parking stands installed, as shown in **Figure 4-15**.

Figure 4-15: Existing Cycle Parking




SHORT STAY

- 4.5.2 In addition to the c.200 spaces provided at the basement level, there are a number of publicly available Sheffield stands in the surrounding public realm, providing 78 cycle parking spaces.
- 4.5.3 Brompton lockers are also provided within Regents Square, allowing customers to rent Brompton bikes for £5, up to 24 hours at a time.


4.5.4 The location of the Sheffield stands and the Brompton locker is illustrated in **Figure 4-16**.

Figure 4-16: Regents Place Public Realm Cycle Parking



4.5.5 There are also short stay cycle parking spaces within the surrounding public realm and local area, as illustrated in **Figure 4-17**.

Figure 4-17: Local Area Cycle Parking



4.5.6 **Figure 4-17** shows a number of Santander Cycles docking stations that are also available within walking distance of Euston Tower. Between them, they offer access to 148 cycles; the locations of the docks and their capacity are:

- Hampstead Road, Euston (54 bicycles)
- Longford Street, The Regent's Park (21 bicycles)
- Bolsover Street, Fitzrovia (19 bicycles)
- Warren Street station, Euston (26 bicycles)
- Drummond Street, Euston (28 bicycles)

PROPOSED

4.5.7 Encouraging and promoting cycling is a key focus of the proposed transport strategy, and a significant part of the basement has been dedicated to cyclist/active travel facilities. An Outline Travel Plan has been prepared, which focuses on maximising the use of the cyclist facilities and is provided in **APPENDIX D**.

4.5.8 The minimum cycle parking requirements have been determined based on the different floor areas occupied by the proposed uses.

4.5.9 The cycle access and parking proposals were discussed with both LBC and TfL during the pre-application stage and TfL stated that: *'The proposals represent an improvement to the existing cycle access arrangements and are welcomed and supported.'*

CYCLE ACCESS

4.5.10 As shown in **Figure 4-18**, cyclists will access the development using a dedicated entrance on Euston Road to the southwest of the Proposed Development.

Figure 4-18: CGI Image of the Proposed Ground Level Cycle Access



- 4.5.11 A shallow gradient (1:12) ramp will allow cyclists to enter the basement parking area without dismounting.
- 4.5.12 The cycle ramp will be an attractive and will lit entrance and the ramp and radius has been designed to feel comfortable for all types of bikes to the Proposed Development.
- 4.5.13 Cyclists unable to use, or those who do not wish to use the ramp can access the basement area using the cycle lift, designed to accommodate larger cycles.
- 4.5.14 The proposed basement access strategy for cyclist is shown in **Figure 4-19**.

Figure 4-19: Ground Level Cycle Access



LONG STAY CYCLE PARKING

- 4.5.15 Long-stay cycle parking will be provided in line with the London Plan minimum cycle parking standards. Based on the Proposed Development quantum, the required cycle parking provision is set out in **Table 4-2**.

Table 4-2: Proposed Long Stay Cycle Parking Provision

LAND USE	LONDON PLAN (MINIMUM LONG-STAY CYCLE PARKING STANDARDS)	LONDON PLAN LONG-STAY REQUIREMENTS	PROPOSED LONG-STAY CYCLE PARKING SPACES
Class E - Office	1 space per 75 sqm	750	861
Class E – Life Science	1 space per 250 sqm	98	
Class E– Retail	1 space per 175 sqm	4	
Class F1 – Public use	1 space per 8 Full Time Employees	9	

4.5.16 As set out in Chapter 8 of the London Cycle Design Standards (LCDS), cycle parking must be fit-for-purpose and able to accommodate all types of cycle.

4.5.17 **Figure 4-20** shows the cycle parking basement level, which provides the following breakdown of the proposed 861 long-stay cycle parking provisions:

- 646 two-tier parking (75%)
- 86 foldable bicycle parking (10%)
- 86 Sheffield stands (10%)
- 43 Enlarged Sheffield stands (5%)

4.5.18 The split of cycle parking types is in line with policy, guidance and was agreed with LBC and TfL at the pre-application stage.


ARRIVAL SPACE

4.5.19 A staffed reception desk will welcome cyclists arriving at the cycle parking level. The staff will be on hand to answer queries and help cyclists should they encounter any difficulties.

SECURITY

4.5.20 Unmanned security 'speed gates' will be installed at the base of the ramp to restrict access to the cycle parking area. The system will use RFID tags (or similar) to detect authorised users and verify only one cycle is present to avoid tailgating.

Figure 4-20: Proposed Cycle Parking Layout – Basement



END OF JOURNEY FACILITIES

- 4.5.21 Male and female changing rooms will be located adjacent to the long-stay cycle parking and will provide 574 lockers (two lockers per three parking spaces), 72 showers including two accessible showers (one shower per 12 cycle parking spaces) and six toilets including two accessible WCs.
- 4.5.22 As well as showering and changing facilities, it is proposed to include cycle maintenance facilities and water dispensers.
- 4.5.23 Considering that the scheme is a redevelopment of an existing building and that the majority of the basement structure is being retained, the layout has been designed to comply with LCDS as far as practicable, given the need to accord with London Plan requirements and the restrictions presented by the existing basement layout. Whilst LCDS states an aisle width of 2.5m should be achieved where accessing two-tier cycle racks, given the spatial and structural constraints of the existing basement, aisle widths in the range of 2.3m – 2.5m have been achieved. Testing was undertaken of cycle racks which identified that 2.3m is generous and allows for easy use of the upper tier.
- 4.5.24 As the proposals retain an existing basement and further excavation is not feasible, this approach to the cycle parking was agreed with LBC And TfL officers during pre-application discussions.
- 4.5.25 The proposed cyclist facilities will enable a higher cycle mode share and is a considerable increase and improvement compared to the existing layout.

SHORT STAY CYCLE PARKING

- 4.5.26 Short-stay cycle parking will be provided in line with the London Plan minimum cycle parking standards. The required short-stay cycle parking provision is set out in **Table 4-3**.


Table 4-3: Proposed Short-stay Cycle Parking Provision

LAND USE	LONDON PLAN (MINIMUM CYCLE PARKING STANDARDS)	LONDON PLAN SHORT-STAY REQUIREMENTS	PROPOSED SHORT-STAY CYCLE PARKING SPACES
Class E - Office	first 5,000 sqm: 1 space per 500 sqm thereafter: 1 space per 5,000 sqm (GEA)	20	89
Class E – Life Science	1 space per 1,000 sqm	9	
Class E– Retail	1 space per 20 sqm (GEA)	39	
Class F1 – Public use	1 space per 100 sqm (GEA)	21	

- 4.5.27 45 Sheffield or similar cycle stands will be provided, offering 90 short-stay cycle parking spaces within the public realm.
- 4.5.28 Two enlarged spaces to accommodate all types of cycle, including cargo bikes are proposed to be located to the south of the dedicated cycle access ramp.
- 4.5.29 The short-stay cycle parking spaces will be located within the public realm close to the building, as shown in **Figure 4-21**.



Figure 4-21: Proposed Short-Stay Cycle Parking



- 4.5.30 There is also an existing 56 dock TfL cycle hire station to the east of the Proposed Development.

SUMMARY

- 4.5.31 The Proposed Development will provide 861 long-stay cycle parking spaces made up of a mixture of cycle parking types to be compliant with the London Plan policy and LBC/TfL guidance. The proposed cycle access is an improvement to the existing arrangements and is supported by TfL.
- 4.5.32 The short-stay cycle will be compliant with the with the policy set out in the London Plan and LBC guidance and will provide 90 spaces within the public realm at ground level.

4.6 CAR PARKING

EXISTING

ON-SITE

- 4.6.1 A total of c.102 car parking spaces are provided within the Euston Tower basement, accessed from the Drummond Street car park ramp.

ON-STREET

- 4.6.2 The Proposed Development is located within the Controlled Parking Zone (CPZ) CA-G, where parking is controlled Monday to Friday between 08:30 and 18:30. Within the CPZ, on-street car and motorcycle parking are permitted in a number of local streets, including Drummond Street, Stanhope Street, Laxton Place, Longford Street and Osnaburgh Street.
- 4.6.3 On Drummond Street, Pay-by-Phone parking is available within laybys along the southern carriageway. The northern carriageway is a single yellow line, which is restricted in line with the CPZ hours.



4.6.4 On Longford Street, resident permit parking is provided between Osnaburgh Street and Laxton Place along the northern carriageway. The remaining carriageway is made up of single and double yellow lines.

4.6.5 A car club space is provided on Longford Street to the east of the junction with Osnaburgh Street.

DISABLED PARKING

4.6.6 Accessible car parking spaces are provided within the wider basement car park, which serves Regents Place, but there are no accessible spaces within the Euston Tower basement area.


PROPOSED

4.6.7 The proposed scheme is to be car-free, in accordance with London Plan and Camden Local Plan policy requirements.

4.6.8 Two blue-badge parking spaces are proposed within the Euston Tower basement demise, as shown in **Figure 4-22**.

4.6.9 The basement route also provides access to twelve car parking spaces which are leased by Santander. These car parking spaces and access to them are to be retained but the parking spaces are outside of the planning redline and Euston Tower basement demise.

Figure 4-22: Proposed Blue Badge and Existing Santander Car Parking




4.6.10 The design and management of the two blue-badge parking spaces is set out in the Car Parking Design and Management Plan which is contained in **APPENDIX E**.

4.7 PEDESTRIAN COMFORT ANALYSIS

EXISTING

- 4.7.1 Pedestrian flow data collected in a survey undertaken in April 2023 has been used to establish an existing baseline for pedestrian flows surrounding the site. The survey captured Euston Road (northern footway), Hampstead Road (western footway), Brock Street (north of the site) and the pedestrian crossings on Hampstead Road (northbound) and Euston Road (off-slip).
- 4.7.2 The existing AM and PM pedestrian flows are shown in **Figure 4-23**.

Figure 4-23: Existing Pedestrian Flows



- 4.7.3 Pedestrian Comfort Level (PCL) classifies the level of comfort based on the crowding a pedestrian experiences walking along a street. Pedestrian crowding is measured in pedestrians per metre per minute (ppmm).
- 4.7.4 PCL designates a score (from A+ to E) whereby a PCL A provides a pleasant walking experience, and a PCL E is an uncomfortable and restricted walking experience.
- 4.7.5 A PCL assessment has been undertaken of existing flows on the surrounding footways during the peak pedestrian hour, as shown in **Table 4-4**.

Table 4-4: Pedestrian Comfort Analysis – Existing Pedestrian Conditions

Ref.	Link	Link Type	Peak Hour Flow	Clear Footway Width	PCL
1	Euston Road	Office and Retail	1,583	6.9m	A
2	Euston Road	Office and Retail	1,583	9.9m	A
3	Hampstead Road	Office and Retail	1,068	15.7m	A+
4	Hampstead Road	Office and Retail	1,068	11.5m	A+
5	Brock Street	Office and Retail	522	6.9m	A+
6	Brock Street	Office and Retail	522	4.9m	A
7	Euston Road Crossing	Office and Retail	2,121	6.7m	A
8	Hampstead Road Crossing	Office and Retail	820	6.5m	A

4.7.6 The existing footway widths provide comfortable pedestrian conditions, with the lowest score of an A. The signalised pedestrian crossings on Euston Road and Hampstead Road have PCL scores of A.

PROPOSED DEVELOPMENT

- 4.7.7 The Proposed Development will change pedestrian flows by generating trips associated with people travelling to and from the building on foot. All modes, with the exception of cycles, will arrive and depart the building by foot.
- 4.7.8 Development trips have been distributed and assigned based on 2011 Census origin-destination data, as detailed in **Section 7**. Most people are expected to travel to the building to and from the south and west due to the location of Warren Street, Euston Square and Euston stations. The primary pedestrian entrances to the office and laboratories are at the south of the building fronting Euston Road. The public entrances for the community and learning space are located on the north side and northwest corner.
- 4.7.9 The forecast AM and PM peak pedestrian flows, including the Proposed Development, are shown in **Figure 4-24** and **Figure 4-25**.



Figure 4-24: Future Pedestrian Flows – AM Peak





Figure 4-25: Future Pedestrian Flows – PM Peak



4.7.10

Table 4-5 shows the PCL assessment once the Proposed Development becomes operational.



Table 4-5: Pedestrian Comfort Analysis – Proposed Pedestrian Conditions

Ref.	Link	Link Type	Peak Hour Flow	Clear Footway Width	PCL
1	Euston Road	Office and Retail	2192	8.1m	A
2	Euston Road	Office and Retail	3027	7m	A-
3	Hampstead Road	Office and Retail	1488	15m	A+
4	Hampstead Road	Office and Retail	1488	8.4m	A
5	Brock Street	Office and Retail	376	4.4m	A+
6	Brock Street	Office and Retail	376	13.1m	A+
7	Euston Road Crossing	Office and Retail	3,016	6.7m	B+
8	Hampstead Road Crossing	Office and Retail	1,138	6.5m	A-

4.7.11 The proposed footway widths provide comfortable pedestrian conditions, with the lowest score of an A- with the Euston Road pedestrian crossing scoring a B+.

4.7.12 A PCL of B+ is considered comfortable by TfL for all footway and crossing link types.

4.8 HIGHWAY OVERSAILING

4.8.1 The existing 'fins' installed for wind mitigation purposes oversail the public highway on the corner of Euston Road and Hampstead Road. There is an oversailing licence in place for this.

4.8.2 As part of the Proposed Development, the podium at Levels 2 and 3 will oversail the public highway. As per the existing situation, the areas that will oversail the public highway are on the corner of Euston Road and Hampstead Road.


4.8.3 It is confirmed that any oversailing of the highway on Euston Road/Hampstead Road will be a minimum of 5.7m above the height of the public highway.

4.8.4 As agreed with TfL during the pre-application stage, there will need to be an obligation for the landowner to agree the details of any oversailing prior to construction. It is understood that this can be dealt with by dedicated licence.

4.8.5 The proposed oversailing arrangement is illustrated in **Figure 4-26**.



Figure 4-26: Proposed Oversailing



4.8.6 As a result of the podium around the building, there will be a net increase of 8.2 sqm, oversailing the public highway.



5 ACTIVE TRAVEL

5.1 PEDESTRIAN NETWORK

EXISTING SITE ACCESSIBILITY AND PUBLIC REALM

- 5.1.1 The site can be accessed from Hampstead Road to the east, Euston Road to the south, and the pedestrianised public realm to the north and west.
- 5.1.2 The existing public realm, pedestrian routes, and local facilities throughout the wider Regent's Place and around the site are shown in **Figure 5-1**.

Figure 5-1: Existing site accessibility and facilities




WALKING

- 5.1.3 The National Travel Survey notes that walking is the most frequent travel mode used for short-distance trips (within 1 mile / 1.6km). Infrastructure that supports efficient travel on foot is therefore of great importance to promote sustainable and active travel and walking as a viable alternative to short car trips.
- 5.1.4 The local streets have an established network of footways typical of a city environment that provide access to the site, nearby facilities and amenities, local bus stops and Warren Street and Euston Square Underground stations, as well as Euston and Kings Cross stations further to the east. All streets in the area have footways on either side of the carriageway.
- 5.1.5 The Hampstead Road/Euston Road signalised junction is provided with straight-across controlled pedestrian crossings on each arm. Each crossing is provided with dropped kerbs and tactile paving with large islands for people crossing to wait.



5.1.6 Pedestrian isochrones from the site are provided within **Figure 5-2** at 10-minute intervals up to a 30-minute walking distance. The figure shows that nearby stations such as Warren Street and Euston are accessible within a 10-minute walk. Kings Cross, and St Pancras International are within a 20-minute walk from the site.


Figure 5-2: Walking Isochrone Plan



5.2 CYCLING

5.2.1 The cycling network in the area surrounding the site is shown in **Figure 5-3**.

Figure 5-3: Local cycle network



5.2.2 **Figure 5-3** shows that there are a number of local cycle routes within proximity of the site, the nearest being Cycleway 27, which provides connections between Hammersmith in the west to Clapton and Homerton in the east via Paddington, Angel, Islington and Hackney. The development is conveniently located in terms of cycle accessibility, with a number of local facilities and amenities accessible by cycle using the network of cycle routes in the vicinity of the site.

5.2.3 Many roads near the site are marked as suitable or signed for cyclists and include lanes and advanced stop lines (ASLs) at each arm of the Hampstead Road junction / A501 Euston Road signalised junction.

5.2.4 Hampstead Road provides cycle lanes, while Longford Street / Drummond Street are quieter local roads recommended for cyclists. In addition, to the south, there is a network of routes that are signed or marked for cyclists and connect the site with Marylebone, Fitzrovia and central London.

5.2.5 Quietway 3 (Q3) is located 2.9km northwest of the site and begins at Regent's Park and connects to St. John's Wood, Hampstead, Kilburn, Willesden Green and Dollis Hill.


5.2.6 Cycle Superhighway (CS6) is located approximately 1.4km east of the site and connects Elephant & Castle to the south and King's Cross to the north.

5.2.7 Cycling has great potential for short journeys less than five kilometres in length; however, many people will cycle longer distances.



- 5.2.8 A cycling isochrone showing areas that can be reached from the site within a 20-minute cycle is provided in **Figure 5-4**.

Figure 5-4: Cycling Catchment



- 5.2.9 Many key destinations and transport nodes within Central London, such as Liverpool Street, Waterloo and London Bridge stations and Oxford Street, can be reached within a 20-minute cycle.

5.3 ACTIVE TRAVEL ZONE ASSESSMENT

OVERVIEW

- 5.3.1 This Active Travel Zone (ATZ) Assessment has been carried out in line with the TfL Transport Assessment guidance, which came into effect on 1 April 2019 and aims to show how the Proposed Development supports Vision Zero and the Healthy Streets policies.
- 5.3.2 The ATZ assessment has been prepared using the 'ATZ assessment instructions' obtained from TfL's Transport Assessments webpage: (<https://tfl.gov.uk/info-for/urban-planning-and-construction/transport-assessment-guide/transport-assessments>).
- 5.3.3 The ATZ assessment outlines a series of observations and, where relevant, recommendations as to how conditions for active travel can be improved, and on which routes are these improvements be best focused.



5.3.4 It should be noted that any recommendations identified are opportunities for the local highway authority and future developers to deliver. They are not specifically linked to the Proposed Development, and their implementation is not required to mitigate its impacts. However, it is hoped that the recommendations will assist in improving the local conditions for active travel.

5.3.5 There are four parts to the ATZ assessment process, which are as follows:

1. **Map One:** The ATZ and all potential key active travel destinations;
2. **Map Two:** Neighbourhood safety and the most important journeys with supporting text, including a vision zero analysis and safety improvement ideas;
3. **Map Three:** ATZ Neighbourhood healthy characteristics check, including text on severance, deficiency, local change, development; and
4. **Neighbourhood Photo Survey:** ATZ neighbourhood key routes check based on the Healthy Streets indicators.

5.3.6 ATZ Maps 1, 2 and 3, and the Photo Survey Locations are contained in **APPENDIX F**.

NEIGHBOURHOOD PHOTO SURVEY

5.3.7 The Neighbourhood Photo Survey site visit was undertaken on Wednesday, 12th July 2023, between 09:00 – 12:00.

5.3.8 A nighttime assessment was undertaken on Wednesday, 25th October 2023, between 20:00 and 22:00.


ACTIVE TRAVEL ZONE

5.3.9 **Figure 5-5** shows all potential key destinations that are within the ATZ. These include:

- Public transport stops and stations;
- London's current and future London-wide strategic cycle network;
- Town centres;
- Parks/greenspace;
- Medical care facilities (including hospitals and general practitioners); and
- Places of worship.



Figure 5-5: Map One - Active Travel Zone Map



- 5.3.10 **Figure 5-5** shows that multiple amenities and facilities are within a 20-minute cycle catchment; these include greenspaces, transport services (i.e., bus and rail), the existing and proposed cycle network, essential shopping, and places for leisure and worship.
- 5.3.11 The map further confirms the high level of public transport access that the site benefits from and shows the potential for active travel to key destinations.

Table 5-1: ATZ Key Destinations Prioritisation

Key Destination	Priority	Justification
London Underground/ National Rail Stations	High	Rail travel allows for convenient medium and long-distance travel to a range of destinations and employment opportunities. The majority of longer-distance travel to/from the development is expected to be by rail. Stations have, therefore, been classified as high priority.
Bus stops	High	The development site is situated near a number of bus stops, which provide access to local bus routes. Bus stops are considered to be high-priority destinations.
Strategic Cycle Network	High	The strategic cycle network will allow future residents of the site to access local facilities easily using zero-emission, active travel. Therefore, the network is classified as a high priority.
Greenspace	Medium	Green spaces in city developments are considered to be key leisure and recreation spaces, encouraging activity. Green spaces are considered a medium priority.
Medical Centre	Low	As most people generally do not need to go to a medical care facility on a daily basis and people who do require medical care are less likely to be able to walk and cycle to this care, this category has been labelled as low priority.
Places of Worship (PoW)	Low	Places of worship will not usually be a daily destination for employees or visitors.




ATZ NEIGHBOURHOOD – KEY DESTINATIONS

5.3.12 **Figure 5-6** shows the key destinations that have been extracted from **Figure 5-5** using the prioritisation set out in **Table 5-1**. Given that the Proposed Development is to be primarily office/life science use with ancillary retail, the site is expected to primarily generate walking and cycling trips by employees mainly to rail stations/bus stops.

5.3.13 For the purposes of the ATZ assessment, five key routes have been plotted (as agreed with Camden and TfL officers). The neighbourhood-scale map and routes to key destinations are set out in **Figure 5-6**.

Figure 5-6: Neighbourhood Zone Map 2



5.3.14 As can be seen in Map 2, five key routes have been identified. The destinations have been grouped into the following routes:

- **Key Route 1:** Euston Road bus stops, Hampstead Road cycle hire, Hampstead Road bus stops, and London Euston Station
- **Key Route 2:** Euston Square Station, St Pancras Station and London King's Cross Station
- **Key Route 3:** Euston Road bus stops, Great Portland Street Station, Regents Park and Regents Park Station
- **Key Route 4:** Warren Street Station, Tottenham Court Road bus stops, and Tottenham Court Road Station
- **Key Route 4b:** University College Hospital
- **Key Route 5:** Warren Street bus stops and Fitzroy Square Gardens

5.1 KILLED OR SERIOUSLY INJURED COLLISION DATA

5.1.1 As a part of this ATZ assessment a Vision Zero analysis has been undertaken and the location of accidents by severity within the most recent five-year data period has been plotted in **Figure 5-7** with a breakdown of the collisions by year provided in **Table 5-2**.

Figure 5-7: Personal Injury Accident Map




Table 5-2: Personal Injury Data

SEVERITY	2018	2019	2020	2021	2022	TOTAL
Fatal	0	0	1	0	0	1
Serious	17	20	10	12	6	65
Total	17	20	11	12	6	66

- 5.1.2 A total of 66 vulnerable road users (pedestrians and cyclists) sustained serious injuries along the ATZ routes, with one fatality recorded.

SUMMARY OF LOCAL ROAD MODIFICATIONS

EUSTON ROAD

- 5.1.3 Euston Road forms part of the TfL network. TfL recently implemented a 20mph speed limit (April 2023) on all of their roads within Central London. This speed limit reduction on Euston Road will assist to improve highway safety.
- 5.1.4 A review of the location of collisions identified that most have occurred on Euston Road which is a major two-way road and forms a key section of the London Inner Ring Road. The road has features which are likely to discourage high vehicle speeds which could otherwise increase the likelihood of severe collisions, such as a 20mph speed limit, signalised crossings, bus stops and regular junctions for local destinations. As such, it is considered that the design of the highway infrastructure is likely to be appropriate for a road with this function, and there are no obvious deficiencies which may have led to the serious and fatal collision(s).
- 5.1.5 While it is acknowledged that any collision is unfortunate, the number of recorded collisions overall and more specifically those involving vulnerable road users (pedestrians/cyclists) is seen to be low considering the busy nature of the road and that the assessment has included all collisions recorded over a five-year period.

TOTTENHAM COURT ROAD

- 5.1.6 There has been a notable reduction in the number of collisions from 2018/2019 to 2020 which can partly be attributed to a 20mph speed limit introduced during 2020.
- 5.1.7 Tottenham Court Road was a one-way street up until 2021, with all three lanes being northbound only and the corresponding southbound traffic using parallel Gower Street to the east. During 2020/2021, new two-way traffic flows on Tottenham Court Road and the surrounding streets were introduced and are now fully completed.
- 5.1.8 Additional improvements on Tottenham Court Road undertaken during 2021 consist of traffic banned from turning left onto Euston Road from Tottenham Court Road and areas of the road are now restricted to buses and cyclists only between Monday to Saturday from 08:00am to 19:00pm.

VISION ZERO ANALYSIS

- 5.1.9 As part of the Vision Zero initiative, a review of all collision 'clusters' within the latest three-year period was undertaken. A cluster is identified as two or more serious or fatal collisions occurring in the same area. A review of the identified collision clusters at junction points and fatal accidents is provided below.



FATALITY

- 5.1.10 On Tuesday, 7th April 2020, at 13:19, a collision occurred on Euston Road, near the junction with Melton Street, involving one bus or coach (17 Or More Passenger Seats), one motorcycle over 500cc and one pedal cycle, resulting in fatal injury to the pedal cyclist.
- 5.1.11 Due to the lack of information, as no police report was provided, it is difficult to ascertain the cause of the incident.

COLLISION CLUSTERS

- 5.1.12 A collision cluster was identified at the junction between Euston Road, Hampstead Road and Tottenham Court Road, adjacent to the proposed site location. Within the three-year recorded period, a cluster involving three collisions occurred; the details of the collisions are provided below.
- ⊙ On Tuesday, 24 November 2020, at 08:59, a Collision occurred on Tottenham Court Road, near the junction with Euston Road, involving one bus or coach (17 Or more passenger seats) and one car.
 - ⊙ On Thursday, 14 October 2021, at 12:45, a collision occurred on Tottenham Court Road, 25 Metres north of the junction with Euston Road, involving one motorcycle over 50cc and up to 125cc and one pedal cycle.
 - ⊙ On Friday, 26 November 2021, at 20:55, a collision occurred on Euston Road, near the junction with Hampstead Road, involving one taxi / private hire car and pedestrian(s).
- 5.1.13 A cluster of collisions has been identified at the junction between Euston Road, Great Portland Street and Marylebone Road. Three collisions occurred at this junction in the reviewed period and are detailed below.
- ⊙ On Sunday, 12 January 2020, at 01:31, a collision occurred on Euston Road, near the junction with Great Portland Street, involving one car and pedestrian(s).
 - ⊙ On Thursday, 10 June 2021, at 11:20, a collision occurred on Marylebone Road, near the junction with Albany Street, involving one motorcycle 50cc and under and one van/goods vehicle 3.5 tonnes maximum gross weight (MGV) and under.
 - ⊙ On Tuesday, 23 November 2021, at 13:26, a collision occurred on Marylebone Road, London nw1, 5 metres north of the junction with Albany Street.
- 5.1.14 A cluster of collisions was identified at the junction between Euston Road, Eversholt Street and Upper Woburn Place. Two collisions occurred at this junction in the reviewed period and are detailed below.
- ⊙ On Tuesday, 28th September 2021 at 23:32, a collision occurred on Euston Road, near the junction with Eversholt Street in Camden involving one motorcycle over 50Cc and up to 125Cc and a pedestrian(s).
 - ⊙ On Wednesday, 18th May 2022, at 14:55 a collision occurred on Euston Road, near the junction with Euston Square in Camden involving one pedal cycle and a pedestrian (s).
- 5.1.15 A cluster of collisions was identified at the junction between Euston Road, Churchway and Dukes Road. Two collisions occurred at this junction in the reviewed period and are detailed below:
- ⊙ On Wednesday 31st March 2021, at 12:40 a collision occurred on Euston Road, near the junction with Churchway in Camden involving one car and one pedal cycle.



- ⦿ On Thursday 10th March 2022, at 16:20 a collision occurred on Euston Road nw1, near the junction with Churchway in Camden involving one car and one motorcycle over 50Cc and up to 125Cc.

5.1.16 A cluster of collisions was identified at the junction between Oxford Street and Tottenham Court Road. Two collisions occurred at this junction in the reviewed period and are detailed below.

- ⦿ On Thursday, 17 September 2020, at 16:05, a collision occurred on Tottenham Court Road, near the junction with Charing Cross Road, London, WC2H. In Westminster, involving one motorcycle - unknown cc and one pedal cycle.
- ⦿ On Friday, 10 September 2021, at 22:30, a collision occurred on Tottenham Court Road, near the junction with New Oxford Street, involving one car and a pedestrian(s).


HEALTHY NEIGHBOURHOOD CHARACTERISTICS

5.1.17 **Figure 5-8** shows the healthy neighbourhood characteristics for the area surrounding the site, including:

- ⦿ Street density
- ⦿ Public transport
- ⦿ Local amenities
- ⦿ Green spaces
- ⦿ Site Allocations



Figure 5-8: Healthy Neighbourhood Characteristics



STREET DENSITY

- 5.1.18 The London permeable neighbourhood network layer (blue coloured) indicates that the area around the site is very permeable, with pedestrians and cyclists easily able to travel from area to area. The key routes include wide footways on both sides of the road, crossing facilities, and cycle routes.

PUBLIC TRANSPORT

- 5.1.19 The site has a PTAL level of 6b and benefits from easy and convenient access to a large number of public transport services. The nearest London Underground station is Warren Street, 20m to the south of the site, providing access to Northern and Victoria London Underground (LU) lines. Euston Square station is located approximately 300m to the east of the site and provides access to a further three LU lines: Metropolitan, Hammersmith & City, and Circle line. The Overground can be accessed from Euston station, located approximately 400m east of the site. Many bus services are also available from bus stops immediately outside the site.

GREEN SPACES

- 5.1.20 The site is located in close proximity to Park Square and Regent's Park. These spaces are ideal for walking, exercise, playing or relaxing. Regent's Park features gardens, children's playgrounds, cricket and football pitches, and London Zoo.



5.2 ATZ KEY ROUTE ASSESSMENT

- 5.2.1 A site visit was undertaken to assess each of the key routes identified as part of the desk-based stages of the ATZ assessment. These routes have been walked to understand the quality of the most important active travel routes from the site.
- 5.2.2 The Worst Point of each route was identified. 'Worst' is defined as the most unpleasant or potentially unsafe part of a route for pedestrians and/or cyclists.
- 5.2.3 The Worst Point of each route has been reviewed and assessed against eight of the 10 Healthy Streets Criteria (criteria 3 – 10) in line with TfL's ATZ and Healthy Streets TA Guidance. The following eight criteria have been assessed:
- ⊙ Easy to cross
 - ⊙ People feel safe
 - ⊙ Things to see and do
 - ⊙ Places to stop and rest
 - ⊙ People feel relaxed
 - ⊙ Not too noisy
 - ⊙ Clean air
 - ⊙ Shade and shelter



KEY JOURNEY 1 – LONDON EUSTON STATION

- 5.2.4 Route 1 is a route between the Site and London Euston station via Euston Road. This was identified as a key route as many employees of the Proposed Development are expected to use the London Underground, Overground or national rail services that serve the station.
- 5.2.5 The worst point on the route, shown in **Figure 5-9**, was identified as the pedestrian island crossing on New Gower Street by its junction with Euston Road. This is because the pedestrian island is not raised or has tactile paving, and as such, visually impaired pedestrians may not realise the central island is there.
- 5.2.6 The wider route is easy to follow and well-kept with wide footpaths on Euston Road. The provided pedestrian infrastructure is conducive to pedestrian movement in the area, such as street lighting and signalised crossing points.
- 5.2.7 The worst point identified on the route to London Euston station has been reviewed against the healthy streets criteria and is presented in **Table 5-3**.

Figure 5-9: Key Route 1 Worst Point



Table 5-3: Key Journey One Healthy Streets Assessment

INDICATOR	INDICATOR MET	DESCRIPTION	IMPROVEMENT
Easy to cross	Yes	The area pictured is easy to cross, with the provision of dropped kerbs and tactile paving catering to pedestrian movement in the area. A crossing with a pedestrian island is provided on New Gower Street that does not have tactile paving. As such, visually impaired pedestrians may not realise they are required to stop and wait at the island before crossing.	Provide tactile paving to the central island at the crossing on New Gower Street.
People feel safe	Yes	The footpaths are generally wide and provide a degree of separation from the busy Euston Road. Footfall traffic is also very heavy; as such, pedestrians do not feel isolated when on the route.	No need for improvement
Things to see and do	Yes	The pictured location is at the junction with Euston Road, which offers a variety of amenities, such as a café, restaurants and a climbing centre.	No need for improvement
Places to stop and rest	Partly	A bus stop is provided a few metres west of the pictured location; however, no public benches are provided. Whilst this is the case, the pictured location is only a few minutes' walk from Regents Place and Euston Station, which both provide areas to stop and rest.	No need for improvement
People feel relaxed	No	The route features high levels of both vehicular traffic and pedestrian footfall, which causes it to feel busy.	No area for improvement
Not too noisy	No	Due to the high levels of pedestrian and vehicular traffic, the route is noisy.	Improve local bus and cycle infrastructure to increase the number of people in the area travelling via sustainable means.
Clean air	No	As per the London Air Quality Network, the pictured location fails to meet the London annual No2 objective.	Increase the provision of street greenery to reduce harmful emissions.
Shade and shelter	Partly	Some shade and shelter are provided by the buildings and trees overlooking the route, as well as the bus stops on Euston Road.	No need for improvement



KEY JOURNEY 2 – LONDON KING’S CROSS STATION

- 5.2.8 Route 2 connects the site to London Kings Cross Station via Euston Road. As a continuation from Route 1, the pedestrian environment is similarly well-kept and conducive to pedestrian movement in the area, with footpaths on either side of the carriageway and appropriate crossing infrastructure.
- 5.2.9 The worst point, shown in **Figure 5-10**, was identified as the footway along Euston Road due to level differences in the footpath. The roots of the trees planted along Euston Road have begun to raise the footway. This is of particular note as Kings Cross Station is one of the primary London links to airports and other UK towns, such there is a higher than typical volume of pedestrians travelling with suitcases and additional items that could be affected by poor paving conditions that could either present a trip hazard or impair movement.
- 5.2.10 The worst point identified on the route to King’s Cross station reviewed against the Healthy Streets criteria is presented in **Table 5-4**.

Figure 5-10: Key Journey 2 Worst Point




Table 5-4: Key Journey Two Healthy Streets Assessment

INDICATOR	INDICATOR MET	DESCRIPTION	IMPROVEMENT
Easy to cross	Yes	Signalised pedestrian crossing points are provided a few metres from the pictured location, complete with dropped kerbs and tactile paving.	No need for improvement
People feel safe	Yes	The footpaths are generally wide, providing a degree of separation from the busy Euston Road. Footfall traffic is also very heavy; as such, there are good levels of natural surveillance. It is noted that the northern footpath on Euston Road is uneven, and there are significant level differences at certain sections.	The footpath should be reviewed and repaired in areas where paving slabs have been raised and have cracked.
Things to see and do	Yes	The pictured location is adjacent to Kings Cross station, which provides numerous stores, cafés, and restaurants both within it and surrounding the station.	No need for improvement
Places to stop and rest	Yes	Benches and seated areas are provided within and surrounding Kings Cross station.	No need for improvement
People feel relaxed	Partly	The pictured location is extremely busy both in terms of pedestrian footfall and vehicular traffic along Euston Road, causing the area to feel hectic.	No area for improvement
Not too noisy	No	Due to the high levels of pedestrian and vehicular traffic, the route is noisy.	Improve local bus and cycle infrastructure to increase the number of people in the area travelling via sustainable means.
Clean air	No	As per the London Air Quality Network, the pictured location fails to meet the London annual NO ₂ objective.	Increase the provision of street greenery to reduce harmful emissions.
Shade and shelter	Partly	Some shade and shelter are provided by the buildings and trees overlooking the route, as well as the bus stops on Euston Road.	No need for improvement



KEY JOURNEY 3 – REGENTS PARK STATION

- 5.2.11 Route 3 connects the site to Regents Park underground station to the west via Euston Road. This was identified as a key route as many employees of the Proposed Development are expected to use the London Underground as their primary mode of transport to and from the site. Alongside this, the route also passes through Regents Park and thus doubles as a route to a recreational/green space.
- 5.2.12 The worst point, shown in **Figure 5-11**, was identified as the overgrown vegetation sprouting from Regents Park on Marylebone Road. The vegetation should be trimmed to prevent it from obstructing the pavement.
- 5.2.13 The worst point identified on the route to Regents Park station reviewed against the healthy streets criteria is presented in **Table 5-5**.

Figure 5-11: Key Journey 3 Worst Point



Table 5-5: Key Journey Three Healthy Streets Assessment

INDICATOR	INDICATOR MET	DESCRIPTION	IMPROVEMENT
Easy to cross	Yes	A signalized pedestrian crossing is provided at every crossing point between the site and the Regents Park Station entrance.	No need for improvement
People feel safe	Yes	Due to the provided crossing points and wide footpaths, pedestrians can feel comfortable when travelling in the area.	No need for improvement
Things to see and do	Yes	The route ends at Regents Park, a recreational area and one of the largest parks in London. It is, however, noted that some of the vegetation from Regents Park fronting onto Euston Road is overgrown and partially obstructing the footway.	Trim vegetation protruding from Regents Park.
Places to stop and rest	Yes	Benches and seated areas are provided within Regents Parks.	No need for improvement
People feel relaxed	Partly	The pictured area is located on Euston Road, a very busy dual carriageway which can be intimidating to pedestrians. However, it is also adjacent to Regents Park, a recreational area where pedestrians can go to relax.	No need for improvement
Not too noisy	No	Euston Road is noisy due to its high levels of vehicular traffic.	Implement acoustic barriers on Euston Road to reduce noise pollution.
Clean air	No	As per the London Air Quality Network, the pictured location fails to meet the London annual No2 objective.	Increase the provision of street greenery to reduce harmful emissions.
Shade and shelter	Yes	Shade and shelter can be sought in Regents Park adjacent to the picture's location.	No need for improvement



KEY JOURNEY 4 – TOTTENHAM COURT ROAD STATION

- 5.2.14 Route 4 identifies a pedestrian walking route from the site to Tottenham Court Road station to the south via Tottenham Court Road. This was identified as a key route as many employees of the Proposed Development are expected to use the London Underground and the Elizabeth Line as their primary mode of transport to and from the site.
- 5.2.15 The worst point, shown in **Figure 5-12**, was identified as the rubbish placed on the street at various points along Tottenham Court Road. It is presumed a lot of the rubbish is placed out there by commercial properties for collection; however, the collection locations can become overrun with rubbish as the public adds to the collection pile. To remedy this, large bins could be placed in strategic locations along Tottenham Court Road to contain all the waste.
- 5.2.16 The worst point identified on the route to Tottenham Court Road station reviewed against the healthy streets criteria is presented in **Figure 5-12**.

Figure 5-12: Key Journey 4 Worst Point



Table 5-6: Key Journey Four Healthy Streets Assessment

INDICATOR	INDICATOR MET	DESCRIPTION	IMPROVEMENT
Easy to cross	Yes	Numerous pedestrian crossing points are provided along the route, with one located a few minutes' walk from the pictured location.	No need for improvement
People feel safe	Yes	High pedestrian footfall stops pedestrians from feeling isolated, and the numerous crossing points provided make pedestrian movement in the area safe and easy.	No need for improvement
Things to see and do	Yes	Tottenham Court Road provides a wealth of high street stores, cafés and food stalls.	No need for improvement
Places to stop and rest	Yes	Benches are provided a few minutes' walk north and south from the pictured location on Tottenham Court Road.	No need for improvement
People feel relaxed	No	The route is very busy, and there is a lot of litter and rubbish scattered at points along Tottenham Court Road, which makes the route less attractive.	Implement large bins for the commercial stores and local residents to use rather than bin bags left on the street.
Not too noisy	No	High levels of vehicular traffic and pedestrian footfall make the routes noisy.	No area for improvement
Clean air	No	As per the London Air Quality Network, the pictured location fails to meet the London annual No2 objective.	Increase the provision of street greenery to reduce harmful emissions.
Shade and shelter	Yes	Shaded and partially sheltered seating areas are provided at numerous points along Tottenham Court Road, a few minutes' walk from the pictured location.	No need for improvement



KEY JOURNEY 4B – UNIVERSITY COLLEGE HOSPITAL

- 5.2.17 Route 4b identifies a pedestrian walking route from the site to the University College Hospital to the south via Tottenham Court Road and Grafton Way. This was identified as medical institutes and pharmacies are an integral amenity in local communities.
- 5.2.18 The route was mostly in line with the criteria highlighted as part of the Healthy Streets assessment, with the worst point, shown in **Figure 5-13**, identified as the vehicular access and egress to the University College Hospital Grafton Way building. These access points are flush with the pedestrian footway and do not feature tactile paving, thereby presenting a issue to visually impaired pedestrians. However, it is noted that these accesses are controlled and not frequently in use.
- 5.2.19 The worst point identified on the route to Tottenham Court Road station reviewed against the healthy streets criteria is presented in **Table 5-7**.

Figure 5-13: Key Journey 4b Worst Point




Table 5-7: Key Journey Four B Healthy Streets Assessment


INDICATOR	INDICATOR MET	DESCRIPTION	IMPROVEMENT
Easy to cross	Yes	Pedestrian crossings are provided at the vehicular access and egress points of the University College Hospital Grafton Way building.	No need for improvement
People feel safe	Yes	Wide footpaths and slow-moving traffic on Grafton Way cause the route to feel safe.	Tactile paving could be provided
Things to see and do	No	There is nothing to see or do on Grafton Way.	Providing planting would give the route a livelier feel.
Places to stop and rest	Yes	Benches are provided a few minutes' walk east of the location on Huntley Street.	No need for improvement
People feel relaxed	Yes	Grafton Way does not have high footfall; as such, the road does not feel overly busy. In addition, the side footpaths provide a large degree of separation from vehicular traffic and are well-maintained.	No need for improvement
Not too noisy	No	Grafton Way is an access point for the University College Hospital, and it features a higher-than-average number of police cars and ambulances, both of which generate a lot of noise.	No area for improvement
Clean air	No	As per the London Air Quality Network, the pictured location fails to meet the London annual NO ₂ objective.	Increase the provision of street greenery to reduce harmful emissions.
Shade and shelter	Partly	Shaded and shelter are partly provided by the building overlooking Grafton Way.	Provide a cover for the bench provided on Huntly Street.



KEY JOURNEY 5 – FITZROY SQUARE GARDENS

- 5.2.20 Route 5 identifies a pedestrian walking route to Fitzroy Square Garden via Euston Road and Fitzroy Street. Fitzroy Square Gardens is a private garden which is open to the public during lunchtime hours between June and September. Fitzroy Square is ‘traffic lite’ with a number of public benches located around the square.
- 5.2.21 The route along Euston Road and Fitzroy Street comprises wide footways and was mostly in line with the criteria highlighted as part of the Healthy Streets assessment. The worst point, shown in **Figure 5-14** identified as the footway outside 47 Fitzroy Street.
- 5.2.22 There are a number of mature trees and street furniture narrowing the available width in places.

Figure 5-14: Key Journey 5 Worst Point



- 5.2.23 The worst point identified on the route to Tottenham Court Road station reviewed against the healthy streets criteria is presented in **Table 5-8**.

Table 5-8: Key Journey Five Healthy Streets Assessment

INDICATOR	INDICATOR MET	DESCRIPTION	IMPROVEMENT
Easy to cross	Yes	Pedestrian crossings are provided across Euston Road from the development site to the southern Euston Road footway	No need for improvement
People feel safe	Yes	Wide footpaths are provided on Euston Road. Fitzroy Street has footways on either side and is lightly trafficked	No need for improvement
Things to see and do	Yes	There are a number of shops and restaurants on Euston Road and Fitzroy Street is well planted with lots of trees	No need for improvement
Places to stop and rest	Yes	A bench is provided near the junction of Euston Road and Fitzroy Street. Numerous benches are provided around Fitzroy Square Gardens	No need for improvement
People feel relaxed	Yes	Wide footpaths are provided on Euston Road. Fitzroy Street has footways on either side and is lightly trafficked	No need for improvement
Not too noisy	No	Euston Road is noisy with heavy traffic flows. Fitzroy Street is quiet due to it being lightly trafficked.	No area for improvement
Clean air	No	As per the London Air Quality Network, the pictured location fails to meet the London annual NO ₂ objective.	Increase the provision of street greenery to reduce harmful emissions.
Shade and shelter	Partly	Several building overhangs provide shade and shelter along Euston Road. Shade and shelter is provided by some trees along Fitzroy Street.	Provide a cover for the bench provided on Huntly Street.

5.2.24 Any recommendations identified are opportunities for the local highway authority and future developers to deliver. They are not specifically linked to the Proposed Development, and their implementation is not required to mitigate its impacts. However, it is hoped that the recommendations will assist in improving the local conditions for active travel.



LOCAL DEVELOPMENT AND REGENERATION PROJECTS

- 5.2.25 The site is part of a wider site allocation within the Euston Area Plan. Camden Council, in collaboration with the TfL and the GLA, drafted the Euston Area Plan, a long-term strategic planning framework to guide transformational change in the area up until 2031. Work on the update to EAP is currently paused due to the uncertainty following the Government decision to pause most works associated with HS2 at Euston.
- 5.2.26 The regeneration of Euston is underway and will provide significant new development, including non-residential facilities that will be within a short walking distance of the site and further encourage active travel.
- 5.2.27 There are currently plans to terminate the new HS2 line at Euston station, as such great emphasis has been put on improving the existing Euston Station and surrounding area with sustainable and appropriate onward travel options which meet increased passenger demands (including those from HS2) and general development in the area.
- 5.2.28 In addition, TfL improvements are planned to Euston Road and Hampstead in order to facilitate the creation of a more pleasant and accessible street environment, with enhancements to Euston Square Gardens and improved road crossings.



6 LONDON-WIDE NETWORK

6.1.1 This section of the TA provides information on the current use of the wider transport network, including how many people travel and their current modes/behaviours.


6.2 PUBLIC TRANSPORT NETWORK

PUBLIC TRANSPORT ACCESSIBILITY LEVEL (PTAL)

6.2.1 PTAL is used to assess the connectivity of a site to the public transport network in consideration of the access time and frequency of services. It considers rail stations within a 12-minute walk (960m) of the site and bus stops within an eight-minute walk (640m) and is undertaken using the AM peak hour operating patterns of public transport services. An Access Index (AI) score is calculated that is used to define a PTAL score.

6.2.2 TfL's online WebCAT tool shows the site AI is 85.4, indicating a PTAL of 6b (excellent). The WebCAT PTAL output is summarised in **Figure 6-1**.

Figure 6-1: Site PTAL map



BUS NETWORK

6.2.3 The site is located in close proximity to a comprehensive level of bus provision. The closest bus stops are situated on Hampstead Road, to the east of the site, which provides access to bus routes 24, 27, 29 and 134. Euston Road bus stop to the south of the site provides access to bus routes 18, 30 and 205.

6.2.4 The local bus services and average peak hour frequency are summarised in **Table 6-1**.

Table 6-1: Local bus stop summary and frequency

SERVICE NUMBER	BUS STOP	ROUTE	FREQUENCY PER HOUR (BY DIRECTION)
18	Euston Road	Sudbury & Harrow Road Station – Euston Station	15
24	Hampstead Road	South End Green - Pimlico	6
27	Hampstead Road	Chalk Farm – Hammersmith Grove	6
29	Hampstead Road	Lordship Lane – Trafalgar Square	12
30	Euston Road	Hackney Wick – Marble Arch	6
73	Euston Square	Stoke Newington – Oxford Circus	10
134	Hampstead Road	North Finchley – Warren Street	7
205	Euston Road	Bow Church - Paddington	6
390	Euston Square	Archway - Victoria	7
TOTAL			75

6.2.5 The table shows that the local bus stops provide access to 150 bus services per hour. The local bus routes are illustrated in **Figure 6-2**.


Figure 6-2: Local Bus Routes



LONDON UNDERGROUND AND RAIL NETWORK

6.2.6 **Figure 6-3** shows the nearest London Underground and rail networks within proximity (i.e., approximately 20-minute walk/10-minute cycle) of the site.

Figure 6-3: Underground and rail networks within proximity of the site



6.2.7 The site is situated within close proximity to a number of TfL Underground routes, making it a highly accessible location within London.

6.2.8 The site is also close to major stations such as Euston, St Pancras International and Kings Cross, which provide journeys to the rest of the UK and internationally via the Eurostar.

LONDON UNDERGROUND

6.2.9 **Table 7.11** shows the peak hour frequencies of Underground services from Warren Street, Euston Square and Regent's Park Stations.

Figure 6-4: Underground Services and Frequencies

STATION	SERVICE	DIRECTION	FREQUENCY PER HOUR	
			AM	PM
Euston Square	Circle	Inner Rail	6	6
		Outer Rail	6	6
	Metropolitan	Northbound	15	15
		Southbound	16	16
	Hammersmith and City	Inner Rail	6	6
		Outer Rail	6	6
Warren Street	Victoria	Northbound	36	36
		Southbound	36	36
	Northern	Northbound	22	23
		Southbound	23	24
Regent's Park	Bakerloo	Northbound	22	21
		Southbound	22	21
TOTAL			216	216

WARREN STREET

- 6.2.10 Warren Street station is located adjacent to the site on the opposite side of Euston Road to the south. The station is approximately 100m away and a two-minute walk. The station is served by the Victoria and Northern line and within TfL fare Zone 1.

EUSTON SQUARE

- 6.2.11 Euston Square station is located to the east of the site on the southern side of Euston Road although can be accessed from both sides of Euston Road. The station is approximately 280m away and a four-minute walk. The station is served by the Metropolitan, Circle and Hammersmith and City lines and is within TfL fare Zone 1.

REGENT'S PARK

- 6.2.12 Regent's Park station is located 550m to the west of the site along the A501 Euston Road, approximately a seven-minute walk. The station is served by the Bakerloo line and is located within TfL fare Zone 1.

EUSTON

- 6.2.13 Euston station is located 600m to the east of the site along the A501 Euston Road, approximately a nine-minute walk. The station is served by the Northern line. The station provides accessible access and is located within TfL fare Zone 1.



KINGS CROSS STATION

- 6.2.14 Kings Cross station is located 1.2km to the east of the site along the A501 Euston Road, approximately a 15-minute walk. The station is served by the Circle, Hammersmith & City, Metropolitan, Northern, Piccadilly, and Victoria lines. The station provides accessible access and is located within TfL fare Zone 1.

NATIONAL RAIL

EUSTON STATION

- 6.2.15 Euston Station is the terminus station for the Avanti West Coast, Caledonian Sleeper, and West Midlands Trains lines. The station provides services to destinations including Birmingham, Milton Keynes, Manchester, Edinburgh, and Glasgow.
- 6.2.16 The station is also served by the London Overground, which provides services to Watford via Willesden Junction and Wembley.

KINGS CROSS STATION

- 6.2.17 Kings Cross station provides services operated by Grand Central, Great Northern, Hull Trains, LNER, and Lumo. The station provides services to destinations including Kings Lynn, Letchworth Garden City, Leeds, Bradford, and Sunderland.
- 6.2.18 Thameslink operations from Kings Cross station provide services to Peterborough and Cambridge via Stevenage.

ST PANCRAS INTERNATIONAL

- 6.2.19 St Pancras International is located adjacent to Kings Cross station and provides services operated by EMR, Eurostar and Thameslink. The station provides services to UK destinations, including St Albans City, Ramsgate, Brighton, Sheffield, Gatwick Airport, Nottingham and Bedford.
- 6.2.20 The station also provides destinations in Europe, including Paris, Amsterdam and Brussels.

TFL OVERGROUND NETWORK


- 6.2.21 Euston station is located 600m to the east of the site along the A501 Euston Road, approximately a nine-minute walk. It is a terminus station of London Overground and provides access to key destinations such as Wembley and Watford.
- 6.2.22 The Overground provides four services per hour in each direction.

PUBLIC TRANSPORT TIME MAPPING

- 6.2.23 Time Mapping (TIM) is a tool developed by TfL within their WebCAT suite of tools to assess connectivity in terms of travel times, taking into account public transport service ranges and interchange opportunities. Time mapping for the site, travelling by public transport during the AM peak, is presented in **Figure 6-5**.



Figure 6-5: TIM mapping



6.3 FUTURE PUBLIC TRANSPORT ACCESSIBILITY

HIGH SPEED 2

- 6.3.1 High Speed 2 train services that will link London to Birmingham and the West Midlands will be departing from Euston station. No opening date for Phase One has been set yet, but services are likely to commence in the late 2020s and early 2030s.
- 6.3.2 There is currently uncertainty following the Government decision to pause most works associated with HS2 at Euston.


CROSSRAIL 2

- 6.3.3 Crossrail 2 is a proposed railway linking rail networks in Hertfordshire and Surrey to central London. Euston St Pancras station to the east of the Proposed Development and Tottenham Court Road to the south are key stations on the proposed route. The project is currently paused, although the land has continued to be safeguarded.

6.4 STRATEGIC HIGHWAY NETWORK

- 6.4.1 The site is located to the northwest of the junction between Euston Road and Hampstead Road, as shown in **Figure 6-6**.

Figure 6-6: Local Road Network



6.5 LOCAL HIGHWAY NETWORK

- 6.5.1 Euston Tower is bounded by the pedestrianised Brock Street to the north and Regent's Place Plaza to the west. To the east, the building is bounded by Hampstead Road and to the south is Euston Road, both of which form part of the Transport for London Road Network (TLRN).
- 6.5.2 Longford Street and Drummond Street provide access to the separate service vehicle ramp and the separate car and cycle ramp to access these facilities at the basement level.
- 6.5.3 Longford Street continues as Drummond Street to the east and intersects with Hampstead Road northeast of the site. Hampstead Road is a section of the A400 that runs from Charing Cross to Archway in north London.
- 6.5.4 Euston Road and Hampstead Road form a signalised junction at the southeast boundary of the site. Both are distributor roads that carry relatively high volumes of traffic.

EUSTON ROAD

- 6.5.5 Euston Road is a 20mph dual carriageway road located south of the site that forms part of the London Red Route and the London Inner Ring Road. It runs in a generally east-west direction, from Marylebone in the west to King's Cross in the east. It is noted that in accordance with 'Vision Zero' and as part of the planned changes by TfL to the London Red Routes, the speed limit of Euston Road will be changed from 30mph to 20mph.
- 6.5.6 In the vicinity of the site, it also forms the northern boundary of the London Congestion Charge (LCC) zone, but the road itself is not part of it.
- 6.5.7 Footpaths provided on either side of Euston Road are wide, and signalised pedestrian crossings are provided at its junction with Hampstead Road, allowing for easy and safe pedestrian movement. Adjacent to the southern boundary of the site, Euston Road also features a bus stop.

HAMPSTEAD ROAD

- 6.5.8 Hampstead Road is a 20-mph two-way single-carriageway located east of the site that forms part of the London Red Route. It runs in a north-south direction, connecting Tottenham Court Road south of the site to Camden High Street in the north.
- 6.5.9 Hampstead Road features a dedicated cycle route and advanced stop lines, allowing cyclists to be segregated from general traffic at junctions. In addition, wide footways are provided on either side of the carriageway, as well as numerous signalised pedestrian crossings provided at regular intervals along the road.
- 6.5.10 The road features numerous mixed-use residential and commercial buildings fronting onto the carriageway.

DRUMMOND STREET

- 6.5.11 Drummond Street is a 20mph two-way single-carriageway road located north of the site that runs in an east-west direction connecting to Euston Road at its eastern end and Longford Street at its Western End.



- 6.5.12 The road features no parking restrictions aside from single white lines along the northern side of the carriageway. The southern side of the carriageway features inset parking bays, allowing vehicles to park on either side of the road without obstructing traffic.
- 6.5.13 Well-maintained footpaths are provided on either side of the carriageway; however, pedestrian crossing locations are few and far between.

LONGFORD STREET

- 6.5.14 Longford Street is located northwest of the site and is a 20mph two-way single-carriageway road running in an east–west direction. It connects to Albany Street at its western end and Drummond Street at its eastern end.
- 6.5.15 The northern side of the carriageway features single yellow line parking restrictions, whilst the southern side of the carriageway features on-street parking bays. The road is fronted by a mixture of residential and commercial properties and provides a zebra crossing at its junction with Laxton Place and an uncontrolled crossing at its junction with Albany Street to assist pedestrian movement in the area.



7 TRAVEL DEMAND AND NETWORK IMPACT

7.1 INTRODUCTION

- 7.1.1 This section quantifies travel demand to determine the likely scale of the effect of the Proposed Development.
- 7.1.2 The Proposed Development will deliver offices and life science uses, along with ancillary retail and public use space. Following comments received from TfL at the pre-application stage, a Maximum office floorspace scenario has also been assessed as offices are occupied at a higher density than life science and will generate a higher number of people trips.
- 7.1.3 The Existing Permitted use of the building has been assessed along with the proposed uses to understand the net increase in trips, but the impact assessment is presented based on a wholly new development, rather than assessed against an increase in floorspace of the permitted use of the building.

7.2 EXISTING SITE PERMITTED TRIP GENERATION

- 7.2.1 The existing site permitted office use travel demand has been estimated using survey data extracted from the Trip Rate Information Computer System (TRICS) database based on the criteria below:
- Land Use – 02/A (Employment/Office)
 - Region – Greater London
 - PTAL - 5+
 - Development Size: 5,000 sqm+
- 7.2.2 For the purpose of this assessment within the TA, all existing floorspace (including the retail units at ground level) has been assessed as office space, which generally generates more trips during the network peak hour.
- 7.2.3 The total person trip rates and person trips for the existing permitted use in the AM and PM peaks are shown in **Table 7-1**.

Table 7-1: Existing Permitted Use - Total Person Trip Rates and Trips

Time Period	Total Person Trip Rates (per 100sqm GFA)			Total Person Trips Forecast		
	In	Out	Total	In	Out	Total
AM Peak hour	2.307	0.202	2.509	1,223	107	1,330
PM Peak hour	0.15	2.152	2.302	80	1,141	1,220
Daily	8.946	8.855	17.801	4,741	4,693	9,435

- 7.2.4 The modal split for journeys to and from the Proposed Development has been calculated using journey-to-work data obtained from the 2011 census (MSOA Camden 021). The public transport mode share is dependent upon the local transport network, which is more accurately obtained from local Census data.



7.2.5 The 2011 census data has been used to calculate the proposed journey-to-work mode share, as the 2021 census was undertaken during the Covid pandemic where the government advised people to work from home. Due to this change in working patterns certain data was not collected and there was an increase in home working from 10.3% in 2011 to 31.2% in 2021, which affected the journey-to-work responses.

7.2.6 Therefore the 2011 data is more representative of the expected mode share and distribution.

7.2.7 **Table 7-2** provides the mode share for the existing permitted use within the Euston Tower.

Table 7-2: Mode Share – Existing Permitted Development

Mode	Permitted Site Use Mode Share
Pedestrians	7%
Cyclists	5%
Bus	11%
Underground	42%
Rail	33%
Car drivers	2%
Car passengers	0%
Total	100%

7.2.8 The resultant number of existing office trips that could be generated by the existing permitted use of Euston Tower is shown in **Table 7-3**.

Table 7-3: Existing Permitted Use Trips by Mode

Mode	AM Peak (08:00-09:00)			PM Peak (17:00-18:00)		
	Arrivals	Departures	Total	Arrivals	Departures	Total
Pedestrians	81	7	88	5	75	81
Cyclists	55	5	60	4	51	55
Bus	133	12	144	9	124	132
Underground	503	44	547	33	469	502
Rail	408	36	444	27	381	407
Car drivers	29	3	32	2	27	29
Car passengers	1	0	2	0	1	1
Total	1211	106	1317	79	1130	1208

7.2.9 **Table 7-3** shows that most trips that could be generated by the existing permitted development will be by public transport.



7.3 PROPOSED TRIP GENERATION

REVISED MODE SHARE

- 7.3.1 **Table 7-4** provides the mode share for the Proposed Development within the Euston Tower. The mode share has been revised to reflect the removal of circa 100 car parking spaces, and the cycle mode share has been revised to reflect the high-quality cycle parking provided at the Proposed Development.

Table 7-4: Revised Mode Share – Proposed Development

Mode	Revised Mode Share (Proposed Development)
Pedestrians	7%
Cyclists	10%
Bus	10%
Underground	40%
Rail	33%
Car drivers	0%
Car passengers	0%
Total	100%

OFFICE TRAVEL DEMAND

- 7.3.2 The trip generation for the office use within the Proposed Development has been calculated using the TRICS database, the same sites and associated trip rates have been used for the existing permitted use of the site.
- 7.3.3 The total person trip rates and person trips in the AM and PM peaks are shown in **Table 7-5**.

Table 7-5: Proposed Development – Office - Total Person Trip Rates and Trips (56,250 sqm)

Time Period	Total Person Trip Rates (per 100sqm GFA)			Total Person Trips Forecast		
	In	Out	Total	In	Out	Total
AM Peak hour	2.307	0.202	2.509	1298	114	1411
PM Peak hour	0.15	2.152	2.302	84	1211	1295
Daily	8.946	8.855	17.801	5032	4981	10013



LIFE SCIENCE TRAVEL DEMAND

7.3.4 The employee density for the laboratory spaces is expected to be at least 50% less compared to the office density. The UK's life sciences have critical mass in Cambridge where a number of technical papers have been produced reviewing employment density produced on behalf of Cambridge City Council. The *Greater Cambridge Employment and Housing Evidence Update (2023)*¹ states:

'Density for lab employees is generally reported as roughly 1:20 sqm NIA (lower than national average closer to 1:30)'

7.3.5 The *Employment Land and Economic Development Study (2020)*² forecasts for commercial premises are set out below:

- *Office (E(g)(i)): an average of 11 sqm NIA and 14 sqm GEA per employee*
- *R&D (E(g)(ii)): an average of 20 sqm NIA and 28 sqm GEA per employee*

7.3.6 The London Employment Sites Database (2021)³ sets out that life science uses are 36 sqm GIA per worker compared to 11.3sqm GIA per worker for office use.

7.3.7 Based on the data set out within the London Employment Sites Database and the guidance documents produced on behalf of Cambridge City Council, a trip rate of 50% of the office trips is appropriate for life science use within the Proposed Development.

7.3.0 The total person trip rates and person trips in the AM and PM peaks are shown in **Table 7-6**.

Table 7-6: Proposed Development – Life Science - Total Person Trip Rates and Trips (24,380 sqm)

Time Period	Total Person Trip Rates (per 100sqm GFA)			Total Person Trips Forecast		
	In	Out	Total	In	Out	Total
AM Peak hour	1.1535	0.101	1.2545	281	25	306
PM Peak hour	0.075	1.076	1.151	18	262	281
Daily	4.473	4.4275	8.9005	1091	1079	2170

OFFICE AND LIFE SCIENCE

7.3.1 The revised model share shown in **Table 7-2** has been applied to the peak hour trips, and the resultant peak hour by mode generated by the proposed office and life science uses is shown in **Table 7-7**.

¹ <https://consultations.greatercambridgeplanning.org/sites/gcp/files/2023-01/EBGCLPDSUEandHEvUJan23v2Jan23.pdf>

² <https://www.greatercambridgeplanning.org/media/1399/greater-cambridge-employment-land-and-economic-development-evidence-study-gl-hearn-nov2020.pdf>

³ https://www.london.gov.uk/sites/default/files/lesd_2021_final_report_22jun2022.pdf



Table 7-7: Proposed Development – Office and Life Science Trips by Mode

Mode	AM Peak (08:00-09:00)			PM Peak (17:00-18:00)		
	Arrivals	Departures	Total	Arrivals	Departures	Total
Pedestrians	108	9	117	7	101	108
Cyclists	156	14	170	10	146	156
Bus	167	15	182	11	156	167
Underground	633	55	689	41	591	632
Rail	514	45	559	33	479	513
Car drivers	0	0	0	0	0	0
Car passengers	0	0	0	0	0	0
Total	1579	138	1717	103	1473	1575

7.3.2 **Table 7-7** shows that most trips generated by the permitted development will be by public transport.

RETAIL USES

EMPLOYEES

- 7.3.3 The London Employment Sites Database (2021), a first principles approach, was used to forecast the number of employees generated by the retail space. One employee per 17.5sqm was applied to the retail area (733sqm GIA) to establish the total number of employees (42).
- 7.3.4 A daily employment occupancy of 85% was applied, resulting in 36 employees travelling to and from the Proposed Development on a given day.
- 7.3.5 The office employee distribution peak hour arrival and departure proportions were applied to the total number of daily retail use employees, and the resultant morning and evening peak hour trips generated by employees of the retail use are shown in **Table 7-8**.



Table 7-8: Retail Employee Peak Hour – Total Trips

Time Period	Arrivals	Departures	Total
AM Peak Hour (0800 - 0900)	17	1	18
PM Peak Hour (1700 - 1800)	1	15	16

7.3.6 The revised model share shown in **Table 7-2** has been applied to the peak hour trips, and the resultant peak hour by mode generated by retail employees is shown in **Table 7-9**.

Table 7-9: Forecast Retail Employee Peak Hour Trips by Mode

Mode	AM Peak Hour (0800-0900)			PM Peak hour (1700-1800)		
	In	Out	Total	In	Out	Total
Pedestrians	1	0	1	0	1	1
Cyclists	2	0	2	0	2	2
Bus	2	0	2	0	2	2
Underground	7	0	7	0	6	6
Rail	5	0	6	0	5	5
Car drivers	0	0	0	0	0	0
Car passengers	0	0	0	0	0	0
Total	17	1	18	1	15	16

RETAIL VISITORS

7.3.7 It is expected that visitor trips will not be new trips generated on the local transport network. Instead, these will be pass-by and local trips on foot generated by the Proposed Development and other existing developments within the local area.

PUBLIC USE – LEARNING CENTRE

EMPLOYEES

7.3.8 A first principles approach was used to forecast the number of employees generated by the public use of learning space. Based on the London Employment Sites Database (2021), a density of 1 employee per 45sqm has been applied to the proposed 2,137sqm (GIA) to establish the total number of employees (47).

7.3.9 A daily employment occupancy rate of 85% has been applied, resulting in 40 daily employees.

7.3.10 The office employee distribution peak hour arrival and departure proportions were applied to the total number of daily public use space employees, and the resultant morning and evening peak hour trips generated by employees of the public use (learning centre space) are shown in **Table 7-10**.

Table 7-10: Public Use Employee Peak Hour – Total Trips

Time period	Arrivals	Departures	Total
AM Peak Hour (0800 - 0900)	19	1	20
PM Peak Hour (1700 - 1800)	1	17	18



VISITORS

- 7.3.11 The public-use learning space has a total person capacity of 390 daily visitors. The learning space may be used for all-day sessions, and on that basis, the peak hour arrival/departure established for employees has been used for the learning facility. **Table 7-11** sets out the total peak hour visitor trips to and from the learning facility.

Table 7-11: Public Use - Learning Centre Visitor Peak Hour - Total Trips

Time period	Arrivals	Departures	Total
AM Peak Hour (0800 - 0900)	155	7	162
PM Peak Hour (1700 - 1800)	7	142	149

TOTAL PUBLIC/LEARNING SPACE TRIP GENERATION

- 7.3.12 The total public use employee and visitor trip generation for the Proposed Development is set out in **Table 7-12**.

Table 7-12: Forecast Public Use – Learning Centre Peak Hour Trips

Time period	Arrivals	Departures	Total
AM Peak Hour (0800 - 0900)	174	7	181
PM Peak Hour (1700 - 1800)	7	159	166

- 7.3.13 The revised model share shown in **Table 7-2** has been applied to the peak hour trips, and the resultant peak hour by mode generated by the learning hub is shown in **Table 7-13**.

Table 7-13: Forecast Public Use – Learning Centre (Employees & Visitors) Peak Hour Trips by Mode

Mode	AM Peak Hour (0800-0900)			PM Peak hour (1700-1800)		
	In	Out	Total	In	Out	Total
Pedestrians	12	1	12	1	11	11
Cyclists	17	1	18	1	16	17
Bus	18	1	19	1	17	18
Underground	70	3	73	3	64	67
Rail	57	2	59	2	52	54
Car drivers	0	0	0	0	0	0
Car passengers	0	0	0	0	0	0
Total	174	7	182	7	159	167

7.4 DELIVERY AND SERVICING TRIPS

- 7.4.1 Servicing trips have been calculated from delivery log data provided by the Regent's Place Management Team. The delivery log provides 24-hour servicing and deliveries to all buildings within Regents Place, and data has been extracted for the occupied office buildings. The data shows Regent's Place campus generates a total of 0.194 servicing vehicle arrivals per 100 sqm per day.
- 7.4.2 The data used is comparable with the TRICS Sites identified in **Table 7-1**, which generate a total of 0.190 servicing vehicle arrivals per 100 sqm per day.



7.4.3 To inform the assessment for the life science deliveries, data from the Francis Crick Institute, located approximately 1.0km to the east, was used. The data provided shows the Crick Institute generate a total of 0.124 servicing vehicle arrivals per 100 sqm per day. The Crick Institute is a purpose-built research building with more than 100 separate research groups and over 2,000 staff and will therefore generate comparable servicing and delivery trips.

7.4.4 The following servicing rates have been applied:

- Office and Learning Space – 0.194 per 100sqm per day;
- Life Sciences – 0.124 per 100sqm per day; and
- Retails uses – 1.35 per 100sqm per day.


7.4.5 **Table 7-14** forecasts the daily servicing trips to the Proposed Development.

Table 7-14: Daily Servicing Vehicles

Land Use	Daily Servicing Trips
Office (Class E)	61
Life Science (Class E)	20
Retail (Class E)	4
Learning Use (Class F1)	5
TOTAL	91

7.4.6 **Figure 7-1** shows a daily profile for the expected servicing demands with 14 vehicles in the peak hour.

Figure 7-1: Delivery and Servicing Trips – Daily Profile



7.4.7 A Draft Delivery and Servicing Plan (DSP) will be implemented to minimise and manage deliveries. The DSP is provided within **APPENDIX C**.



7.5 TOTAL TRIP GENERATION

7.5.1 The forecast trips generated by the Proposed Development for the morning and evening peak hours are shown in **Table 7-15**.

Table 7-15: Total Development Trips by Mode

Mode	AM Peak Hour (0800-0900)			PM Peak hour (1700-1800)		
	In	Out	Total	In	Out	Total
Pedestrians	121	10	131	8	113	121
Cyclists	175	15	190	11	163	174
Bus	188	16	204	12	175	187
Underground	710	59	769	44	661	705
Rail	576	48	624	36	536	572
Car drivers	0	0	0	0	0	0
Car passengers	0	0	0	0	0	0
Total	1770	148	1918	111	1648	1759

7.6 NET DIFFERENCE – EXISTING PERMITTED USE AND PROPOSED DEVELOPMENT

7.6.1 **Table 7-16** and **Table 7-17** compare the AM And PM peak hour trips per mode for the existing permitted use of the building and the Proposed Development.

Table 7-16: Comparison of Permitted Use with The Proposed Development AM Peak Hour

Mode	Permitted Use			Proposed Development			Difference		
	Arrive	Depart	Total	Arrive	Depart	Total	Arrive	Depart	Total
Pedestrians	81	7	88	121	10	131	40	3	43
Cyclists	55	5	60	175	15	190	120	10	130
Bus	133	12	144	188	16	203	55	4	59
Underground	503	44	547	710	59	769	207	15	222
Rail	408	36	444	576	48	623	168	12	179
Car drivers	29	3	32	0	0	0	-29	-3	-32
Car passengers	1	0	2	0	0	0	-1	0	-2
Total	1211	106	1317	1770	146	1916	559	40	599

Table 7-17: Comparison of Permitted Use with The Proposed Development PM Peak Hour

Mode	Permitted Use			Proposed Development			Difference		
	Arrive	Depart	Total	Arrive	Depart	Total	Arrive	Depart	Total
Pedestrians	5	75	81	8	113	120	3	38	39
Cyclists	4	51	55	11	163	174	7	112	119
Bus	9	124	132	12	175	186	3	51	54
Underground	33	469	502	44	661	705	11	192	203
Rail	27	381	407	36	536	572	9	155	165
Car drivers	2	27	29	0	0	0	-2	-27	-29
Car passengers	0	1	1	0	0	0	0	-1	-1
Total	79	1130	1208	111	1648	1758	32	518	550



7.6.2 When compared to the permitted use, there is an increase of circa 600 trips in the AM peak and 550 trips in the PM peak hour.

7.7 SENSITIVITY ASSESSMENT

MAXIMUM OFFICE

7.7.1 Although the Proposed Development is designed to accommodate life sciences on floors 3 – 11 with increased floor to floor heights and additional plant, the proposed Class Use E(g) is flexible and therefore, as a sensitivity test, the life science floors have been assessed as office use for a worst-case demand scenario.

7.7.2 The total person trip rates and person trips in the AM and PM peaks are shown in **Table 7-18**.

Table 7-18: Sensitivity Test – Max Office - Total Person Trip Rates and Trips (80,630 sqm)

Time Period	Total Person Trip Rates (per 100sqm GFA)			Total Person Trips Forecast		
	In	Out	Total	In	Out	Total
AM Peak hour	2.307	0.202	2.509	1,860	163	2,023
PM Peak hour	0.15	2.152	2.302	121	1,735	1,865
Daily	8.946	8.855	17.801	7,213	7,140	14,353

7.7.3 The resultant number of maximum office trips generated by the Proposed Development is shown in **Table 7-19**.

Table 7-19: Sensitivity Test – Maximum Office Trips by Mode

Mode	AM Peak (08:00-09:00)			PM Peak (17:00-18:00)		
	Arrivals	Departures	Total	Arrivals	Departures	Total
Pedestrians	127	11	138	8	119	127
Cyclists	184	16	200	12	172	184
Bus	197	17	214	13	184	197
Underground	746	65	811	49	696	745
Rail	605	53	658	39	564	603
Car drivers	0	0	0	0	0	0
Car passengers	0	0	0	0	0	0
Total	1860	163	2023	121	1735	1856

7.7.4 **Table 7-19** shows that most trips generated by the permitted development will be by public transport.

RETAIL AND PUBLIC/LEARNING SPACE TRIPS

7.7.5 For the Max Office scenario assessment, the retail and public space trips will remain as set out in the sections above.



TOTAL TRIP GENERATION

7.7.6 The forecast trips generated by the Proposed Development for the morning and evening peak hours are shown in **Table 7-20**.

Table 7-20: Sensitivity Test - Max Office - Total Development Trips by Mode

Mode	AM Peak Hour (0800-0900)			PM Peak hour (1700-1800)		
	In	Out	Total	In	Out	Total
Pedestrians	140	12	152	9	131	140
Cyclists	203	17	220	13	189	202
Bus	217	18	236	14	202	216
Underground	823	69	891	52	766	818
Rail	667	56	723	42	621	663
Car drivers	0	0	0	0	0	0
Car passengers	0	0	0	0	0	0
Total	2051	171	2222	129	1910	2039

7.7.7 When compared to the Proposed Development, the Maximum office scenario generates circa 300 additional person trips in the AM and PM peak hours.

SERVICING TRIP GENERATION

7.7.8 For the Max Office assessment, the office servicing and delivery trips set out in 7.4.4 have been applied alongside the retail and public spaces. **Table 7-21** forecasts the daily servicing trips to the Proposed Development.

Table 7-21: Daily Servicing Vehicles

Land Use	Daily Servicing Trips
Office (Class E)	93
Retail (Class E)	4
Learning Use (Class F1)	5
TOTAL	102

7.7.9 The Max Office Scenario assessment shows an additional eleven daily deliveries with two additional delivery vehicles in the peak hour.



7.8 LONDON WIDE IMPACT ASSESSMENT

7.8.1 The development has been vacant for a number of years, and as agreed with TfL during the pre-application stage, the impact assessment is presented based on a wholly new development, rather than assessed against an increase in floorspace of the permitted use of the building.

TRIP DISTRIBUTION AND ASSIGNMENT

7.8.2 As set out above, the 2011 census data has been used to calculate the proposed journey-to-work mode share and distribution, as the 2021 census was undertaken during the Covid pandemic where the government advised people to work from home. Due to this change in working patterns certain data was not collected and there was an increase in home working from 10.3% in 2011 to 31.2% in 2021, which affected the journey to work responses.

7.8.3 Trips are distributed based on 2011 Census origin-destination data for travel to Camden (location of usual residence and place of work by method of travel to work). The most detailed output area for which data is available is at the Middle Level Super Output Area (MSOA) level, which includes the originating trip location for all employees working in Camden.

7.8.4 This is considered to be representative of the distribution of future employees at the Proposed Development and is shown in **Table 7-22**.

Table 7-22: Trip Distribution by Mode and Location for Travel to Camden.

	Area	Underground	Train	Bus	Bicycle	On foot
	Camden	3.3%	0.7%	17.3%	10.1%	61.6%
	Hackney	3.1%	1.7%	10.3%	14.5%	2.8%
	Hammersmith and Fulham	3.4%	0.2%	0.9%	2.1%	0.1%
	Haringey	6.3%	0.5%	10.7%	6.2%	1.0%
	Islington	4.2%	0.6%	16.4%	15.9%	11.4%
Inner London Boroughs (Travel from Borough by Mode)	Kensington and Chelsea	2.1%	0.1%	2.5%	1.9%	0.3%
	Lambeth	7.3%	1.4%	2.5%	6.7%	0.5%
	Lewisham	1.5%	3.5%	1.5%	1.6%	0.2%
	Newham	3.4%	0.9%	0.6%	0.4%	0.1%
	Southwark	3.2%	1.7%	5.7%	5.0%	1.1%
	Tower Hamlets	4.8%	0.2%	1.4%	4.8%	0.7%
	Wandsworth	6.7%	1.9%	1.1%	6.8%	0.1%
	Westminster and the City of London	2.7%	0.3%	10.7%	4.7%	11.4%
	Inner London (subtotal)	51.9%	13.7%	81.6%	80.6%	91.3%
	Outer London	43.0%	33.3%	15.3%	16.7%	4.2%
	Southeast	1.2%	24.8%	1.3%	1.1%	1.3%
	East of England	3.2%	22.3%	0.9%	0.9%	0.9%




Rest of England	0.7%	5.8%	0.8%	0.7%	2.2%
TOTAL	100.0%	100.0%	100.0%	100.0%	100.0%

- 7.8.5 Given that Census data only allows respondents to input their main travel mode, for instances where journeys are likely to be undertaken by multiple modes, trips have been assigned to both the main mode and final mode.
- 7.8.6 Some trips have multiple service or route choices, such as along bus corridors served by multiple routes or where Underground stations are served by two lines. In such instances, trips have been assigned to public transport services based on the frequency and travel time.

BUS NETWORK ASSESSMENT

- 7.8.7 The bus trips are forecast to be 203 and 186 trips in the AM and PM peak hours, respectively. These trips have been distributed based on the origin-destination Census data, as shown in **Table 7-22** and assigned to bus services based on route and frequency.
- 7.8.8 The PTAL assessment identified 19 services that can be used to access the site. Trips to and from the Proposed Development have been assigned manually to the most likely bus service available from the three closest bus stops.
- 7.8.9 In those instances where a bus trip could use one of many services (e.g., along high-frequency corridors), the trips have been split between the different bus services based on service frequency and travel time. For instance, bus trips to Islington have been assigned to the multiple buses available: 29, 30, 73, 134, 205 and 390. The bus routes associated with the closest bus stops are shown in **Figure 7-2**.

Figure 7-2: Bus Routes



7.8.10 The additional bus passenger increase for each service for the Proposed Development is summarised in **Table 7-23**.

Table 7-23: Additional Bus Passengers per Service – Proposed Development

Service	Stop	Peak Hour Frequency	Direction	AM Peak Hour (0800-0900)		PM Peak hour (1700-1800)	
				Arrival	Departure	Arrival	Departure
18	Euston Road	5 minutes	Eastbound	1.7	0.1	0.2	1.6
			Westbound	0.0	0.0	0.0	0.0
24	Hampstead Road	8 minutes	Northbound	1.2	0.1	0.1	1.1
			Southbound	0.8	0.1	0.1	0.7
27	Hampstead Road	10 minutes	Eastbound	1.4	0.1	0.1	1.3
			Westbound	0.0	0.0	0.0	0.0
29	Hampstead Road	6 minutes	Northbound	0.3	0.0	0.0	0.3
			Southbound	2.8	0.2	0.2	2.6
30	Euston Road	10 minutes	Eastbound	1.2	0.1	0.1	1.2
			Westbound	2.6	0.2	0.2	2.4
73	Euston Square	6 minutes	Northbound	0.0	0.0	0.0	0.0
			Southbound	1.2	0.1	0.1	1.2
134	Hampstead Road	9 minutes	Northbound	0.0	0.0	0.0	0.0
			Southbound	4.1	0.3	0.4	3.8
205	Euston Road	10 minutes	Eastbound	1.5	0.1	0.1	1.4
			Westbound	2.1	0.1	0.2	1.9
390	Euston Square	9 minutes	Northbound	0.3	0.0	0.0	0.3
			Southbound	1.8	0.1	0.2	1.7

7.8.11 **Table 7-23** shows the expected bus passengers generated by the Proposed Development is low during the peak hours. On average, 1.3 additional passengers per bus are generated by the Proposed Development, which is equivalent to less than 2% of capacity in the AM and PM peak periods.

SENSITIVITY ASSESSMENT – MAX OFFICE

7.8.12 The sensitivity test shows that an additional 32 trips in the AM peak and 30 trips in the PM will be generated by the Proposed Development. This would equate to an additional 0.2 person trips per bus service which is less than 0.3% of the bus capacity in the AM and PM peak hours.



RAIL TRIPS

- 7.8.13 Although the rail termini are the point where passengers reach central London several other modes of travel will be used to reach the Proposed Development.
- 7.8.14 Census data is based on 'main mode', which is defined as the mode that trips travel the greatest distance on, and therefore, many rail trips will also use the Underground, bus or cycle to access their destination.
- 7.8.15 TfL's Policy Analysis Research Report Central London Rail Termini: Analysing passengers' onward travel patterns (September 2011) investigated onward travel from rail termini and the potential for mode shift to reduce congestion on some parts of the transport network. As part of the Research Report, passengers were surveyed at 13 termini stations in 2010. One of the findings relating to onward distance travelled by modes was that:
- "There is a "tipping point at around 1.5 kilometres, beyond which walking ceases to take account for the majority of trips. Although distance travelled is not the only factor affecting mode share, it is a very significant one which needs to be carefully considered when planning initiatives to achieve mode shift."*
- 7.8.16 It should also be noted that travel patterns vary depending on the rail station. Part Two of the Research Report includes passenger distribution by mode for individual stations. Stations located closest to Camden, such as Kings Cross, Euston and St. Pancras, had particularly high walk mode shares; 70-80% of onward journeys between 1km and 2km were on foot.
- 7.8.17 The onward mode (final mode) of rail trips to the site has been determined based on a review of the travel distance between the rail station and the site, the journey options and information contained within the Research Report.
- 7.8.18 To determine the use of the central London rail termini by rail passengers associated with the Proposed Development, reference has been made to data from the Office of Rail and Road⁴ on the usage of train stations from March 2019 to February 2020 (pre-COVID).
- 7.8.19 The Proposed Development rail trips have been distributed proportionally amongst the busiest Central London Stations, as shown in **Table 7-24**.

⁴ <https://dataportal.orr.gov.uk/statistics/usage/estimates-of-station-usage>



Table 7-24: Proposed Development - Rail Trips – By Station

Rail Station	% Distribution	AM Peak Hour Trips		PM Peak Hour Trips	
		Arrival	Departure	Arrival	Departure
London Bridge	14%	81	7	5	76
London Euston	10%	58	5	4	54
London Kings Cross	7%	42	3	3	39
London Liverpool Street	15%	85	7	5	79
London Paddington	10%	58	5	4	54
London St Pancras	8%	46	4	3	43
London Victoria	16%	95	8	6	88
London Waterloo	19%	112	9	7	104
TOTAL	100%	576	48	36	536

7.8.20 The TfL Report 'Analysing passengers' onward travel patterns' has been used to assess the modes used for onward travel.

7.8.21 The report sets out that onward journeys are made by:

- Underground – 40%
- On Foot – 36%
- Bus – 10%
- Rail – 9%
- Cycle – 2%
- Other – 3%

7.8.22 The mode used for onward travel was linked with the distance travelled, with different modes dominating different distances:

- 90% of trips on foot were less than 2km;
- 87% of bus trips were between 1 and 5 kilometres, and
- 88% of Underground journeys were longer than 2 kilometres.

7.8.23 Based on the modal splits set out within the TfL Report, the onward journey for rail passengers has been split by distance, mode, expected route and destination station or stop, as shown in **Table 7-25**.



Table 7-25: Proposed Development - Rail Trips – Onward Journey by Mode

Station	Distance to Site	Onward Journey Mode	Line/Service	Station/Stop	%age	AM Peak Hour Trips		PM Peak Hour Trips	
						Arrive	Depart	Arrive	Depart
						London Bridge	5.2km	Underground	Northern
London Euston	0.5km	Walk	-	-	100%	58	5	4	54
London Kings Cross	1.5km	Underground	Met/H&C	Euston Square	25%	10	1	1	10
		Bus	30/73/205/390	Uni College Hospital	25%	10	1	1	10
		Walk	-	-	50%	21	2	1	19
London Liverpool St	4.9km	Underground	Circle/Met/H&C	Euston Square	100%	85	7	5	79
London Paddington	2.8km	Underground	Circle/H&C	Euston Square	65%	38	3	2	35
			Bakerloo	Regents Park	25%	14	1	1	13
		Bus	18/27/205	Euston Road	10%	6	0	0	5
London St Pancras	1.5km	Underground	Victoria	Warren Street	25%	12	1	1	11
		Bus	30/73/205/390	Uni College Hospital	25%	12	1	1	11
		Walk	-	-	50%	23	2	1	22
London Victoria	4.0km	Underground	Victoria	Warren Street	100%	95	8	6	88
London Waterloo	3.4km	Underground	Northern	Warren Street	100%	112	9	7	104
TOTAL						576	48	36	536

SENSITIVITY ASSESSMENT – MAXIMUM OFFICE FLOOR AREA

- 7.8.24 The sensitivity test shows that an additional 100 trips in the AM peak and 91 trips in the PM will be generated by the Proposed Development on the rail network.
- 7.8.25 Once the additional trips are separated by arrival/departure station, this equates to a worst case increase of 18 passengers in the AM peak hour at Waterloo Station and 15 additional passengers in the AM peak hour at Victoria Station.
- 7.8.26 Once the additional AM and PM peak hour trips are disaggregated by onward journey mode there is an imperceptible increase on the network.



UNDERGROUND TRIPS

7.8.27 Proposed Development trips that use the London Underground as their main mode have been distributed onto the network based on the analysis shown in **Table 7-22**.

7.8.28 There are several London Underground stations that serve the site (Warren Street, Euston Square, Euston and Regents Park), served by several lines. The analysis calculates the proposed Underground trips per destination station. **Table 7-26** shows the distribution of proposed trips by line and station.

Table 7-26: Proposed Development - Underground Trips by Line and Station

Route/Line	Station	AM Peak Hour Trips	PM Peak Hour Trips	Total	Distribution
Bakerloo	Regents Park	14	13	27	2%
Circle/H&C/Metro	Euston Square	219	202	422	29%
Northern	Warren Street	119	109	228	16%
Northern	Euston	95	87	182	12%
Northern or Victoria	Warren Street	184	169	353	24%
Victoria	Warren Street	130	119	249	17%
TOTAL		762	699	1461	100%

7.8.29 **Table 7-26** shows that 57% of proposed underground trips are expected to use Warren Street Station, 29% will use Euston Square Station, 12% will use Euston Station, and 2% will use Regent's Park Station.

TOTAL UNDERGROUND AND RAIL PASSENGERS

7.8.30 As set out in **Table 7-25** proposed rail trips will use a different mode of onward travel to complete their journey. **Table 7-27** shows the expected underground and rail journeys by London Underground (LU) station.

Table 7-27; Proposed Development - Rail and Underground Trips by LU Station

Station	AM Peak Hour Flows		PM Peak Hour Flows	
	Entry	Exit	Entry	Exit
Regents Park	1	13	12	1
Euston Square	29	331	309	22
Warren Street	59	666	621	44
Euston	17	188	176	12

7.8.31 The assessment robustly assumes that all trips are new to these underground routes, whereas many workers will be relocating from other central London areas and will therefore already be on the public transport network.



SENSITIVITY ASSESSMENT – MAX OFFICE

UNDERGROUND TRIPS

7.8.32 The sensitivity test shows that an additional 123 trips in the AM peak and 113 trips in the PM will be generated by the Proposed Development on the underground network.

7.8.33 Based on the assessment set out in **7.8.28**, **Table 7-28** shows the distribution of proposed trips by underground line and station.

Table 7-28: Sensitivity Test – Max Office - Underground Trips by Line and Station

Route/Line	Station	AM Peak Hour Trips	PM Peak Hour Trips	Total	Distribution
Bakerloo	Regents Park	17	16	32	2%
Circle/H&C/Metro	Euston Square	257	236	494	29%
Northern	Warren Street	138	127	265	16%
Northern	Euston	111	102	214	12%
Northern or Victoria	Warren Street	215	197	412	24%
Victoria	Warren Street	152	140	292	17%
TOTAL		891	818	1709	100%

TOTAL RAIL AND UNDERGROUND PASSENGERS

7.8.34 **Table 7-27** shows the expected underground and rail journeys by London Underground (LU) station.

Table 7-29; Sensitivity Test – Max Office - Rail and Underground Trips by LU Station

Station	AM Peak Hour Flows		PM Peak Hour Flows	
	Entry	Exit	Entry	Exit
Regents Park	1	13	12	1
Euston Square	29	331	309	22
Warren Street	59	666	621	44
Euston	17	188	176	12

7.8.35 Warren Street station is expected to accommodate the majority of the underground trips to and from the Proposed Development with over 55% of all proposed underground trips using the station.

7.8.36 The assessment robustly assumes that all trips are new to these underground routes, whereas many workers will be relocating from other central London areas to the Proposed Development and will therefore already be on the public transport network.




7.9 WARREN STREET STATION ASSESSMENT

- 7.9.1 Warren Street Station is the closest station to the Proposed Development, and it is expected to have an additional 725 trips during the AM peak hour through the station. An assessment has been undertaken on the gate line and escalators at the station to assess the impacts of the Proposed Development.
- 7.9.2 Warren Street station has ten gates, of which eight are standard, and two are wide gates. There are three escalators for access between the ticket hall and platform level.
- 7.9.3 The following assessment and analysis were presented to TfL during the pre-application process, where it was reviewed within TfL and concluded that there is currently capacity on the network to accommodate the demand associated with the development. LUL were content with both the gate line and escalator assessment.

CURRENT STATION USAGE


- 7.9.4 2022 TfL Numbat Data was used to assess the current station usage. **Figure 7-3** shows the hour flows entering and exiting the station. Based on the latest Numbat data, the average Tuesday, Wednesday, and Thursday flows are higher than both the Monday and Friday flows, suggesting work pattern changes post-pandemic. The figure also demonstrates two significant peaks associated with commuter travel.

Figure 7-3: Warren Street Station Hourly Flows



- 7.9.5 As mentioned above, Warren Street station is associated with commuter travel and, as shown in **Figure 7-4**, is highly tidal with AM peak hour station exits and PM peak hour entries. The figure also demonstrates a small amount of interchange between the Northern and Victoria Lines, which do not pass the gate line.

Figure 7-4: Warren Street Station - Entry, Exit and Interchange Flows




7.9.6 The busiest 15-minute period in the AM peak shows 1,473 station entries and exits (approx. 98 people per minute), and the PM peak shows 1,364 station entries and exits (approx. 91 people per minute)

STATION USAGE - 2019 TO 2022 COMPARISON

7.9.7 To understand the changes to travel patterns and the usage at Warren Street Station pre and post-pandemic, the 2019 station flows were compared to the 2022 flows, as shown in **Figure 7-5**.

Figure 7-5: Warren Street – 2019 vs 2022 flows



7.9.8 The total station flows are 32% lower in the AM peak, 38% in the PM peak and 31% over the day.

WIDER LONDON UNDERGROUND NETWORK ASSESSMENT


7.9.9 An assessment of the 2019 and 2022 Numbat data for total entry and exits across the entire London Underground Network shows a fall in usage of 17%. Warren Street station shows a fall of over 30% in total station entry/exit flows, which can partly be attributed to changes in working patterns post-pandemic and significant permanent changes to the network, i.e. the Elizabeth Line fully opening in May 2022, which has had impacts on travel patterns.

7.9.10 **Figure 7-6** demonstrates the percentage change between 2019 and 2022 in entry/exit flows in London Underground stations within 750m of the Elizabeth Line.

7.9.11 The figure shows that total entry/exit passenger flows at all Elizabeth Line stations have increased. Usage at the majority of other stations within the buffer zone has decreased between 30-40% from 2019 data. This demonstrates that on top of the change in working patterns and a reduction of 17% in total usage, these stations have experienced a shift in travel patterns linked to the Elizabeth Line.

7.9.12 Therefore, if working patterns do revert close to 2019 levels, the permanent changes to the network mean that several stations will still be well below the passengers flows that were experience in 2019, with Warren Street being one of those stations.

Figure 7-6: Elizabeth Line Impact



GATE LINE ASSESSMENT

2022 EXISTING STATION FLOWS

7.9.13 The gate line assessment is shown in **Table 7-30** based on the 2022 existing Warren Street Station entry and exit flows.

Table 7-30: Gate Line Assessment – 2022 Existing Station Flows

UTS Gate line Requirement		
	AM	PM
Entry Flow 5 min	58	427
Total Exiting Passengers	183	42
In Gates	0.5	3.4
Out Gates	3.7	0.8
In Gates (rounded)	1	4
Out Gates (rounded)	4	1
n=platform clearance time (min)	2	2
X (Extra Gates required)	1	1
Number of Gates Required	6	6
WAG Requirement		
Size of gate line	Lower boundary of the gate line	Minimum number of Wide gates
up to 6 (unidirectional gate line only)	1	1
up to 12	7	2
up to 18	13	3
more than 18	19	4
Required number of gates (Max. of AM and PM)		6
Minimum Wide aisle gates required		2

7.9.14 As shown in **Table 7-30**, six gates are required to accommodate the existing 2022 station flows. Warren Street Station currently provides ten gates and is therefore working well within capacity.



2022 EXISTING STATION FLOWS PLUS PROPOSED DEVELOPMENT

7.9.15 **Table 7-31** shows the Warren Street Station gate line assessment based on the existing 2022 station flows plus the Proposed Development flows.

Table 7-31: Gate Line Assessment – 2022 Existing Station Flows Plus Proposed Development

UTS Gate line Requirement		
	AM	PM
Entry Flow 5 min	64	485
Total Exiting Passengers	206	48
In Gates	0.5	3.9
Out Gates	4.1	1.0
In Gates (rounded)	1	4
Out Gates (rounded)	5	1
n=platform clearance time (min)	2	2
X (Extra Gates required)	1	1
Number of Gates Required	7	6
WAG Requirement		
Size of gate line	Lower boundary of the gate line	Minimum number of Wide gates
up to 6 (unidirectional gate line only)	1	1
up to 12	7	2
up to 18	13	3
more than 18	19	4
Required number of gates (Max. of AM and PM)		7
Minimum Wide aisle gates required		2

7.9.16 As shown in **Table 7-31**, seven gates are required to accommodate the existing 2022 station flows plus the Proposed Development. Warren Street Station currently provides ten gates and can therefore accommodate the additional Proposed Development flows within the existing gate line capacity.



2022 BASE WITH MAXIMUM OFFICE FLOWS

7.9.17 **Table 7-32** shows the Warren Street Station gate line assessment based on the existing 2022 station flows, plus, the maximum office scenario development flows.

Table 7-32: Gate Line Assessment – 2022 Existing Station Flows Plus Max Office Flows

UTS Gate line Requirement		
	AM	PM
Entry Flow 5 min	65	495
Total Exiting Passengers	209	49
In Gates	0.5	4.0
Out Gates	4.2	1.0
In Gates (rounded)	1	4
Out Gates (rounded)	5	1
n=platform clearance time (min)	2	2
X (Extra Gates required)	1	1
Number of Gates Required	7	6
WAG Requirement		
Size of gate line	Lower boundary of the gate line	Minimum number of Wide gates
up to 6 (unidirectional gate line only)	1	1
up to 12	7	2
up to 18	13	3
more than 18	19	4
Required number of gates (Max. of AM and PM)		7
Minimum Wide aisle gates required		2

7.9.18 As shown in **Table 7-32**, seven gates are required to accommodate the existing 2022 station flows plus the flows generated by the maximum office scenario. Warren Street Station currently provides ten gates and can therefore accommodate the additional maximum office scenario flows within the existing gate line capacity.



ESCALATOR ASSESSMENT

7.9.19 An assessment has been undertaken to review the escalator throughput for the 2022 base, 2022 base plus development flows and 2022 base plus sensitivity flows. There are currently three escalators at Warren Street which are appropriate to accommodate all assessed scenarios. The escalator assessment is shown in **Table 7-33**.

Table 7-33: Warren Street Station – Escalator Assessment

Escalator Assessment	2022 Base		2022 Base + Dev		2022 Base + Sen	
	AM	PM	AM	PM	AM	PM
Peak 15-minute exit flow	1327	298	1489	343	1517	351
Per minute average	88	20	99	23	101	23
Escalators required	0.88	0.20	0.99	0.23	1.01	0.23
Escalators required	1	1	1	1	1	1
Peak 15-minute entry flow	146	1067	160	1213	163	1237
Per minute average	10	71	11	81	11	82
Escalators required	0.10	0.71	0.11	0.81	0.11	0.82
Escalators required	1	1	1	1	1	1
Total Escalators Required	2	2	2	2	2	2

7.9.20 As shown in **Table 7-33**, there are sufficient escalators to accommodate the assessed scenarios, with two escalators required during each peak period.

WARREN STREET STATION ASSESSMENT SUMMARY

7.9.21 As shown in the assessment above the current Warren Street station configuration of ten gates and three escalators can accommodate the additional flows expected to be generated by the Proposed Development.

7.9.22 As set out in Paragraphs **7.9.9** to **7.9.12**, the permanent changes to the underground network with the opening of the Elizabeth Line mean that travel patterns have changed and Warren Street is expected to have additional station capacity.



7.10 CYCLE HIRE DOCKING STATION ASSESSMENT

7.10.1 Following the pre-application response from TfL. There is a request for a contribution to:

Expand Cycle Hire capacity by creating a new docking station with the red line boundary.

7.10.2 **Figure 7-7** shows the location of the nearest cycle hire stations as well as the publicly accessible short-stay cycle parking.

Figure 7-7: Existing Cycle Hire Locations




7.10.3 There are four cycle hire docking stations within 400m of the site with the closest located on the eastern footway of Hampstead Road adjacent to the Proposed Development. Between them, they offer access to 120 cycles. The locations of the docks and their capacity are:

- Hampstead Road, Euston (54 bicycles)
- Longford Street, The Regent's Park (21 bicycles)
- Bolsover Street, Fitzrovia (19 bicycles)
- Warren Street station, Euston (26 bicycles)

7.10.4 Cycle Hire usage data has been extracted from public TfL data⁵ for the latest available month (22nd May 23 to 18th June 23). The data provides the date and time of each hire, along with the starting station, end station and duration of hire period.

7.10.5 Where the starting or end station is Hampstead Road or Warren Street, this data has been extracted to produce a monthly arrival and departures profile by day as shown in **Figure 7-8** and **Figure 7-9**.

Figure 7-8: Hampstead Road Docking Station – Daily Usage



⁵ cycling.data.tfl.gov.uk



Figure 7-9: Warren Street Docking Station – Daily Usage



7.10.6 The Hampstead Road hire station which consists of 56 docks has an average weekday daily usage of 41 arrivals and 40 departures. Warren Street hire station consists of 26 docks and has an average weekday daily usage of 84 arrivals and 85 departures.

7.10.7 A midweek (Tuesday, Wednesday and Thursday) hourly profile was extracted from the from the data to understand the average arrival and departure profile over a 24-hour period for both the Hampstead Road Warren Street docking station which are shown in **Figure 7-10** and **Figure 7-11**.

Figure 7-10: Daily Profile and Accumulation – Hampstead Road






Figure 7-11: Daily Profile and Accumulation – Warren Street



- 7.10.8 The Hampstead Road docking station shows a flat daily profile with a balanced number of docks and hires over the day, whereas the Warren Street profile shows a number of hires during the morning peak and a number of docks during the afternoon peak.
- 7.10.9 The daily profile for Warren Street suggests that it is used by commuters linked to Warren Street Station (AM hires and PM docks) and it would not be expected that employees or visitors to the Proposed Development will use the Warren Street docking station.
- 7.10.10 The latest figures provided by TfL in **Figure 7-12** show that cycle hire in September 2023 was down circa 35% per cent, compared to September 2022 and it is the lowest number since 2013, when fewer bikes and docking stations were available.⁶

⁶ <https://www.bbc.co.uk/news/uk-england-london-66541858>

Figure 7-12: TfL Cycle Hire Usage



- 7.10.11 The drop in usage of the TfL cycles could be attributed to two factors, the TfL hire charges were raised in September 2022, and the growth of other cycle hire operators such as Lime, Human Forest, Tier etc which offer electric bikes.

SUMMARY

- 7.10.12 It is not expected that employees or visitors to the Proposed Development will use the Warren Street cycle hire station, as the Hampstead Road docking station is adjacent to the development.
- 7.10.13 A small number of employees or visitors to the Proposed Development will use one of the cycle hire schemes available. As shown in the latest TfL data on cycle hire usage, the number of hires and docks is reducing. This will mean that fewer employees or visitors will use the docking station, which will increase the space capacity should employees or visitors wish to use it.
- 7.10.14 It is therefore unnecessary to provide a contribution to a new docking station when the data provided by TfL shows a significant reduction in use. The Hampstead Road docking station is currently underutilised with sufficient capacity to accommodate any increase in usage associated with the Proposed Development.



7.11 IMPACT ON LOCAL ROAD NETWORK

- 7.11.1 The Proposed Development is car-free and will generate negligible vehicle trips. The Proposed Development removes circa 100 car parking spaces within the basement and therefore reduce traffic generation when compared to the permitted use of the site.
- 7.11.2 A total of 14 delivery and servicing vehicles are forecast in the peak hour (10:00-11:00), as set out in **Section 7.4**.
- 7.11.3 The Proposed Development will have a negligible impact on the local highway network.


7.12 LOCAL HIGHWAY IMPROVEMENTS

TfL– FUTURE OF TEMP - HAMPSTEAD ROAD

- 7.12.1 As part of the TfL improvements to sustainable travel, minor works are proposed on Hampstead Road between its junctions with Euston Road and Drummond Street. The proposed works include:
- A relocated northbound bus shelter;
 - Minor northbound kerb works;
 - Northbound cycle lane extended circa 20m to the south;
 - New southbound bus stop, and shelter

- 7.12.2 An extract from TfL drawing number STPJ271C-ARC-010-02_01-DRG-HE-00002-C01 is shown in **Figure 7-13**.

Figure 7-13: Extract from Future of Temp – Hampstead Road



- 7.12.3 It is understood that these works are being delivered by TfL in Q4 of 2023 and are not part of the development proposals.

TFL EUSTON CIRCUS/HAMPSTEAD ROAD – GREENING OPTIONS

7.12.4 A Future Greening scheme is currently being developed by TfL which seeks to improve the Euston Circus junction and the Hampstead Road environment by providing additional greening along with improvements for pedestrians, cyclist and bus users.

7.12.5 **Figure 7-14** is TfL's outline proposals for potential greening options on the Hampstead Road corridor adjacent to the Site. The works include revisions to the north and southbound bus stops, kerb works at the Euston Circus junction and greening improvements at both the junction and Hampstead Road.

Figure 7-14: TfL Hampstead Road – Proposed Greening Scheme



7.12.6 Although these works are not related to the Proposed Development, discussions are taking place with TfL over the mechanism of delivering improvement works to the footways adjacent to the site which form part of the Transport for London Road Network.

7.13 MANAGEMENT STRATEGIES

7.13.1 A number of management plans will be implemented to ensure the Proposed Development encourages sustainable travel and operates efficiently. It is expected that these plans will be secured by planning conditions or obligations.

OUTLINE TRAVEL PLAN

7.13.2 As part of this application, an Outline Travel Plan (TP) has been prepared in accordance with TfL and DfT guidance, which sets out a range of preliminary management strategies and measures to support and encourage sustainable travel.

7.13.3 The overall aim/objective of any TP should be to minimise the impact of travel on the local and wider environment and to promote sustainable travel choices, such as walking, cycling and public transport.

7.13.4 The TP identifies the requirement for specific travel plans to be developed upon occupation of the site.

DRAFT DELIVERY & SERVICING PLAN

- 7.13.5 A Draft Delivery & Servicing Plan (DSP) will be prepared, setting out a management strategy to ensure the site can be serviced in an efficient and safe manner.
- 7.13.6 A DSP has been produced to support the planning application as a standalone document in order to manage refuse, delivery and service vehicle arrangements and overall accessibility. While it is recognised this will be a live document that will need to be adapted over the life of the development, the DSP sets out a range of management strategies and measures to ensure the site can be readily serviced in an efficient and safe manner without inconveniencing others.

CAR PARKING DESIGN AND MANAGEMENT PLAN

- 7.13.7 A Car parking Design and Management Plan (CPDMP) will be prepared, setting out a management strategy to ensure the proposed accessible parking on site can be designed and managed in an efficient and safe manner.

OUTLINE CONSTRUCTION LOGISTICS PLAN

- 7.13.8 An Outline Construction Logistics Plan (CLP) has been prepared setting out a construction logistics strategy to ensure the site can be accessed in an efficient and safe manner.
- 7.13.9 Ahead of deconstruction and construction, a contractor will be appointed who will ensure that a detailed CLP is prepared to satisfy planning conditions to secure its production prior to the commencement of any works. This will be prepared in accordance with TfL Construction Logistics Plan Guidance.
- 7.13.10 The detailed CLP will provide the necessary vehicle swept path drawings to confirm the safe site access/egress and manoeuvrability within the site for deconstruction and construction by various vehicle types, including any abnormal loads.



8 OUTLINE CONSTRUCTION LOGISTICS PLAN

8.1 INTRODUCTION

- 8.1.1 This section of the TA sets out the Outline Construction Logistics Plan (CLP) to support the planning application. It summarises the key transport-related matters during the construction works of the Proposed Development.
- 8.1.2 A detailed CLP will be prepared before construction and implemented and monitored throughout the construction programme.
- 8.1.3 An appropriate planning condition will secure the requirement for a detailed CLP, which will be prepared following TfL's Construction Logistics Planning Guidance (the 'Guidance') before the commencement of deconstruction and construction.

8.2 CONSTRUCTION LOGISTICS PLANNING POLICY

- 8.2.1 Relevant local and regional planning policies and guidance have been reviewed to provide context for deliveries and servicing concerning the development proposal.

LONDON PLAN (2021)

- 8.2.2 The London Plan is part of the statutory development plan and aims to ensure that London's transport is easy, safe, and convenient for everyone and actively encourages more walking and cycling.
- 8.2.3 Policy T7, 'Freight and Servicing', states that Construction Logistics and Delivery and Servicing Plans will be required and should be developed in accordance with Transport for London guidance and in a way that reflects the scale and complexities of developments.

TFL CONSTRUCTION LOGISTICS PLAN GUIDANCE

- 8.2.4 TfL issued the Guidance to ensure that CLPs of high quality are produced to minimise the impact of construction logistics on the road network.
- 8.2.5 The Guidance focuses on reducing the impact of construction in terms of the following:
- environmental impact: lower vehicle emissions and noise levels;
 - road risk: improving the safety of road users;
 - congestion: reduced vehicle trips, particularly in peak periods, and
 - cost: efficient working practices and reduced deliveries.
- 8.2.6 CLPs provide a framework for understanding and managing construction vehicle activity into and out of the Proposed Development and should detail:
- the amount of construction traffic generated;
 - the routes the construction vehicles will use and consideration of local impacts;
 - the impact on relevant community considerations, and
 - any traffic management that will be in place.



8.2.7 The Guidance states that an Outline CLP should be provided which gives the planning authority an overview of the expected logistics activity during the construction programme. A detailed CLP is submitted to a planning authority pursuant to and in the discharge of a condition imposed on the planning permission. It provides the planning authority with the logistics activity expected during the construction programme.


8.2.8 The Guidance suggests a range of measures and strategies that should be considered to reduce the impact of construction on the local environment.

CONTEXT PLANS

8.2.9 **Figure 8-1** shows the location of the Proposed Development in a regional context, including:

- Strategic roads that are likely to be used to access the Site; and
- Community considerations (i.e., stations and greenspace).

Figure 8-1: Site Location Within a Regional Context



8.2.10 **Figure 8-2** shows the location of the site in relation to the surrounding local area. **Figure 8-3** shows the site boundary plan showing the extent of footways, other buildings, cycle lanes and road markings



Figure 8-2: Site Located in the Context of the Local Transport Network





Figure 8-3: Planning Application Boundary Plan (Ground floor)



8.3 OBJECTIVES

8.3.1 The overall objectives of the CLP are to:

- **Lower emissions;**
- **Enhance safety** – improve vehicle and road users' safety; and
- **Reduce congestion** – reduce trips overall, especially in peak periods.

8.3.2 To support the realisation of these objectives, several sub-objectives are provided:

- Encourage construction workers to travel to the Site by non-car modes;
- Promote smarter operations that reduce the need for construction travel, or that reduce or eliminate trips in peak periods;
- Encourage the use of greener vehicles and sustainable freight modes;
- Manage the ongoing development and delivery of the CLP with construction contractors;
- Communicate Site delivery and servicing facilities to workers and suppliers; and
- Minimise queueing and disrupting the traffic along the surrounding roads.

8.4 CONSTRUCTION PROGRAMME

8.4.1 Planning for deconstruction and construction is understandably at a preliminary stage and may be subject to review and modification during detailed construction planning. For this reason, the following information is based on reasonable assumptions in the construction programme and the collective experience of the consulting team with similar projects. Nevertheless, the indicative programme at this stage is representative of a programme that is reasonable and achievable. The programme presents the likely sequence of activities, site logistics and the mitigation measures that will be implemented.

8.4.2 The development will be delivered over three main phases:

- Phase 1 – Site set up and Deconstruction to Ground Level
- Phase 2 – Enabling and substructure works and
- Phase 3 – Superstructure, envelope, and fit-out

8.4.3 The construction programme is expected to be of the order of 60 months. **Table 8-1** and **Figure 8-4** outlines the main activities to be undertaken and the approximate duration of the works. Some activities will occur concurrently. A copy of the indicative construction programme is provided in **APPENDIX G**.

Table 8-1: Indicative Sequence of Works and Estimated Duration

Construction Task/Activity	Start Date (Quarter and Year)	Completion Date (Quarter and Year)	Duration
Site Set-up and Deconstruction Works	Q1 2025	Q4 2026	24 months
Substructure – Piling and Basement Walls	Q1 2026	Q2 2027	14 months
Superstructure (slabs and steelworks)	Q3 2027	Q3 2029	27 months



Cladding	Q3 2027	Q2 2030	31 months
Finishes and Fitout	Q2 2027	Q1 2030	36 months
Testing and Commissioning	Q3 2029	Q2 2030	11 months
External Works (Landscaping and public realm)	Q2 2029	Q4 2029	8 months

Figure 8-4: Indicative Construction Programme

PROGRAMME	Duration (months)	2025				2026				2027				2028				2029				2030			
		Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Site Set Up & Demolition Works	24	Feb 25							Nov 26																
Excavation	4				Oct 25	Jan 26																			
Piling & Basement Walls	14					Feb 26							Apr 27												
Super structure - Slabs	27												Apr 27												July 29
Super structure - Steelwork	27												Apr 27												July 29
Cladding	31													Sept 27											Apr 30
Finishes and Fit out	36												Apr 27												Apr 30
Testing & Commissioning	11																							Aug 29	Jun 30
Landscape (Public Realm)	8																						May 29	Dec 29	

8.5 CONSTRUCTION METHODOLOGY

8.5.1 Prior to the commencement of any site works, all occupiers surrounding the site will be notified in writing of the nature and duration of the works to be undertaken. The name and contact details of the person responsible for the site works will be included in the introductory letter, and this will be used for all enquiries and complaints for the entire duration of the works. Updates of work will be provided regularly, and any complaints will be properly addressed as quickly as possible as part of the Contractor's commitment to the Considerate Contractors Scheme.

8.5.2 The safety of the public and protection of pedestrians will be provided for at all times by having the construction area, materials storage areas and waste storage areas either hoarded or fenced with lockable access. Relevant signage will be erected to ensure adequate warning/information regarding the health and safety of the public.

ENABLING WORKS

8.5.3 All construction site boundaries will be enclosed by clean, safe and well-maintained hoardings. These hoardings will be designed to allow the displaying of relevant signage and notice boards to ensure good communication with the local neighbourhood. Low-voltage bulkhead lights will be installed as part of the hoardings to ensure footpaths, signage, and notice boards are well-lit.

8.5.4 During this period, the office welfare accommodation will be set up along with access routes and temporary services.

DECONSTRUCTION

8.5.5 The initial period of the deconstruction programme will involve the installation and setup of the principal temporary works required for the deconstruction, namely a tower crane situated on top of the existing reinforced concrete lift core structure and the installation of a descending screen at the roof level, supported by a framework to enable the removal of the existing cladding.



- 8.5.6 As the works commence, the product of the deconstruction work will be moved to the ground level and basement levels for removal from the site. Deconstruction arisings will be transported to the basement level through an existing satellite lift shaft fitted with baffles, and demounted glass and metal mullions will be transported to ground level in a hoist situated in another satellite lift shaft.
- 8.5.7 Deconstruction arisings will be removed from the basement via eight-wheeled tipper vehicles that access the area from the Regent's Place Service Yard entrance on Longford Street, whereas demounted cladding and the like will be transported from the site via ground-level access from the Euston Road exit slip road entrance.

ENABLING WORKS AND SUBSTRUCTURE

- 8.5.8 As the deconstruction works progress, the ground to the second-floor structure will be removed, leaving the cross shape of the original building, known as the pinwheel, in place. Once this 'podium' structure is removed, the ground-level slab will be removed to open the existing basement to blue sky.
- 8.5.9 It is currently anticipated that the basement wall to the south and east elevations will require support in the temporary condition.
- 8.5.10 Following the removal of the ground-level slab and the grubbing out of the existing basement slab construction, a piling mat will be installed, from which new piles will be installed. This will include piles for tower crane bases and the like. Once the piling works are completed and tower cranes installed as required, pile cap/raft construction will follow as the deconstruction works of the existing pinwheel to the basement level conclude.
- 8.5.11 As the pile cap/raft slab works continue, the construction of vertical elements to the underside of the proposed ground-level slab will follow, as will the ground-level slab itself.
- 8.5.12 In addition to deconstruction works, it is anticipated that an element of enabling works for the proposed steelwork substructure will be incorporated into the central core as the deconstruction lowers the existing building.

SUPERSTRUCTURE, ENVELOPE AND FITOUT

- 8.5.13 Upon completion of the ground floor, superstructure steelwork and precast floor plank installation will commence.
- 8.5.14 Steelwork will be installed over three levels to accommodate the fascia bracing to the structure, followed by three levels of precast plank installation to provide the floor structure. This process will continue to rise up the building, utilising the tower cranes for installation.
- 8.5.15 Once the superstructure has reached an appropriate height, the installation of the unitised cladding panels will commence to follow the superstructure steelwork and precast planks.
- 8.5.16 Mechanical and electrical installation will occur concurrently with the superstructure and cladding works, and fitout works will follow once a floor is enclosed and weathertight.
- 8.5.17 Following the completion of the superstructure and cladding works, the external cranes and hoists will be dismantled.



EXTERNAL WORKS/LANDSCAPING

- 8.5.18 External works and landscaping for the Proposed Development will be undertaken at the end of the construction programme. Along with the proposed landscaping and public realm works, making good of any temporary arrangements and/or any damage to footpaths surrounding the site may be required.

8.6 SITE LOGISTICS


- 8.6.1 The efficient management of the Site logistics will be vital to the project's success. A key logistics strategy for a construction project is to ensure that the products and materials arrive on-site at the time and in the required quantities.
- 8.6.2 The contractors will ensure that the necessary pre-planning is undertaken and that the quality of the communication between those planning the project and those supplying the products and materials is maintained throughout the project.

8.7 VEHICLE ROUTING

- 8.7.1 The contractor will use designated construction traffic routes for deliveries to the Site, waste removal, etc.
- 8.7.2 Access routes to and from the Site to be used by HGVs will be agreed upon with LBC and TfL before the initiation of the construction programme via the detailed CLP to minimise disruption to the road and pedestrian network. The strategic road network will be used as far as possible to reach the Site.
- 8.7.3 During all phases, access to the Site will be from Longford Street (Rigid HGV basement access only), Euston Road and Hampstead Road.
- 8.7.4 It is anticipated that the primary routes for construction traffic will be Euston Road and Hampstead Road. All vehicles will enter or exit the Site area from the Strategic Road Network (SRN) via the M25, M4 or the M1, or via the Transport for London Road Network to and from the Site. Using the SRN and TLRN are the most appropriate routes for construction vehicles and the addition of the expected construction traffic numbers associated with the Proposed Development will lead to an imperceptible change on these heavily trafficked routes.




Figure 8-5: Regional Routing Plan



- 8.7.5 The regional plan in **Figure 8-5** shows the access from the Strategic Road Network (M4 and M1) via the A40 and A41. Local entry access is then via Euston Road to the site or Longford Street to access the existing basement. Egress is via Hampsted Road to the north and connecting to the Strategic Road Network via the A1.
- 8.7.6 The route avoids local residential streets and TfL designated cycle routes. It provides the most appropriate routing for access to the site.
- 8.7.7 All delivery vehicles to the Site will be informed by the contractor (once appointed) of the access strategy and requested to follow these routes (rather than other local residential roads) depending on the direction in which the respective deliveries originate.
- 8.7.8 **Figure 8-6** shows the proposed local vehicle routing.



Figure 8-6: Proposed construction vehicle routes



- 8.7.9 Once the contractor is appointed, further opportunities to maximise vehicle access to the Site will be investigated to reduce the construction programme and mitigate associated impacts.
- 8.7.10 These will be included within the submitted detailed Construction Environmental Management Plan and/or the Construction Traffic Management Plan, which are expected to be secured by a planning condition. A Draft Construction Management Plan Camden Proforma has been submitted with the planning application.




8.8 CONSTRUCTION LOGISTICS STRATEGY OPTIONS

SITE CONSTRAINTS

- 8.8.1 The Site is bound by Euston Road off slip (eastbound) to the south, Hampstead Road (two-way) to the east, Brock Street to the north and Regent's Place Plaza to the west both of which are pedestrianised.
- 8.8.2 Hampstead Road to the east of the Site comprises four traffic lanes, made up of a northbound bus and cycle lane, and a general traffic lane. Southbound is the same configuration with a shared bus and cycle lane and one general traffic lane. Adjacent to the northeast of the corner of the Site, the northbound Hampstead Road bus stop and flag are located as shown in **Figure 8-7**.
- 8.8.3 Vehicle access via Brock Street is restricted due to the existing Hampstead Road bus stop, the tree of importance (Category A) and overhangs from neighbouring buildings as shown in **Figure 8-7**.

Figure 8-7: Hampstead Road Bus Stop




- 8.8.4 Euston Road off-slip to the south comprises three eastbound traffic lanes. The left flare comprises Bus Stop KA Warren Street and is a left turn only flare. The middle lane is straight on to Euston Road on-slip and North Gower Street. The right lane is straight on and right to Euston Road and Gower Street south. The Euston Road off-slip bus stop and shelter are shown in **Figure 8-8**.

Figure 8-8: Euston Road off-slip Bus Stop



8.8.5 The Regent's Place Plaza to the west of the Site has a 5T weight restriction over the basement below restricting vehicle access to the Site as shown in Figure 8-9.

Figure 8-9: Indicative Estate wide Loading Plan




8.8.6 Due to constraints within the basement, vehicle access is restricted to rigid HGVs with a maximum height of 4.1m.



8.8.7 Based on vehicle access constraints to the Site, the Euston Road off-slip to the south and Hampstead Road to the east are the only vehicle access locations that can accommodate the articulated vehicles that are necessary during construction.

8.8.8 **Figure 8-10** shows the existing site constraints in terms of ground level vehicle access.

Figure 8-10: Existing Site Constraints



OPTION A – TRITON SQUARE, REGENTS PLACE PLAZA AND TLRN ACCESS

ACCESS SUMMARY

8.8.9 **Option A** proposes the use of Triton Square and Regent's Place Plaza as the vehicle access, manoeuvring and loading/unloading area. As the proposed deconstruction and construction requires access from two sides to make the most efficient use of the tower cranes, entry would also be required from Euston Road off-slip with exit onto Hampstead Road as shown in **Figure 8-11** to **Figure 8-14**.



Figure 8-11: Construction Logistics Strategy – Option A – Phase 0




Figure 8-12: Construction Logistics Strategy – Option A – Phase 1




Figure 8-13: Construction Logistics Strategy – Option A – Phase 2




Figure 8-14: Construction Logistics Strategy – Option A – Phase 3



ENABLING WORKS REQUIRED

- Basement and ground level construction of new vehicle route over pedestrianised Triton Square and Regent’s Place Plaza and within operational basement;
- Construction vehicle crossovers on Euston Road off-slip and Hampstead Road; and
- Site hoarding and welfare accommodation.



POTENTIAL IMPACTS

- Enabling works would take significant time and delay the start of the construction programme as the works need to be completed before Phase 1 (Deconstruction) can start;
- Triton Square pedestrian route is 8.0m wide with pedestrian and cycle access points on both sides. Can a safe construction route, that provides vehicle (construction and emergency) access be provided whilst retaining access to the buildings;
- Fire vehicle access required throughout construction. Fire tender route cannot be retained during enabling works. Significant hazard;
- Landscaping on Triton Square to be removed for whole construction programme;
- The basement servicing area may be out of action to accommodate the strengthening works – This impacts the operational requirements of 10 Brock Street and 20-30 Brock Street including the retail units at ground level, that are serviced from the shared loading bays;
- Construction vehicles may not be able to use the basement loading area due to structural/strengthening works;
- Basement impacts to parking areas and 10 Brock Street access routes. Potential loss of routes during both the enabling works and through the construction programme.
- Fire escapes along the route from 1 and 4 Triton Square, and The Old Diorama Arts Centre to be retained;
- The existing pedestrian access to Triton Square, Regents Plaza and Brock Street will be severely impacted by the enabling works and hoarding required for vehicle manoeuvring and loading/unloading within Triton Square and Regent's Place Plaza;
- Pedestrian Comfort Levels affected due to enabling works construction and the hoarding requirements for vehicle manoeuvring and loading/unloading within Triton Square and Regent's Place Plaza. PCLs affected for the entire construction programme;
- Lease and legal access agreements affected by enabling works both at ground level and within the basement;
- Significant impact to construction viability – significant financial costs associated with the enabling works and the extension to the construction programme;
- Construction vehicle crossovers required on Euston Road off-slip and Hampstead Road;
- On-street double length pit lane required on Euston Road off-slip during Phase 2 of construction and single length during Phase 3.

OPTION B - BASEMENT AND TLRN ACCESS – HAMPSTEAD ROAD BUS STOP SUSPENDED

ACCESS SUMMARY

- 8.8.10 **Option B** proposes the use of the existing basement, and entry via Euston Road with vehicles exiting in two locations on Hampstead Road. To facilitate the northern egress on Hampstead Road, it is proposed the northbound bus stop is suspended for the duration of the construction programme. High-level access proposals for each construction phase are shown in **Figure 8-15** to **Figure 8-17**.



Figure 8-15: Construction Logistics Strategy – Option B – Phase 1

**Construction Logistics Strategy
Option B – Hampstead Road Bus Stop Suspended – Phase 1**




Figure 8-16: Construction Logistics Strategy – Option B – Phase 2

**Construction Logistics Strategy
Option B – Hampstead Road Bus Stop Suspended – Phase 2**





Figure 8-17: Construction Logistics Strategy – Option B – Phase 3



ENABLING WORKS REQUIRED

- Construction vehicle crossovers on Euston Road off-slip and two crossovers on Hampstead Road;
- Hampstead Road northbound bus stop to be suspended; and
- Site hoarding and welfare accommodation

POTENTIAL IMPACTS

- Significant disruption to bus users at Hampstead Road. The nearest bus stops are 250m north or between 150m and 175m to the south and southeast. The suspension of the bus stop would be for the duration of the construction programme (60-months/5-years)
- Construction vehicle crossovers required on Euston Road off-slip and two on Hampstead Road;
- On-street pit lanes required on Euston Road off-slip and Hampstead Road during Phase 2 of construction.
- Significant impact to construction viability – significant financial costs associated with the suspension of the bus stop for the whole construction programme.

OPTION C - BASEMENT AND TLRN ACCESS – HAMPSTEAD ROAD BUS STOP RELOCATED

ACCESS SUMMARY

- 8.8.11 **Option C** proposes the use of the existing basement, and entry via Euston Road with vehicles exiting in two locations on Hampstead Road. To facilitate the northern egress on Hampstead Road, it is proposed to relocate the northbound bus stop approx. 18m north for the duration of the construction programme. The high-level access proposals for each construction phase are shown in **Figure 8-18** to **Figure 8-20**.

Figure 8-18: Construction Logistics Strategy – Option C – Phase 1




Figure 8-19: Construction Logistics Strategy – Option C – Phase 2





Figure 8-20: Construction Logistics Strategy – Option C – Phase 3



ENABLING WORKS REQUIRED

- Construction vehicle crossovers on Euston Road off-slip and two crossovers on Hampstead Road;
- Hampstead Road northbound bus stop to be relocated (existing shelter to be reused); and
- Site hoarding and welfare accommodation

POTENTIAL IMPACTS

- Minor disruption to bus users at Hampstead Road. The bus stop is proposed to be relocated 18m north and the redundant bus shelters to be reused. The relocation of the bus stop would be for the duration of the construction programme (60-months/5-years)
- Construction vehicle crossovers required on Euston Road off-slip and two on Hampstead Road;
- On-street pit lanes required on Euston Road off-slip and Hampstead Road during Phase 2 of construction.
- Minor impact to construction viability – minor financial costs associated with the relocation of the bus stop for the entire construction programme.

OPTION D - BASEMENT AND TLRN ACCESS – HAMPSTEAD ROAD BUS STOP RETAINED

ACCESS SUMMARY

8.8.12 **Option D** proposes the use of the existing basement, and entry via Euston Road with vehicles exiting onto Hampstead Road on one location. For this option it is proposed to retain the northbound Hampstead Road bus stop for the duration of the construction programme. High-level access proposals for each construction phase are shown in **Figure 8-21** to **Figure 8-23**.



Figure 8-21: Construction Logistics Strategy – Option D – Phase 1



Figure 8-22: Construction Logistics Strategy – Option D – Phase 2





Figure 8-23: Construction Logistics Strategy – Option D – Phase 3



ENABLING WORKS REQUIRED

- Construction vehicle crossover on Euston Road off-slip and on Hampstead Road;
- Site hoarding and welfare accommodation

POTENTIAL IMPACTS

- Minor disruption to bus users at Hampstead Road. The extension to the construction programme will mean the hoarding line will be in place for the duration of the construction programme (eight years)
- Construction vehicle crossovers required on Euston Road off-slip and Hampstead Road;
- On-street double length pit lane required on Euston Road off-slip during Phase 2 and Phase 3 of construction.
- Significant impact to construction viability – major financial costs associated with the extension of the entire construction programme by circa three years.

SUMMARY OF CONSTRUCTION LOGISTICS STRATEGY OPTIONS

- 8.8.13 Larger version of the Construction Logistic Options and Phasing Plans are contained within **APPENDIX H**
- 8.8.14 Whilst it is understood that there will always be impact with such significant construction works adjacent to a busy transport network, the options discussed above have been analysed and their impacts reviewed against a number of users including pedestrian, cyclists, bus users and general road users, along with the construction programme and financial viability of the construction.
- 8.8.15 The summary set out in **Table 8-2** to **Table 8-5** and included in **APPENDIX I** shows a ‘Traffic Light’ impact study of the various users against each construction logistic strategy options.

Table 8-2: Impact Study – Option A

Option A - Triton Square Access						
Construction Phase	Phase 0 - Basement, Plaza and Access Route - Enabling Works	Phase 1 - Deconstruction to Ground Level	Phase 2 - Deconstruction of Ground Level Slab and Return to Ground	Phase 3 - Above Ground Construction	Summary	
Initial Construction Programme	24 months	24 months	16 months	40 months	64 months*/9 Years	
All Users	Buses	No change	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.
	General Traffic	Additional construction traffic on Langford Street, Drummond Street and the pedestrianised Triton Square and Regent's Place Plaza	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.
	Cycles	Additional construction traffic on Langford Street, Drummond Street and the pedestrianised Triton Square and Regent's Place Plaza	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.
	Pedestrians	Additional construction traffic on Langford Street, Drummond Street and the pedestrianised Triton Square and Regent's Place Plaza	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road - Regent's Place Plaza closed and significant impact on Triton Square	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road - Regent's Place Plaza closed and significant impact on Triton Square	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road - Regent's Place Plaza closed and significant impact on Triton Square	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road - Regent's Place Plaza closed and significant impact on Triton Square
Safety	Pedestrians	Additional construction traffic on Langford Street, Drummond Street and the pedestrianised Triton Square and Regent's Place Plaza	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road - Regent's Place Plaza closed and significant impact on Triton Square. Construction entry and exit points crossing footway	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road - Regent's Place Plaza closed and significant impact on Triton Square. Construction entry and exit points crossing footway	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road - Regent's Place Plaza closed and significant impact on Triton Square. Construction entry and exit points crossing footway	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road - Regent's Place Plaza closed and significant impact on Triton Square
	Cycles	Additional construction traffic on Langford Street, Drummond Street and the pedestrianised Triton Square and Regent's Place Plaza	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.	Hampstead Road Site Egges - Construction vehicles crossing cycle lane, under management.
	Construction Vehicles	Construction activity and hoarding line will affect pedestrian movements within Triton Square and the Plaza	Adequate space will be provided on-site for the loading and unloading of construction vehicles. Access to site to be managed	Pit lane required on Euston Road off-slip	Adequate space will be provided on-site for the loading and unloading of construction vehicles. Access to site to be managed	Construction vehicles conflict with all road users when entering and leaving the site. All access from the TLRN will be under managed condition.
	Vehicle Volumes	Additional construction traffic on Langford Street, Drummond Street and the pedestrianised Triton Square and Regent's Place Plaza	Additional construction vehicles on Additional construction traffic on Langford Street, Drummond Street and both Euston Road off-slip and Hampstead Road - Negligible increase in overall vehicles.	Additional construction vehicles on Additional construction traffic on Langford Street, Drummond Street and both Euston Road off-slip and Hampstead Road - Negligible increase in overall vehicles.	Additional construction traffic on Additional construction traffic on Langford Street, Drummond Street and both Euston Road off-slip and Hampstead Road - Negligible increase in overall vehicles.	Additional construction vehicles on Additional construction traffic on Langford Street, Drummond Street and both Euston Road off-slip and Hampstead Road - Negligible increase in overall vehicles.
Buses and Bus Stops Impacts	Boarders	No change	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges
	Alighters	No change	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges
	Onboard	No change	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges
	Bus speeds	No change	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road and Hampstead Road Site Egges
Footway Impact and Pedestrian Flows	Pedestrians	Construction activity and hoarding line will affect pedestrian movements within Triton Square and the Plaza, and on both Euston Road and Hampstead Road	Construction activity and hoarding line will affect pedestrian movements within Triton Square and the Plaza, and on both Euston Road and Hampstead Road	Construction activity and hoarding line will affect pedestrian movements within Triton Square and the Plaza, and on both Euston Road and Hampstead Road	Construction activity and hoarding line will affect pedestrian movements within Triton Square and the Plaza, and on both Euston Road and Hampstead Road	Construction activity and hoarding line will affect pedestrian movements within Triton Square and the Plaza, and on both Euston Road and Hampstead Road
	PCL assessment	Construction activity and hoarding line will affect pedestrian movements within Triton Square and the Plaza.	PCL assessment shows worst case "B" during construction for Euston Road, Hampstead Road and Brook Street. Additional assessment for Triton Square and Regent's Place Plaza required.	PCL assessment shows worst case "B" during construction for Euston Road, Hampstead Road and Brook Street. Additional assessment for Triton Square and Regent's Place Plaza required.	PCL assessment shows worst case "B" during construction for Euston Road, Hampstead Road and Brook Street. Additional assessment for Triton Square and Regent's Place Plaza required.	PCL assessment shows worst case "B" during construction for Euston Road, Hampstead Road and Brook Street. Additional assessment for Triton Square and Regent's Place Plaza required.
Lane Rental Charges	Developer	No change	No change	Pit lane required on Euston Road off-slip	No change	Pit lane required on Euston Road off-slip during Phase 2
Air Quality	All users	Construction Vehicle Activity closer to residents on Drummond Street	Construction Vehicle Activity	Construction Vehicle Activity	Construction Vehicle Activity	Construction Vehicle Activity
Construction Programme/Duration	All users	24 month programme extension for significant enabling works	No change from preliminary Programme	No change from preliminary Programme	No change from preliminary Programme	24 month programme extension due to significant enabling works
Construction Cost/Viability	All users	24 month programme extension for significant enabling works	No change from preliminary construction costs	No change from preliminary construction costs	No change from preliminary construction costs	24 month programme extension due to significant enabling works and 20 month programme extension

Table 8-3: Impact Study – Option B

Option B - Hampstead Road Northbound Bus Stop Suspended					
Construction Phase	Phase 1 - Deconstruction to Ground Level	Phase 2 - Deconstruction of Ground Level Slab and Return to Ground	Phase 3 - Above Ground Construction	Summary	
Initial Construction Programme	24 months	16 months	40 months	60 months*/9 Years	
TLRN/Road Users	Buses	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Suspension of Hampstead Road Bus Stop for entire construction programme
	General Traffic	No change	No change	No change	No change
	Cycles	Shared bus and cycle lane retained - bus stop removed	Bus and cycle lane suspended - cycles to be with general traffic	Shared bus and cycle lane retained - bus stop removed	With the exception of Phase 2, cyclists will continue to use the shared bus and cycle lane
	Pedestrians	Hoarding and gantry on both Euston Road and Hampstead Road. Construction vehicle crossovers, one on Euston Road and two on Hampstead Road	Hoarding and gantry on both Euston Road and Hampstead Road. Construction vehicle crossovers, one on Euston Road and two on Hampstead Road	Hoarding and gantry on both Euston Road and Hampstead Road. Construction vehicle crossovers, one on Euston Road and two on Hampstead Road	Hoarding and gantry on both Euston Road and Hampstead Road. Construction vehicle crossovers, one on Euston Road and two on Hampstead Road
Road Safety	Pedestrians	Hoarding and gantry on both Euston Road and Hampstead Road. Construction vehicle crossovers, one on Euston Road and two on Hampstead Road	Hoarding and gantry on both Euston Road and Hampstead Road. Construction vehicle crossovers, one on Euston Road and two on Hampstead Road	Hoarding and gantry on both Euston Road and Hampstead Road. Construction vehicle crossovers, one on Euston Road and two on Hampstead Road	Hoarding and gantry on both Euston Road and Hampstead Road. Construction vehicle crossovers, one on Euston Road and two on Hampstead Road
	Cycles	Shared bus and cycle lane retained - bus stop removed	Bus and cycle lane closed - cycles to be with general traffic	Shared bus and cycle lane retained - bus stop removed	With the exception of Phase 2, cyclists will continue to use the shared bus and cycle lane
	Construction Vehicles	Adequate space will be provided on-site for the loading and unloading of construction vehicles. Access to site to be managed	Pit lane required on Euston Road off-slip	Adequate space will be provided on-site for the loading and unloading of construction vehicles. Access to site to be managed	Construction vehicles conflict with all road users when entering and leaving the site. All access from the TLRN will be under managed condition.
	Vehicle Volumes	Additional construction vehicles on Additional construction traffic on Langford Street, Drummond Street and both Euston Road off-slip and Hampstead Road - Negligible increase in overall vehicles	Additional construction vehicles on Additional construction traffic on Langford Street, Drummond Street and both Euston Road off-slip and Hampstead Road - Negligible increase in overall vehicles	Additional construction vehicles on Additional construction traffic on Langford Street, Drummond Street and both Euston Road off-slip and Hampstead Road - Negligible increase in overall vehicles	Additional construction vehicles on Additional construction traffic on Langford Street, Drummond Street and both Euston Road off-slip and Hampstead Road - Negligible increase in overall vehicles
Buses and Bus Stops Impacts	Boarders	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Suspension of Hampstead Road Bus Stop for entire construction programme
	Alighters	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Suspension of Hampstead Road Bus Stop for entire construction programme
	Onboard	No change	No change	No change	No change
	Bus speeds	No change	Slow of bus line on Hampstead Road to be suspended. Buses to join general traffic line	No change	No change
Footway Impact and Pedestrian Flows	Pedestrians	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road
	PCL assessment	PCL assessment shows worst case "B" during construction	PCL assessment shows worst case "B" during construction	PCL assessment shows worst case "B" during construction	PCL assessment shows worst case "B" during construction
Lane Rental Charges	Developer	No change - on street pit lanes not required	Pit lanes required on both Euston Road off-slip and Hampstead Road	No change - on street pit lanes not required	Pit lanes and lane rental charges required during Phase 2
Total Cost/Economic Impact	Developer	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Suspension of Hampstead Road Bus Stop for entire construction programme
	TfL	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Hampstead Road Bus Stop suspended	Suspension of Hampstead Road Bus Stop for entire construction programme
Air Quality	All users	Construction Vehicle Activity	Construction Vehicle Activity	Construction Vehicle Activity	Construction Vehicle Activity
Construction Programme/Duration	All users	No change from preliminary Programme	No change from preliminary Programme	No change from preliminary Programme	No change from preliminary Programme
Construction Cost/Viability	All users	No change from preliminary construction costs	No change from preliminary construction costs	No change from preliminary construction costs	No change from preliminary construction costs



Table 8-4: Impact Study – Option C

Option C - Hampstead Road Bus Stop Relocated					
Construction Phase		Phase 1	Phase 2	Phase 3	Summary
Construction Duration		24 months	16 months	40 months	60 months*/5 Years
Road Users	Buses	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed
	General Traffic	No change	No change	No change	No change
	Cycles	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop
Road Safety	Pedestrians	Hoarding, scaffolding and gantry - Vehicle accesses will be fully managed by trained traffic marshals	Hoarding, scaffolding and gantry - Vehicle accesses will be fully managed by trained traffic marshals	Hoarding, scaffolding and gantry - Vehicle accesses will be fully managed by trained traffic marshals	Hoarding, scaffolding and gantry - Vehicle accesses will be fully managed by trained traffic marshals
	Cycles	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop
	Construction Vehicles	Adequate space will be provided on-site for the loading and unloading of construction vehicles. Access to site to be managed	PI lanes required on Euston Road off slip	Adequate space will be provided on-site for the loading and unloading of construction vehicles. Access to site to be managed	Construction vehicles conflict with all road users when entering and leaving the site. All access from the TRN will be under managed conditions
Buses and Bus Stops Impacts	Vehicle Volumes	Additional construction vehicles on Additional construction traffic, Longford Street, Drummond Street and both Euston Road off slip and Hampstead Road - Negligible increase in overall vehicles	Additional construction vehicles on Additional construction traffic, Longford Street, Drummond Street and both Euston Road off slip and Hampstead Road - Negligible increase in overall vehicles	Additional construction vehicles on Additional construction traffic, Longford Street, Drummond Street and both Euston Road off slip and Hampstead Road - Negligible increase in overall vehicles	Additional construction vehicles on Additional construction traffic, Longford Street, Drummond Street and both Euston Road off slip and Hampstead Road - Negligible increase in overall vehicles
	Boarders	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed
	Alighters	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed
Footway Impact and Pedestrian Flow	Onboard	No change	No change	No change	No change
	Bus speeds	No change	Minor Delay - 40m of bus lane on Hampstead Road to be suspended	No change	No change
	Pedestrians	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road
Lane Rental Charges	PCL assessment	PCL assessment shows worst case 'B' during construction	PCL assessment shows worst case 'B' during construction	PCL assessment shows worst case 'B' during construction	PCL assessment shows worst case 'B' during construction
	Developer	No change - on street pit lanes not required	PI lanes required on both Euston Road off-slip and Hampstead Road	No change - on street pit lanes not required	PI lanes required on both Euston Road off-slip and Hampstead Road during Phase 2
	Developer	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed
Total Cost/Economic Impact	TI	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop relocated 10m north - redundant bus shelters to be removed
	Air Quality	Additional construction vehicles on both Euston Road off slip and Hampstead Road	Additional construction vehicles on both Euston Road off slip and Hampstead Road	Additional construction vehicles on both Euston Road off slip and Hampstead Road	Additional construction vehicles on both Euston Road off slip and Hampstead Road
	Construction Programme/Duration	No change from preliminary Programme	No change from preliminary Programme	No change from preliminary Programme	No change from preliminary Programme
Construction Cost/Viability	All users	No change from preliminary construction costs	No change from preliminary construction costs	No change from preliminary construction costs	No change from preliminary construction costs

Table 8-5: Impact Study – Option D

Option D - Hampstead Road Bus Stop Retained					
Construction Phase		Phase 1	Phase 2	Phase 3	Summary
Construction Duration		24 months	24 months	80 months	110 months*/9 Years
Road Users	Buses	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed
	General Traffic	No change	No change	No change	No change
	Cycles	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop
Road Safety	Pedestrians	Hoarding, scaffolding and gantry - Vehicle accesses will be fully managed by trained traffic marshals	Hoarding, scaffolding and gantry - Vehicle accesses will be fully managed by trained traffic marshals	Hoarding, scaffolding and gantry - Vehicle accesses will be fully managed by trained traffic marshals	Hoarding, scaffolding and gantry - Vehicle accesses will be fully managed by trained traffic marshals
	Cycles	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop	Cycles to be with general traffic until joining existing cycle lane north of the bus stop
	Construction Vehicles	Adequate space will be provided on-site for the loading and unloading of construction vehicles. Access to site to be managed	PI lanes required on Euston Road off slip	Adequate space will be provided on-site for the loading and unloading of construction vehicles. Access to site to be managed	Construction vehicles conflict with all road users when entering and leaving the site. All access from the TRN will be under managed conditions
Buses and Bus Stops Impacts	Vehicle Volumes	Additional construction vehicles on Additional construction traffic, Longford Street, Drummond Street and both Euston Road off slip and Hampstead Road - Negligible increase in overall vehicles	Additional construction vehicles on Additional construction traffic, Longford Street, Drummond Street and both Euston Road off slip and Hampstead Road - Negligible increase in overall vehicles	Additional construction vehicles on Additional construction traffic, Longford Street, Drummond Street and both Euston Road off slip and Hampstead Road - Negligible increase in overall vehicles	Additional construction vehicles on Additional construction traffic, Longford Street, Drummond Street and both Euston Road off slip and Hampstead Road - Negligible increase in overall vehicles
	Boarders	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed
	Alighters	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed	Hampstead Road Bus Stop retained 10m north - redundant bus shelters to be removed
Footway Impact and Pedestrian Flow	Onboard	No change	No change	No change	No change
	Bus speeds	No change	Minor Delay - Double length pit lane required on Euston Road off-slip	Minor Delay - Double length pit lane required on Euston Road off-slip	Minor Delay - Double length pit lane required on Euston Road off-slip during Phase 2 and 3
	Pedestrians	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road	Hoarding, scaffolding and gantry on both Euston Road and Hampstead Road	Hoarding, scaffolding and gantry - Vehicle accesses will be fully managed by trained traffic marshals. Pedestrians affected by construction
Lane Rental Charges	PCL assessment	PCL assessment shows worst case 'B' during construction	PCL assessment shows worst case 'B' during construction	PCL assessment shows worst case 'B' during construction	PCL assessment shows worst case 'B' during construction
	Developer	No change - on street pit lanes not required	Double length pit lane required on Euston Road off-slip	Double length pit lane required on Euston Road off-slip	Minor Delay - Double length pit lane required on Euston Road off-slip during Phase 2 and 3
	Developer	No change	Double length pit lane required on Euston Road off-slip	No change	Double length pit lane and lane changes required during Phase 3
Total Cost/Economic Impact	TI	No change	No change	No change	No change
	Air Quality	Additional construction vehicles on both Euston Road off-slip and Hampstead Road	Additional construction vehicles on both Euston Road off-slip and Hampstead Road	Additional construction vehicles on both Euston Road off-slip and Hampstead Road	Additional construction vehicles on both Euston Road off-slip and Hampstead Road
	Construction Programme/Duration	No change from preliminary Programme	Minor programme increase	Significant Programme increase	Significant Programme increase
Construction Cost/Viability	All users	No change from preliminary construction costs	Minor programme increase - leading to additional construction costs	Significant Programme increase leading to additional construction costs	Significant Programme increase leading to additional construction costs



- 8.8.16 **Option C** provides the least impact on all users listed above and has the shortest construction programme which reduces the time where certain users are impacted. i.e. pedestrians are impacted due the hoarding line and reduced footway widths for five years in Option C or eight years in Options A or nine years in Option D.
- 8.8.17 The impacts to all users on the relocation of the Hampstead bus stop are listed below:
- Minor impact to all bus users
 - Minor impact on bus delay – construction vehicle access points – Phase 2 pit lanes on both Euston Road and Hampstead Road
 - Shortest construction programme (5-years)
 - Minor impact to cyclists – required to join general traffic for approx. 80m until joining existing cycle lane.
 - Minor impact to pedestrians on Hampstead Road and Euston Road due to the hoarding line and construction vehicle access points.
 - Pit lanes on both Euston Road and Hampstead Road required during Construction Phase 2
- 8.8.18 Overall, the relocation of the Hampstead Road northbound bus stop, is the least impactful on all users and provides the most efficient construction programme.
- 8.8.19 To facilitate the construction of the Hampstead Road egress points during Phases 1 and 3 and the introduction of a pit lane during Phase 2. It is proposed to relocate the northbound bus stop on Hampstead Road 18m to the north and re-use the redundant bus shelters associated with the previous location of the bus stop.
- 8.8.20 The proposed relocation retains the southbound carriageway, including the latest TfL (Future of Temp Works) proposals as set out in **Section 7.11**.
- 8.8.21 As part of the proposals, the shared northbound cycle lane is removed from the bus lane between the junction with Euston Road and to rejoin the existing cycle lane circa 80m north.
- 8.8.22 The proposed bus stop relocation is shown in **Figure 8-24** and a scaled plan is included in **APPENDIX J**.



Figure 8-24: Proposed Hampstead Road Bus Stop Relocation



SITE ACCESS

8.8.23 The proposed logistics plan for the Site incorporates the following key features:

- ⊙ Use of the existing basement servicing area will be maximised, but is limited due to vehicle height and length constraints;
- ⊙ Products and materials will be delivered to the Site by vehicle and unloaded within the Site boundary. Marshals will strictly control any movements through the access, and short-term temporary barriers will be erected to safeguard pedestrians where required; and
- ⊙ Access and egress to the site are to be controlled by banksman.

CONSTRUCTION VEHICLE ACCESS

- 8.8.24 Vehicular movements to and from the site will be controlled and managed. Separate access gates will be provided for pedestrian and vehicular access to the site. A plan of the immediate site will be provided to all delivery companies, clearly showing the access and exit points for all vehicles.
- 8.8.25 To facilitate the construction of the development, a qualified banksman will be on hand to ensure the safe access and egress of construction vehicles. As set out within the Health and Safety Executive (HSE) guidance, the traffic marshal directing vehicle movements will be trained and authorised.
- 8.8.26 Trained traffic marshals will be responsible for facilitating unloading/loading goods to the Site/from the correct offloading zone and storage areas to ensure safe unloading practices.
- 8.8.27 The main access points for construction vehicles will be:


- ⊙ via the existing Longford Street basement access, which cannot accommodate articulated vehicles;
- ⊙ from the Euston Road off slip and exiting the site onto Hampstead Road; or
- ⊙ via proposed pit lanes on Euston Road off slip and Hampstead Road during Construction Phase 2.

Figure 8-25: Proposed Site Layout and Vehicle Access




- 8.8.28 Secure gates and wheel cleaning facilities (if needed) will be established at the construction gates.
- 8.8.29 To minimise the likelihood of congestion during the construction period, strict monitoring and control of vehicles entering and egressing the sites will be implemented. Construction deliveries will be carefully planned, with delivery times agreed with each sub-contractor and supplier using a booking system. Delivery schedules will be produced in order to look at the profiles of up-and-coming deliveries and to regulate deliveries to avoid any potential queueing.
- 8.8.30 **Figure 8-26** shows the proposed construction logistics layout plan for Phase 1, which includes the reduction in the width of Brock Street to the north and the narrowing of Hampstead Road (western footway) and Euston Road (northern footway) to a clear 2.5m in width. Vehicle access is gained from Euston Road off slip, and vehicles exit northbound onto Hampstead Road.
- 8.8.31 As part of the access strategy for all construction phases, it is proposed to relocate the existing northbound Hampstead Road bus stop by circa 18m north to allow construction vehicles to egress the Site. The proposed relocation is covered in more detail in **Section 8.10**.

Figure 8-26: Construction Vehicle Access – Phase 1



8.8.32 **Figure 8-27** shows the proposed construction logistics layout plan for Phase 2, which includes the reduction in the width of Brock Street to the north and the narrowing of Hampstead Road (western footway) and Euston Road (northern footway) to a clear 2.5m in width. As the ground level slab is removed during Phase 2, pit lanes are to be provided on both Euston Road off-slip and Hampstead Road.

Figure 8-27: Construction Vehicle Access – Phase 2



8.8.33 **Figure 8-28** shows the proposed construction logistics layout plan for Phase 1, which includes the reduction in the width of Brock Street to the north and the narrowing of Hampstead Road (western footway) and Euston Road (northern footway) to a clear 2.5m in width. Vehicle access is gained in two locations from Euston Road off slip, and vehicles exit northbound onto Hampstead Road.

Figure 8-28: Construction Vehicle Access – Phase 3



PERSONNEL ACCESS

- 8.8.34 Given the accessible location of the Site, most operatives are anticipated to arrive by public transport. No operative parking will be permitted or encouraged.
- 8.8.35 Pedestrian access to the Site will always be segregated from vehicle traffic, with clear signage to maintain the Site's safety and the public. Personnel access is proposed to the west of the Site via Regents Place Plaza.
- 8.8.36 Once the contractor is appointed, further opportunities to maximise access to the construction Site will be investigated to reduce the construction programme and mitigate associated impacts.
- 8.8.37 These will be included within the submitted detailed Construction Environmental Management Plan and/or the Construction Traffic Management Plan, which are expected to be secured by a planning condition. A Draft Construction Management Plan Camden Proforma has been submitted with the planning application.


8.9 CONSTRUCTION – PEDESTRIAN COMFORT LEVEL ASSESSMENT

8.9.1 A PCL assessment has been undertaken of existing flows on the surrounding footways during the peak hour throughout the construction period, the results of which are shown in **Table 8-6**.

Table 8-6: Pedestrian comfort analysis - pedestrian conditions during the construction period

Ref.	Link	Link Type	Peak Hour Flow	Clear Footway Width	PCL
1	Euston Road	Office and Retail	1,583	2.5m	B+
2	Euston Road	Office and Retail	1,583	2.5m	B+
3	Hampstead Road	Office and Retail	1,068	2.05m*	B
4	Hampstead Road	Office and Retail	1,068	2.5m	A-

*Existing landscaping and street furniture



8.9.2 The PCL assessment indicates that:

- On Euston Road (northern footway), pedestrian conditions will be comfortable with peak hour PCLs of B+;
- On Hampstead Road South (western footway), the PCL is expected to be B in the peak hour;
- On Hampstead Road North (western footway), the PCL is expected to be A- in the peak hour;

8.9.3 Based on TfL's 'pedestrian comfort guidance technical note,' a PCL of 'B' is considered to be 'comfortable'.

8.9.4 The PCLs on all links are considered acceptable given that the construction scenario is temporary and will improve following the completion of construction works and opening of the Proposed Development. The contractor will review opportunities to maximise footway widths throughout the construction programme.

8.10 STRATEGIES TO REDUCE CONSTRUCTION IMPACTS

8.10.1 A few strategies and measures are planned to reduce the impacts of construction and construction traffic on the local area. The planned measures can be categorised as follows:

- Committed - measures that will be implemented as part of the CLP;
- Proposed - measures that are feasible and likely to be implemented. Once a contractor is appointed, these measures will be studied further and confirmed within the detailed CLP; and
- Considered - measures that are unlikely to be implemented or feasible but could be investigated or become relevant in the future.

8.10.2 **Table 8-7** summarises the planned measures for constructing the Proposed Development based on the checklist provided in TfL's CLP guidance.

Table 8-7: Construction Planned Measures

PLANNED MEASURES	COMMITTED	PROPOSED	CONSIDERED
MEASURES INFLUENCING CONSTRUCTION VEHICLES AND DELIVERIES			
Safety and environmental standards and programmes	X		
Adherence to designated routes	X		
Delivery scheduling	X		
Re-timing for out-of-peak deliveries			X
Re-timing for out-of-hours deliveries			X
Use of holding areas and vehicle call-off areas	X		
Use of logistics and consolidation centres			X
Vehicle choice	X		
MEASURES TO ENCOURAGE SUSTAINABLE FREIGHT			
Freight by water			X
Freight by rail			X
MATERIAL PROCUREMENT MEASURES			
Design for manufacture and assembly and off-site manufacture			X
Re-use of material on the Site		X	
Smart procurement		X	
OTHER MEASURES			
Collaboration with other Sites in the area			X
Implement a Staff Travel Plan	X		

8.10.3 The CLOCS (Construction Logistics and Community Safety) standard will be signed up to, which will ensure that the construction contractor (as well as suppliers and sub-contractors) follow safe practices in the management of their operations, vehicles, drivers and construction sites.


- 8.10.4 All construction vehicle operators will be required to be accredited in line with the Fleet Operator Recognition Scheme (FORS). FORS accreditation confirms that a fleet operator can demonstrate that appropriate systems and policies exist to ensure drivers are suitably fit, qualified and licenced to operate vehicles which are properly maintained, equipped and insured. It is a mechanism by which adherence to the CLOCS standard can be assured and monitored.
- 8.10.5 A delivery scheduling system is planned to allow for the control and management of the timings of deliveries. Booking availability will be determined by unloading space available activities on site and managed carefully to minimise impacts on the local transport network. A comprehensive daily logistics schedule will be maintained, and unauthorised deliveries will be turned away until the approved procedure has been followed.
- 8.10.6 Construction staff on site will be prepared for the arrival of all vehicles to prevent vehicles needing to wait on the public highway. Deliveries will be made 'just in time' to minimise the amount of space required on site for construction materials. Hard copies of daily delivery schedules will be displayed at prominent locations, e.g., provided at the gate/ offloading points, at hoists and also issued to drivers, forklift drivers and any other materials handling equipment operators, all of whom need to be in constant radio communication with one another. All radio users will be trained on correct radio procedures and protocols.
- 8.10.7 To prevent the contamination of local roads, a proprietary wheel wash system and a jet wash will be in place inside the site delivery gates. The system will clean the wheels and undercarriage of vehicles during the deconstruction, substructure and superstructure phases. The traffic marshal will then check each vehicle for cleanliness before allowing the vehicle to leave the site. Additionally, working practises will be selected to minimise the release of dust, for example, through water suppression during cutting operations.
- 8.10.8 Any abnormal loads will be planned in advance and agreed upon with the Highways Authority.
- 8.10.9 The use of an off-site construction consolidation centre will be investigated; however, the booking system will allow deliveries to be managed efficiently. Where possible, vehicles will be fully loaded, thereby minimising the number of vehicle trips made by tipper trucks and concrete mixing trucks.
- 8.10.10 Smart procurement will be encouraged in order to share suppliers and minimise the number of construction vehicle trips. All suppliers will be made aware of access and routing requirements.
- 8.10.11 The use of water and rail modes to transport freight is unlikely to be practical given that there will be limited demolished or muck-away material to remove. Off-site manufacture and re-use of material will be investigated and proposed where practical. Once appointed, the contractor will develop a plan to maximise smart procurement.
- 8.10.12 A staff Travel Plan will be prepared by the contractor as part of the Detailed CLP to encourage the use of sustainable modes considering the good level of public transport accessibility. Car parking for construction workers will not be provided. Staff cycle parking facilities will be provided.
- 8.10.13 Construction is anticipated to take place during normal construction working hours (08:00 – 18:00 Mon-Fri, 08:00-13:00 Saturday). Is it anticipated that there might be some work carried out outside of these hours (e.g., concrete pours).
- 8.10.14 Once appointed, the contractor will investigate the opportunity to collaborate with other local construction sites.



8.11 ESTIMATED VEHICLE MOVEMENTS

8.11.1 Based on the indicative programme and construction information, the estimated number of construction vehicle trips (two-way) for both LGVs and HGVs is summarised in **Figure 8-29**. The anticipated monthly number of vehicles is expected to peak during Q3 of the third year of the deconstruction and construction period. The peak will generate approximately 50 two-way vehicle movements per day.

Figure 8-29: Estimated Construction Vehicles



8.11.2 The number of vehicles accessing the site summarised in **Table 8-8** has been estimated based on our previous experience, proposed programme, and construction methodology.


Table 8-8: Estimated Construction Vehicles – Monthly and Daily

Construction Task/Activity	Period of Stage	Estimated Number of Monthly Trips	Peak No. of Trips (Daily)
Site Set-up and Demolition Works	Q1 2025 – Q4 2026	226	11
Substructure – Piling and Basement Walls	Q1 2026 - Q2 2027	314	16
Superstructure (slabs and steelworks)	Q3 2027 - Q3 2029	119	5
Cladding	Q3 2027 - Q2 2030	21	1
Finishes and Fitout	Q2 2027 - Q1 2030	108	5
Testing and Commissioning	Q3 2029 - Q2 2030		
Peak period of Construction	Q1 2027	466	25

8.11.3 **Figure 6-1** illustrates the peak hourly volumes of construction vehicles anticipated during construction based on estimations of construction material volumes and the programme within **Figure 8-4**.



Figure 8-30: Tfl CLP Tool Graphs



- 8.11.4 Around ten construction vehicle arrivals and ten construction vehicle departures are expected on a typical/average day. Peak demand is expected to generate circa 25 vehicle arrivals and 25 vehicle departures per day.
- 8.11.5 The peak demands can be accommodated on the transport network with minimal impact. Vehicles will access and egress directly from the strategic road network.
- 8.11.6 No construction staff car parking will be provided on site and no construction workers are expected to travel by car.



- 8.11.7 As set out above, it is proposed that all construction vehicles will access the Site from the west and enter via the existing basement on Longford Street or via new construction vehicle crossovers on Euston Road off-slip. All construction vehicles will exit the site to the north via Hampstead Road from the existing basement or via new construction vehicle crossovers on Hampstead Road. The indicative construction logistics strategy is shown in **Figure 8-31**.

Figure 8-31: Indicative Construction Logistics Strategy



VEHICLE ROUTING AND ESTIMATED MOVEMENT BY PHASE

- 8.11.8 Where possible, use of the existing basement will be maximised, but access is restricted by vehicle length and height, meaning that larger articulated vehicles have to access the site at ground level. Based on the estimated vehicle movements for each construction task, vehicles have been distributed between the basement access and ground level site access for each phase of construction.


PHASE 1 – DECONSTRUCTION TO GROUND LEVEL

- Site setup and deconstruction - 90% via basement, 10% at ground level.
- Basement excavation and piling - 50 % via basement and 50% at ground level.

- 8.11.9 It is expected that the peak month for construction vehicles will occur during Phases 1 and 2 where an estimated 25 vehicles per day (50 two-way movements) are expected. The construction vehicle distribution is shown in **Figure 8-32**.



Figure 8-32: Construction Vehicle Distribution – Phase 1




PHASE 2 – DECONSTRUCTION OF GROUND SLAB, AND RETURN TO GROUND LEVEL

- Sub-structure - 50 % via basement and 50% at ground level.

8.11.10 It is expected that the peak month for construction vehicles will occur during Phases 1 and 2 where an estimated 25 vehicles per day (50 two-way movements) are expected. The construction vehicle distribution is shown in **Figure 8-33**.

Figure 8-33: Construction Vehicle Distribution – Phase 2




PHASE 3 – ABOVE GROUND CONSTRUCTION

- Super-structure - 10% via basement and 90% at ground level.
- Cladding - 10% via basement and 90% at ground level.
- Fitout, testing and commissioning - 10% via basement and 90% at ground level.
- Public Realm - 10% via basement and 90% at ground level.

8.11.11 It is expected that during Phase 3, the peak construction trips will be reduced from Phases 1 and 2, and it is estimated that a peak of eleven vehicles per day (22 two-way movements) are expected. The construction vehicle distribution is shown in **Figure 8-34**.



Figure 8-34: Construction Vehicle Distribution – Phase 3



8.12 IMPLEMENTATION, MONITORING AND UPDATING

IMPLEMENTING

- 8.12.1 In the first instance, the Outline CLP will be issued to LBC and TfL for review as part of the planning application. The local community will be consulted to identify any concerns about construction activity and traffic. An appropriate planning condition/obligation will secure the requirement for a detailed CLP to be submitted and approved before the Proposed Development's commencement. The principal contractor will prepare the detailed CLP.
- 8.12.2 The principal contractor will be responsible for implementing the CLP. It is expected that a Contractor and Driver Handbook will be used to distribute information which makes sure that all contractors are aware of their obligations.
- 8.12.3 The key measures identified to manage and control the impacts of construction traffic and travel by staff are expected to be:
- Commitment to meet CLOCS / FORS accreditation;
 - Use of delivery scheduling system;
 - Designated construction traffic routes, ensuring all HGVs use appropriate strategic roads and
 - Travel Plan for construction staff.



MONITORING

- 8.12.4 A coordinator will be appointed to undertake the day-to-day management of the CLP and will be the first point of contact for dealing with any Site issues. The CLP will be regularly monitored.
- 8.12.5 Data sharing is a key principle for construction's success and continuous improvement. A list of items will be agreed upon, and specific data will be disseminated. This is expected to include the following:
- Compliance
 - FORS compliance
 - Routing compliance
 - Data from the delivery scheduling system and the recorded log of vehicle movements to the Site:
 - Vehicle type and size
 - Duration on site
 - Safety issues, including any injuries or near misses
 - Breaches and complaints
 - Staff travel survey
- 8.12.6 The contractor will review opportunities to maximise footway widths throughout the construction programme.

UPDATING

- 8.12.7 The outline CLP will be developed into a detailed CLP once a contractor is appointed and following the grant of any planning permission.
- 8.12.8 Once the contractor is appointed, further opportunities to maximise vehicle access/egress of the construction Site will be investigated to reduce the construction programme and mitigate associated impacts.
- 8.12.9 These will be included within the submitted detailed Construction Environmental Management Plan and/or the Construction Traffic Management Plan, which is expected to be secured by a planning condition. A Draft Construction Management Plan Camden Proforma has been submitted with the planning application.
- 8.12.10 The detailed CLP will be prepared following consultation with LBC and TfL and will require the approval of the highway authorities. This will ensure that all construction activities on the Site accord with relevant policy requirements.
- 8.12.11 After the detailed CLP is submitted and approved, the CLP will be an evolving document to account for any changes to the construction strategy and incorporate monitoring results and any consequent changes. It will be reviewed internally every month and/or at any time there is a significant change in the construction process. This will ensure that the document remains relative to the realities of the Site at any point in time.
- 8.12.12 The CLP will be kept on-site and updated by the Principal Contractor in consultation with the highway authority.



8.13 SUMMARY

8.13.1 The TfL Guidance focuses on reducing the impact of construction and providing a framework for understanding and managing construction vehicle activity into and out of the Proposed Development.

REDUCING THE IMPACT AND MANAGING CONSTRUCTION VEHICLE ACTIVITY		SOLUTIONS / MECHANISMS
Environmental Impact	Lower vehicle emissions	FORS accreditation which helps improve fleet performance in key areas such as vehicle emissions.
	Noise Levels	Noise Monitoring systems. Appropriate and well-maintained hoardings constructed on the boundaries of adjacent noise-sensitive premises.
Road Risk	Safety of Road Users	The CLOCS (Construction Logistics and Community Safety) standard will be signed up to, which will ensure that the construction contractor (as well as suppliers and sub-contractors) follow safe practices in the management of their operations, vehicles, drivers and construction sites. Designated construction traffic routes, ensuring all HGVs use appropriate strategic roads.
Congestion	Reduced Vehicle Trips	A delivery scheduling system is planned to allow for the control and management of the timings of deliveries. Booking availability will be determined by unloading space available activities on site and managed carefully to minimise impacts on the local transport network. A comprehensive daily logistics schedule will be maintained, and unauthorised deliveries will be turned away until the approved procedure has been followed
Cost	Working Practices	The CLOCS (Construction Logistics and Community Safety) standard will be signed up to, which will ensure that the construction contractor (as well as suppliers and sub-contractors) follow safe practices in the management of their operations, vehicles, drivers and construction sites. All construction vehicle operators will be required to be accredited in line with the Fleet Operator Recognition Scheme (FORS). FORS accreditation confirms that a fleet operator can demonstrate that appropriate systems and policies exist to ensure drivers are suitably fit, qualified and licenced to operate vehicles which are properly maintained, equipped and insured. It is a mechanism by which adherence to the CLOCS standard can be assured and monitored
	Reduced Deliveries	A delivery scheduling system is planned to allow for the control and management of the timings of deliveries. Booking availability will be determined by unloading space available activities on site and managed carefully to minimise impacts on the local transport network



9 SUMMARY AND CONCLUSIONS

- 9.1.1 This Transport Assessment has been prepared to support an application for full planning permission at Euston Tower, 286 Euston Road, London, NW1 3DP ('the Site'), situated within the London Borough of Camden.
- 9.1.2 The Site covers an area of 8,079 sqm, comprised of a single ground plus an existing 36-storey tower. The tower has been largely vacant for several years, predominantly comprising office uses on the upper floors; however, there are still retail uses currently in operation at the ground floor level.
- 9.1.3 The development proposal will redevelop the site to deliver a new office-led mixed-use development. The Proposed Development is designed by 3XN Architects.
- 9.1.4 Full Planning Permission is sought for the following:
- Redevelopment of Euston Tower, including the partial retention (retention of existing core, foundations and basement), disassembly, reuse and extension of the existing building, to provide a 32-storey building for use as offices and research and development floorspace (Class E(g)) and office, retail, café and restaurant space (Class E) and learning and community space (Class F) at ground, first and second floors, and associated external terraces. Provision of public realm enhancements, including new landscaping, and provision of new publicly accessible steps and ramp. Provision of short and long-stay cycle storage, servicing, refuse storage, plant and other ancillary and associated works.*
- 9.1.5 The transport strategy for the development has been developed in mind of the Healthy Streets approach by prioritising walking and cycling and minimising and managing trips by motorised vehicles.
- 9.1.6 Active frontage, pedestrian-prioritised landscaped footways and public realm will be provided as part of the proposal. The walking experience around the site will be significantly improved with the new public realm and landscaping.
- 9.1.7 The development has been designed to provide an excellent experience for cyclists with a dedicated access ramp, significant cycle parking (861 long-stay and 90 short-stay spaces) and supporting facilities including showers, lockers, changing space, a towel service, maintenance, and repair facilities. A Travel Plan will be implemented to maximise active travel and the use of these facilities.
- 9.1.8 The existing vehicle access points from Drummond Street and Longford Street are retained as they serve the Regent's Place Campus. The Longford Street access is primarily used by service vehicles to access the basement via a ramp. Eight servicing bays and waste storage facilities are provided within the basement loading area, which is shared with the Brock Street buildings. The servicing strategy for the development will explore the use of site consolidation to minimise and manage the number of servicing vehicle journeys. A cargo bike facility at both ground and basement levels will be provided to encourage sustainable freight.
- 9.1.9 The site has a PTAL of 6b, demonstrating its excellent access to public transport services, including step-free stations and stops and suitability for high trip-generating development. A range of local facilities and public transport nodes which will encourage active travel can be easily accessed from the site.



- 9.1.10 A thorough trip generation and distribution exercise has been undertaken to establish the impacts of the Proposed Development. Travel will primarily be undertaken by public transport and active modes. Assessments of the local public transport network demonstrate that development trips can be accommodated on the network without perceptible impact. Furthermore, the assessment has demonstrated that the Elizabeth Line has changed travel patterns, with other London Underground stations near to the Elizabeth Line (such as Warren Street station) experiencing a significant reduction in total entry and exit flows.
- 9.1.11 The Proposed Development is expected to generate an increase in trips in the AM and PM peak hours as a result of the Proposed Development. The forecast increases are considered to be accommodated within the existing transport network capacities, and the impact on the local public transport, active travel and highway networks has been shown not to be significant in the context of the public transport network capacity.
- 9.1.12 High-level construction logistics strategies have been thoroughly explored at the request and through discussions with TfL. The construction logistics strategy options have been reviewed against the impacts on pedestrians, cyclists, bus users, general road traffic, highway safety and the construction programme and financial viability of construction. The review concluded that relocating the northbound Hampstead Road bus stop 18m north is the preferred strategy as this would have the least impact on all road users and provides the most efficient construction programme.



9.1.13 In accordance with TfL's Healthy Streets TA Guidance, **Table 9-1** summarises the key transport impacts and issues, and proposed solutions and mechanisms for the Proposed Development.

Table 9-1: Healthy Streets Transport Assessment Conclusions

	KEY TRANSPORT IMPACTS / ISSUES	SOLUTIONS / MECHANISMS
Site & Surroundings	The site is highly accessible by public transport.	Improvements form part of the scheme design, including significant enhancements to pedestrian permeability and connectivity as a result of the proposed public realm improvements.
	Limited existing public realm or attractive space on Euston Road and Hampstead Road	Active frontage and pedestrian-prioritised, landscaped public realm will be provided as part of the proposal. A dedicated cycle entrance and an entrance into the public use space will be provided on Euston Road.
	Providing for the policy-compliant long-stay cycle parking and associated end of trip facilities for cyclists required for a high-density scheme.	861 long-stay and 90 short-stay cycle parking spaces will be provided. High quality cycle parking facilities will be provided. The quantity of long and short stay cycle parking spaces meets the London Plan (2021) standards.
Active Travel and Vision Zero	Five KSIs collisions took place in the vicinity of the Site.	The recently introduced 20mph speed limit on the Euston Road will help to decrease potential KSI incidents
	There are a number of key destinations within a 20-minute cycle ride of the site, including bus stops, London Underground / Overground and National Rail stations and retail. The identified routes show how well connected the site is to the public transport network.	The public realm proposals will enhance the local pedestrian and cycling network. New pedestrian and cycling access points will be created, which will meet the desire lines.
London Wide Network	The development will generate new trips on the transport network, particularly the public transport network, considering it will be car-free.	A detailed review of how and where people will travel has been undertaken, and the impacts of the development on the London-wide network are expected to be negligible. The proposed development is located in an area with excellent access to public transport routes and high-frequency services, which can accommodate the forecast development trips without perceptible impact. An Outline Travel Plan has been provided as part of the planning application, which sets out a range of measures and initiatives aimed at encouraging further use of active travel for users of the Proposed Development.
LB Camden Analysis	The development will add to the existing high footfall around the site, which may affect the pedestrian comfort levels.	A pedestrian comfort level analysis has been undertaken and shows the surrounding footways will provide comfortable pedestrian conditions.
Construction	Full details of the construction timing and methodology will not be known until a contractor is appointed.	An Outline CLP has been included in this TA and a Detailed Construction Logistics Plan will be prepared by a contractor once appointed.



9.1.14 The proposed scheme is consistent with relevant transport policy guidance and is not expected to give rise to any material transport related impacts. It therefore meets the test of the NPPF at paragraph 111 which states that:

“...development should only be prevented or refused on transport grounds where the residual cumulative impacts of development are severe.”

9.1.15 This Transport Assessment has demonstrated that the Proposed Development will prioritise active and sustainable travel, have a negligible impact on the London-wide public transport and highways networks, and will contribute localised improvements to the site and its surroundings. It is concluded that the planning application proposal is acceptable in traffic and transport terms.

